



Agile Product Lifecycle Management

Product Collaboration User Guide

v9.2.2.5

Part No. E12815-01

August 2008

Copyright and Trademarks

Copyright © 1995, 2008, Oracle. All rights reserved.

The Programs (which both the software and documentation) contain proprietary information; they are provided under a license agreement containing restrictions on use and disclosure and are also protected by copyright, patent, and other intellectual and industrial property laws. Reverse engineering, disassembly, or decompilation of the Programs, except to the extent required to obtain interoperability with other independently created software or as specified by law, is prohibited.

The information contained in this document is subject to change without notice. If you find any problems in the documentation, please report them to us in writing. This document is not warranted to be error-free. Except as may be expressly permitted in your license agreement for these Programs, no part of these Programs may be reproduced or transmitted in any form or by any means, electronic or mechanical, for any purpose.

Oracle Data Integrator can be used for initial Oracle Agile PLM source to Oracle Agile PLM Data Mart target synchronizations. Oracle Data Integrator can be used for subsequent bulk loads and batch data transfers from Oracle Agile PLM source to Oracle Agile PLM Data Mart target.

If the Programs are delivered to the United States Government or anyone licensing or using the Programs on behalf of the United States Government, the following notice is applicable:

U.S. GOVERNMENT RIGHTS Programs, software, databases, and related documentation and technical data delivered to U.S. Government customers are "commercial computer software" or "commercial technical data" pursuant to the applicable Federal Acquisition Regulation and agency-specific supplemental regulations. As such, use, duplication, disclosure, modification, and adaptation of the Programs, including documentation and technical data, shall be subject to the licensing restrictions set forth in the applicable Oracle license agreement, and, to the extent applicable, the additional rights set forth in FAR 52.227-19, Commercial Computer Software--Restricted Rights (June 1987). Oracle USA, Inc., 500 Oracle Parkway, Redwood City, CA 94065.

The Programs are not intended for use in any nuclear, aviation, mass transit, medical, or other inherently dangerous applications. It shall be the licensee's responsibility to take all appropriate fail-safe, backup, redundancy and other measures to ensure the safe use of such applications if the Programs are used for such purposes, and we disclaim liability for any damages caused by such use of the Programs.

Oracle and Agile are registered trademarks of Oracle Corporation and/or its affiliates. Other names may be trademarks of their respective owners.

The Programs may provide links to Web sites and access to content, products, and services from third parties. Oracle is not responsible for the availability of, or any content provided on, third-party Web sites. You bear all risks associated with the use of such content. If you choose to purchase any products or services from a third party, the relationship is directly between you and the third party. Oracle is not responsible for: (a) the quality of third-party products or services; or (b) fulfilling any of the terms of the agreement with the third party, including delivery of products or services and warranty obligations related to purchased products or services. Oracle is not responsible for any loss or damage of any sort that you may incur from dealing with any third party.

CONTENTS

Copyright and Trademarks	ii
Items	1
Item Objects	1
Lifecycle Phase	3
Title Block Tab	3
Changes Tab	5
BOM Tab	5
Manufacturers Tab	9
Sites Tab	10
Prices Tab	10
Quality Tab	10
Compliance Tab	10
Suppliers Tab	11
Relationships Tab	11
Attachments Tab	11
History Tab	12
Working with Item Revisions	13
Viewing a Different Revision	13
Introductory Revisions	13
Blank Revisions	14
How the Revision List Works	14
Revisions and Attachment Capabilities	15
How Rev and Site Lists are Determined	16
Working with Pending Revisions	16
Attachments on Pending Revisions	16
Creating Agile Items	18
Creating Items in Java Client	18
Creating Items in Web Client	19
Creating an Item Using Save As	20
Creating an Item Using Add	21
Deleting Agile Objects	23
Soft-Deleting an Object	25

Undeleting an Object	25
Hard-Deleting an Object	25
Editing Agile Items	26
Editing an Unreleased Item	26
Editing a Released Item	27
Changing an Item's Subclass	28
Releasing an Agile Item to Production	28
Unreleasing an Item	29
Incorporating and Unincorporating Items	29
Overview of File Folders and Item Attachments	30
Overview of Incorporation	30
Pre-incorporating an Item	31
Incorporating an Item	31
Unincorporating an Item	31
Where Used Tab	32
Sites and the Where Used Tab	32
Printing Item Tabs	33
Sites and Distributed Manufacturing	35
What is Agile Distributed Manufacturing?	35
What Are Sites?	37
How Sites Can Be Used	38
Different AMLs at Each Site	38
Different BOMs at Each Site	38
Different Effectivity Dates and Dispositions at Each Site	39
How Sites Work	39
Site Information on BOMs and AMLs	39
Sites Tab of Items	39
Changes and Sites	40
Controlling Access to Sites	40
Common BOM/AML Sections	40
Where Sites Are Documented	40
Site Objects	41
General Info Tab - Sites	42
Attachments Tab	44
History Tab	44
Creating Sites	45
Creating Manufacturing Sites	45
Creating a Site Using the Save As Feature	46
Associating a Site with an Item	46

Fields on the Sites Tab	46
Adding Sites to the Sites Tab	47
Removing Sites from the Sites Tab	48
Deleting Site Objects	48
Editing Sites	48
Printing Sites	49
Manufacturing Objects	51
What Is Agile AML?	51
What Does Agile AML Do?	51
About Manufacturing Objects	52
Many-to-One Relationships in Agile AML	52
Sites and AML Data	53
Setting Up Manufacturing Data	53
Manufacturing Objects: Manufacturers and Manufacturer Parts	54
Manufacturing Object Tabs	54
About Manufacturers	56
About Manufacturer Parts	57
Creating and Managing Manufacturing Objects	58
Creating Manufacturers	58
Creating a Manufacturer Using the Save As Feature	59
Creating Manufacturer Parts	60
Creating a Manufacturer Part Using the Save As Feature	64
Modifying Manufacturing Objects	66
Deleting Manufacturing Objects	66
Manufacturers Tab of an Item	67
Manufacturers Tab Buttons	67
Manufacturers Tab Fields	67
Viewing AML Information by Site	68
Associating a Manufacturer Part with Its Corresponding Item	68
Important Considerations When Working with Manufacturing Objects	69
Working with Manufacturing Data on Preliminary Items	69
Adding a Manufacturer Part to the Manufacturers Tab	69
Deleting a Manufacturer Part from the Manufacturers Tab	71
Modifying a Manufacturer Part on the Manufacturers Tab	71
Modifying Manufacturing Data from the Redlines Tab	72
Overview of Redlining Manufacturing Data	72

Redline Manufacturers Tab	72
Adding a Manufacturer Part on the Redline Manufacturers Tab	74
Adding Nonexistent Manufacturer Parts on the Redlines Tab	74
Deleting a Manufacturer Part from the Redlines Tab	74
Editing Manufacturer Part Information on the Redline Manufacturers Tab	74
Undoing Changes to the Redline Manufacturers Tab	76
Printing Manufacturing Objects and AMLs	76
Bills of Material	77
About Bills of Material	77
BOM Tab	77
How the Agile Administrator Controls What You See	78
BOM Tab Buttons	78
BOM Table Fields	80
Common and Site-specific Portions of the BOM	81
Viewing BOMs by Site	82
Opening Items on a BOM	82
Opening a Part, Assembly, or Document from the BOM Tab	83
Expanding and Collapsing an Assembly	83
Using BOM Go To	84
Revisions Listed on BOMs	86
BOMs of Items Affected by an ECO	86
About Modifying the BOM Table	86
Modifying Site-Specific Portions of the BOM of a Preliminary Item	87
Adding Items to the BOM Table of a Preliminary Item	87
Modifying the BOM Table of a Preliminary Item	95
Removing Items from the BOM Table	96
Working with Reference Designators	96
Viewing Reference Designators	96
Adding Reference Designators	98
Deleting Reference Designators	103
Modifying Reference Designators	103
Redlining the BOM of a Released Item	104
Overview of BOM Redlining	105
Redline BOM Tab	105
Adding an Item to a Redline BOM Table	107
Removing an Item from a Redline BOM Table	108
Editing Item Information on a Redline BOM Table	108
Undoing Changes to a Redline BOM Table	109
Printing BOM Data	110

Changes.....	111
Change Classes	111
Change Subclasses	111
Change Objects.....	112
Cover Page Tab	113
Affected Items Tab	116
Workflow Tab.....	117
Relationships Tab.....	119
Attachments Tab	120
History Tab	120
Workflow Routings Inbox.....	122
Changes and Manufacturing Sites	122
Site Information Affected by Changes.....	123
Sites and ECOs.....	123
Sites and MCOs	124
Site Change Orders.....	124
The Relationship of Changes to Item Revisions	125
Creating Changes.....	126
Site Change Order Save As Limitations.....	126
Modifying Changes.....	126
Agile Change Control Workflows.....	127
Redlining through ECOs, MCOs, and SCOs.....	127
Redlining through ECOs.....	128
Redlining through MCOs	128
Redlining through SCOs.....	128
Deleting Changes	128
Undeleting Changes	128
Printing Change Tabs.....	129
Routing Managers: Change Analyst and Component Engineer	129
Affected Items of Changes.....	131
Affected Items Tab	131
Buttons on the Affected Items Tab	132
Fields on the Affected Items Tab.....	133
Affected Items by Manufacturing Site.....	138
Fields That Allow Site-Specific Values	138
Site-Specific Effectivity and Obsolete Dates	138

Viewing the Disposition of Parts in an ECO or SCO	139
Adding an Item to the Affected Items Tab	139
Using the Add Affected Items Wizard	139
Performing Bulk Changes	140
Working with the Affected Items Table	147
Special Considerations for ECOs	147
Special Considerations for MCOs	148
Special Considerations for SCOs	149
Special Considerations for ECRs	150
Special Considerations for Deviations	150
Special Considerations for Stop Ships	151
Removing an Item from the Affected Items Tab	151
Editing Rows in the Affected Items Tab	152
Editing Affected Items Tab Rows in Java Client	152
Editing Affected Items Tab Rows in Web Client	154
Viewing the Redlines of an Affected Item	155
Working with Product Reports and Process Reports	157
About Agile Reports	157
Oracle BI Publisher Report Options	157
About Product Reports and Process Reports	158
Accessing Product Reports and Process Reports	158
Agile Products Reports	159
Assembly Cost (Item Master) Report	160
BOM Comparison Report	161
BOM Explosion Report	163
Consolidated BOM Report	165
Effective BOM Explosion Report	166
Item Activity Report	168
Item Manufacturers Report	169
Manufacturer BOM Report	170
Where Used Report	172
Agile Process Reports	173
Change Activity Report	174
Change Backlog Report	175
Change Cycle Time Report	177
Change Metrics Report	178
Change Package Report	179
IP Transfer Report	181

Help For Power Users.....	183
Details about Discovery and Read Privileges	183
Displaying Non-viewable Fields.....	184
Part or Document?	184
Changing an Item's Subclass.....	185
About Matching Criteria in Workflows	186
Details About Revision Display on BOMs	187
Quick Access to Agile Objects using Smart Object URLs.....	189
Agile-Generated Quick Access Object URLs	189
Formats for User-Generated Smart Object URLs	189
Using Quick Access Object URLs	190

Preface

The Oracle|Agile documentation set includes Adobe® Acrobat™ PDF files. The [Oracle Technology Network \(OTN\) Web site](http://www.oracle.com/technology/documentation/agile.html) <http://www.oracle.com/technology/documentation/agile.html> contains the latest versions of the Oracle|Agile PLM PDF files. You can view or download these manuals from the Web site, or you can ask your Agile administrator if there is an Oracle|Agile Documentation folder available on your network from which you can access the Oracle|Agile documentation (PDF) files.

Note To read the PDF files, you must use the free Adobe Acrobat Reader™ version 7.0 or later. This program can be downloaded from the [Adobe Web site](http://www.adobe.com) <http://www.adobe.com>.

The [Oracle Technology Network \(OTN\) Web site](http://www.oracle.com/technology/documentation/agile.html) <http://www.oracle.com/technology/documentation/agile.html> can be accessed through Help > Manuals in both the Agile Web Client and the Agile Java Client. If you need additional assistance or information, please contact [support](http://www.oracle.com/agile/support.html) <http://www.oracle.com/agile/support.html> (<http://www.oracle.com/agile/support.html>) for assistance.

Note Before calling Agile Support about a problem with an Oracle|Agile PLM manual, please have the full part number, which is located on the title page.

TTY Access to Oracle Support Services

Oracle provides dedicated Text Telephone (TTY) access to Oracle Support Services within the United States of America 24 hours a day, 7 days a week. For TTY support, call 800.446.2398. Outside the United States, call +1.407.458.2479.

Readme

Any last-minute information about Oracle|Agile PLM can be found in the Readme file on the [Oracle Technology Network \(OTN\) Web site](http://www.oracle.com/technology/documentation/agile.html) <http://www.oracle.com/technology/documentation/agile.html>

.

Agile Training Aids

Go to the [Oracle University Web page](http://www.oracle.com/education/chooser/selectcountry_new.html)

http://www.oracle.com/education/chooser/selectcountry_new.html for more information on Agile Training offerings.

Accessibility of Code Examples in Documentation

Screen readers may not always correctly read the code examples in this document. The conventions for writing code require that closing braces should appear on an otherwise empty line; however, some screen readers may not always read a line of text that consists solely of a bracket or brace.

Accessibility of Links to External Web Sites in Documentation

This documentation may contain links to Web sites of other companies or organizations that Oracle does not own or control. Oracle neither evaluates nor makes any representations regarding the accessibility of these Web sites.

This chapter includes the following:

▪ Item Objects.....	1
▪ Working with Item Revisions.....	13
▪ Creating Agile Items	18
▪ Deleting Agile Objects	23
▪ Editing Agile Items	26
▪ Releasing an Agile Item to Production.....	28
▪ Incorporating and Unincorporating Items.....	29
▪ Where Used Tab.....	32
▪ Printing Item Tabs.....	33

Item Objects

Items can be parts or documents. In general, if the document is shipped as part of a product, or it has costs associated with it, create it as a part object. If the document is an internal document, procedure, or reference, create it as a document object. (In some cases, you may want to create a document as a part. For examples, see [Part or Document?](#) (on page 184))

This section includes the following topics:

- [Lifecycle Phase](#) (on page 3)
- [Title Block Tab](#) (on page 3)
- [Changes Tab](#) (on page 5)
- [BOM Tab](#) (on page 5)
- [Manufacturers Tab](#) (on page 9)
- [Sites Tab](#) (on page 10)
- [Prices Tab](#) (on page 10)
- [Quality Tab](#) (on page 10)
- [Compliance Tab](#) (on page 10)
- [Suppliers Tab](#) (on page 11)
- [Relationships Tab](#) (on page 11)
- [Where Used Tab](#) (on page 32)
- [Attachments Tab](#) (on page 11)
- [History Tab](#) (on page 12)

To locate and open an item, follow the instructions in *Getting Started with Agile PLM*.

When you view an item in Java Client, information about it is displayed on tabs in an item window.

When you view an item in Web Client, information about it is displayed on tabs in the right pane.

The following table lists the items tabs.

The Agile administrator may have added additional tabs or sections, called Page Two and Page Three by default. These tabs or sections contain custom fields defined by the administrator.

Item tab name	Tab information includes
Title Block Tab (on page 3)	General information about the item, unique class and subclass fields defined by the Agile administrator
Changes Tab (on page 5)	Any pending or released changes against the item
BOM Tab (on page 5)	The item's bill of material
Manufacturers Tab (on page 9)	Manufacturer and manufacturer parts information about sources for that part
Sites Tab (on page 10)	The manufacturing sites that use the item
Prices Tab (on page 10)	Prices associated with the item. For more information about Product Cost Management (PCM), see the <i>Product Cost Management User Guide</i> .
Quality Tab (on page 10)	Information about Product Quality Management (PQM) objects associated with this item. Product Service Requests (PSRs) are problem reports or non-conformance reports about this item. For more information about PQM, see the <i>Agile Product Quality Management User Guide</i> .
Compliance Tab (on page 10)	Information about the compliance to material regulations related to the item. For more information about Product Governance & Compliance (PG&C), see the <i>Agile Product Governance and Compliance User Guide</i> . Note: The Compliance tab is visible in Web Client only. Agile PG&C is a Web Client-based solution.
Suppliers Tab (on page 11)	Information about the approved suppliers for the item. This tab is used in both the PG&C and PCM solutions. For more information about PG&C, see the <i>Agile Product Governance and Compliance User Guide</i> . For more information about PCM, see the <i>Product Cost Management User Guide</i> . Note: The Supplier tab is visible in Web Client only. Agile PG&C and Agile PCM are Web Client-based solutions.

Item tab name	Tab information includes
Relationships Tab (on page 11)	The Relationships tab allows you to create relationships with other Agile objects and to create dependencies between the current item object and other routable objects. For more information about relationships, see the chapter about working with business objects in <i>Getting Started with Agile PLM</i> .
Where Used Tab (on page 32)	Where the item is used
Attachments Tab (on page 11)	Attached drawings and files
History Tab (on page 12)	Actions taken on the item, for example, when attachments were added and removed

Lifecycle Phase

A lifecycle phase name at the top right of the object window of an item indicates the production lifecycle phase of the item. (The names that you see may differ if the Agile administrator has customized the lifecycle names for your organization.)

The lifecycle phase name also appears in the Lifecycle Phase field on the item Title Block tab. See [Title Block Tab](#) (on page 3).

The following table shows the default lifecycle phases.

Lifecycle phase name	Lifecycle definition
Preliminary	The item has never been released. It may have a pending change against it.
Prototype	The item has been released to be built in very limited quantities for testing.
Pilot	The item has been released to be built in limited initial quantities.
Production	The item has been released for regular production.
Inactive	The item is temporarily not in use but may be reactivated.
Obsolete	This item is no longer in use.

Title Block Tab

The Title Block tab has fields that contain the information found on a typical paper-based title block. Some fields are filled in automatically; you complete the rest. You may not be able to edit the contents of some fields. Your assigned roles and privileges determine which entries you are allowed to edit.

For more information about editing items, see [Editing an Unreleased Item](#) (on page 26) and [Editing a Released Item](#) (on page 27).

For more information about Title Block fields, see [Fields on the Title Block Tab](#) (on page 4).

Fields on the Title Block Tab

By default, the item object Title Block tab contains the fields listed in the following table. Agile administrators determine which fields are enabled and visible on the Title Block tab.

In Web Client, the Title Block can contain two additional sections, called Page Two and Page Three by default. In Java Client, these are separate tabs. Agile administrators can add custom class fields to Page Two section and customer subclass fields to the Page Three section. The Agile administrator determines whether these sections are enabled, and what they are called.

Field	Definition
Number	The item's number. The item number is completed when the item is created. Depending on Agile system settings, the number may be automatically generated or the user may enter a number.
Description	Text that describes the item. By default, descriptions can be up to 240 characters, counting spaces and carriage returns (carriage returns count as two spaces).
Size	Drawing size; select from the list.
Product Line(s)	The product group or groups that include this item; select from the list.
Lifecycle Phase	The lifecycle phase of the item for the displayed revision, for example, Prototype or Production. See Lifecycle Phase (on page 3) for more information.
Rev Incorporate Date	The date an item is incorporated; automatically completed when the item is incorporated.
Rev Release Date	The date an item is released; automatically completed when the item is released.
Part Type	The subclass of this item; completed when the item is created. Depending on Agile system settings, the part type field may be automatically completed or the user may select a part type. See Changing an Item's Subclass (on page 28) for more information.
Part Category	The category that includes the item; select from the list.
Effectivity Date	Displays the date the revision becomes effective. This date is specified on the Affected Items tab of the change that released the revision. See also Site-Specific Effectivity and Obsolete Dates (on page 124).
Shippable Item Exclude from Rollup Compliance Calculated Date Part Family Mass Overall Compliance	These fields are associated with Agile PG&C. For more information about Product Governance & Compliance (PG&C), see the <i>Agile Product Governance and Compliance User Guide</i> . See also <i>Agile Administrator Guide</i> and <i>Getting Started with Agile PLM</i> .

Changes Tab

The item object Changes tab displays a list of changes related to the item you are viewing, displayed in two tables. The information on this tab is filled in automatically. You can sort the tables by clicking the heading of the column by which you want to sort. For example, to sort by description, click the Description column heading.

Note If you do not have Discovery privilege for a change, it does not appear on the Changes tab. You may see a message telling you how many changes are not displayed. For more information, see [Details about Discovery and Read Privileges](#) (on page 183). If you have questions about your Discovery or Read privileges, see the Agile administrator.

The upper table, Pending Changes, shows pending changes, including changes on hold. The lower table, Change History, shows released and canceled changes.

The Site column displays the site entered on the Affected Items tab of the change. If more than one site is listed on the Affected Items tab, then the change is listed once for each site.

Note Although its name is similar, the History tab shows actions made against an item, while the Change History table on the Changes tab lists released and canceled changes for the item.

To open a change listed on the Changes tab:

- In Java Client, double-click the change row.
- In Web Client, click the change number.

The change opens with the Cover Page tab on top.

BOM Tab

The BOM tab lists all the items on an item's bill of material (BOM). For details on the BOM tab, see [Bills of Material](#) (on page 77).

Note If you do not have Discovery privilege for an item, it does not appear on the BOM tab. You may see a message telling you how many items are not displayed. For more information, see [Details about Discovery and Read Privileges](#) (on page 183).

If there are site-specific items on the BOM, common items and site-specific items are grouped together. The common items are listed first; the Sites column is blank for common items. The Sites column of site-specific items displays the associated site name.

Note You can directly edit the BOM table when an item is initially created and before it is added to the Affected Items table of a change. See [Creating a Common BOM](#) (on page 6) and [Creating a Site-Specific BOM](#) (on page 7).

The common section of the BOM lists items that are associated with all the sites where the parent item is associated. The common section of a BOM can be modified through a revision change only.

The site section of the BOM lists items specific to the selected site. The site section of the BOM can be modified through a revision change or an SCO (site change order). For a site to be listed in a section of the BOM, the site must also be associated with the parent item.

Note By assigning a color to each site, you can color code the site section of the BOM tab.

If you want to view all the components for all sites, select ALL from the Site drop-down list.

To open an item listed on the BOM tab:

- In Java Client, double-click the item row. The item opens with the Title Block tab on top.
Or, right-click the item row, choose Open, then choose a tab. The item opens with the selected tab on top.
- In Web Client, click the item number. The item opens with the Title Block tab on top.

Creating a Common BOM

You can directly edit the item object BOM table when an item is initially created and before it is added to the Affected Items table of a change.

To create a common BOM using Java Client:

To add items to the BOM table:

1. On the BOM tab, click the Add drop-down menu button and choose a menu option to add components to the BOM.
2. Depending on your menu selection, do one of the following:
 - Search – Search for one or more existing items. In the Add BOM dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.) In the search results, select the items you want, select Common in Site drop-down list, and click OK. All the items in the Selected Items list are added to the BOM.

Note If the selected items do not have the necessary site association, you are prompted to add the sites to the selected items. When you accept the warning, the selected items are added to the BOM.

Type-in Known Numbers – **enter one or more existing item numbers, select Common in Site drop-down list, and click Add.**

Note You may enter a non-existent number to add a placeholder row. When prompted that the number does not exist, accept the warning to add the placeholder row to the BOM.

- Create – Select a type from the Type drop-down list. If appropriate, enter an object number and complete any required fields. Select Common in Site drop-down list. Click OK. The common sites are automatically added to the newly created item.

Note If you have already selected ALL in the item's Site drop-down list, Common is preselected for you in the Search, Type-in Known Numbers, or Create dialog.

To create a blank row for common BOM using Java Client:

1. Select ALL in the item's Site drop-down list.
2. In the BOM Add menu, select Add Blank Row.

Add Blank Row adds a blank row to the BOM table that can be filled in later.

The Sites column is blank to indicate that the item is associated with all the sites assigned to the BOM.

To create a common BOM using Web Client:

1. On the BOM tab, click the Add button and, in the drop-down menu, choose a menu option to add components to the BOM.
2. Depending on your menu selection, do one of the following:

- **Search** – Search for one or more existing items. In the Add BOM Items dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.) In the search results, select the items you want, select Common in the Add for Site drop-down list, and click OK. All the items in the Selected Items list are added to the BOM.

Note	If any selected items do not have the necessary site association, you are prompted to add the site to the items. When you accept the warning, the selected items are added to the BOM.
------	--

- **Type-in Known Numbers** – enter one or more numbers, select Common in the Add for Site drop-down list, and click Add.

Note	You may enter a non-existent number to add a placeholder row. When prompted that the number does not exist, accept the warning to add the placeholder row to the BOM.
------	---

- **Create New** – Select a type from the Type drop-down list. If appropriate, enter an object number and complete any required fields. Select Common in the Add for Site drop-down list, and click OK. The common sites are automatically added to the newly created item.

Note	If you have already selected ALL in the item's Site drop-down list, Common is preselected for you in the Search, Type-in Known Numbers, or Create New dialog.
------	---

To create a blank row for common BOM using Web Client:

1. Select ALL in the item's Site drop-down list.
2. In the BOM Add menu, select Blank Row.

Blank Row adds a blank row to the BOM table that can be filled in later.

The Sites column is blank to indicate that the item is associated with all the sites assigned to the BOM.

Creating a Site-Specific BOM

You can directly edit the item object BOM table when an item is initially created and before it is added to the Affected Items table of a change.

Note	If the site for which you want to create a site-specific BOM is not on the Site list, you must associate the item with that site through the item's Site tab.
------	---

To create a site-specific BOM using Java Client:

1. Select the site you want in the item's Site drop-down list.

To add items to the BOM table:

1. On the BOM tab, click the Add drop-down menu button and choose a menu option to add components to the BOM.
2. Depending on your menu selection, do one of the following:
 - Search – Search for one or more existing items. In the Add BOM dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.) In the search results, select the items you want, select Common in Site drop-down list, and click OK. All the items in the Selected Items list are added to the BOM.

Note	If the selected items do not have the necessary site association, you are prompted to add the sites to the selected items. When you accept the warning, the selected items are added to the BOM.
------	--

Type-in Known Numbers – **enter one or more numbers and click Add.**

Note	You may enter a non-existent number to add a placeholder row. When prompted that the number does not exist, accept the warning to add the placeholder row to the BOM.
------	---

- Create – Select a type from the Type drop-down list. If appropriate, enter an object number and complete any required fields. Click OK. The site will be automatically associated with the newly created item.

Note	If you have already selected the site you want in the item's Site drop-down list, it is preselected for you in the Search, Type-in Known Numbers, or Create dialog.
------	---

If you selected ALL in the item's Site drop-down list in step 1 above, select the site you want before you complete the dialog.

To create a site-specific blank BOM row using Java Client:

3. Select the site you want in the item's Site drop-down list.
4. In the BOM Add menu, select Add Blank Row.

Add Blank Row adds a blank row to the BOM table that can be filled in later.

The Site column is automatically completed with the site selected from the Site list as the associated site.

To create a site-specific BOM using Web Client:

1. Select the site you want in the item's Site drop-down list.

Note	If you select ALL in the item's Site drop-down list, you can then select any site in the Search, Type-in Known Numbers, or Create dialog in step 3 below.
------	---

2. On the BOM tab, click the Add button and, in the drop-down menu, choose a menu option to add components to the BOM.

3. Depending on your menu selection, do one of the following:
 - Search – Search for one or more existing items. In the Add BOM Items dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.) In the search results, select the items you want, select Common in the Add for Site drop-down list, and click OK. All the items in the Selected Items list are added to the BOM.
4. If any selected items do not have the necessary site association, you are prompted to add the site to the items. When you accept the warning, the selected items are added to the BOM.
 - Type-in Known Numbers – enter one or more numbers and click Add.

Note You may enter a non-existent number to add a placeholder row. When prompted that the number does not exist, accept the warning to add the placeholder row to the BOM.

- Create New– Select a type from the Type drop-down list. If appropriate, enter an object number, and complete any required fields. Click OK. The site will be automatically associated with the newly created item.

Note If you have already selected the site you want in the item's Site drop-down list, it is preselected for you in the Search, Type-in Known Numbers, or Create New dialog.

If you selected ALL in the item's Site drop-down list in step 1 above, select the site you want before you complete the dialog.

To create a site-specific blank BOM row using Web Client:

5. Select the site you want in the item's Site drop-down list.
6. In the BOM Add menu, select Blank Row.

Blank Row adds a blank row to the BOM table that can be filled in later.

The Site column is automatically completed with the site selected from the Site list as the associated site.

Manufacturers Tab

The Manufacturers tab displays the manufacturer parts used for the item, including site-specific manufacturer parts. The information on the tab is derived from associated manufacturing objects. If your company is using Agile AML features, and you have the appropriate privileges, you can use this tab to construct an approved manufacturers list (AML) for the item.

The Manufacturers tab displays, in a sortable table, information about:

- The manufacturers that produce the part
- The manufacturer parts that they supply, including:
 - Whether the manufacturer part is the preferred or an alternate part
 - Whether they are currently an active manufacturer of that part
 - The manufacturer's part number corresponding to the part in Agile PLM.
- The manufacturing site to which the manufacturer part applies (manufacturer parts are listed once per applicable site). The AML Split column on the Manufacturers tab allows you to define

the percent (%) allocated for the AML for the selected site.

Note	If you do not have Discovery privilege for a manufacturer, it does not appear on the Manufacturers tab. You may see a message telling you how many manufacturers are not displayed. For more information, see Details about Discovery and Read Privileges (on page 183).
------	--

Viewing a Manufacturer Part from the Manufacturers Tab

To open a manufacturer part from the item object Manufacturers tab:

- In Java Client, double-click the manufacturer part row.
Or, right-click the manufacturer part row, choose Open, then choose a tab. The manufacturer part opens with the selected tab on top.
- In Web Client, click the manufacturer part number.

Sites Tab

The Sites tab of an item lists all the manufacturing sites that use the item or that have site-specific information that pertains to the item.

To make an item available to site-specific BOMs and AMLs, you must add the appropriate sites to the item's Sites tab. For example, if you want to enable users at the India site to add site-specific information for a part, add India to the part's Sites tab. With the necessary privileges, you can add, edit, and remove information on the Sites tab.

For more information about manufacturing sites, including how to work with the Sites tab, see [Associating a Site with an Item](#) (on page 46).

Prices Tab

The item object Prices tab shows information about the prices associated with the item.

For more information about pricing and the Prices tab, see *Getting Started with Agile PLM* or the *Product Cost Management User Guide*.

Quality Tab

The Quality tab of an item (part or document) lists the product service requests (PSRs) that reference the item. PSRs may include non-conformance reports (NCRs) and problem reports (PRs). The Agile administrator may have defined additional PSR types for your company. This tab is filled in automatically. For more information about the Quality tab and PQM features, see *the Product Quality Management User Guide*.

Compliance Tab

The item object Compliance tab relates to Agile PG&C and lists the compliance declarations associated with the item. For more information, see *Agile Product Governance and Compliance User Guide*.

Note The Compliance tab is visible in Web Client only. Agile PG&C is a Web Client-based solution.

Suppliers Tab

This item object Suppliers tab relates to Agile PG&C and lets you associate suppliers with the item. For more information, see *Agile Product Governance and Compliance User Guide*.

Note The Supplier tab is visible in Web Client only. Agile PG&C is a Web Client-based solution.

Relationships Tab

The item object Relationships tab allows you to create relationships with other business objects, both lifecycle objects and routable objects. If the related object is a routable object, you can specify a rule for the relationship, thus creating a dependency between the current item and the routable object. A relationship with a rule indicates a routable object whose workflow progression is affected by the lifecycle phase of the current item object.

A relationship with no specified rule does not limit or affect the workflow progression of the related routable object. You can use non-rule relationships to record objects that are somehow related to the current item, but do not have any dependencies with the current item.

Note You cannot specify a rule for an item relationship with another lifecycle phase (non-routable) object.

For more information about relationships and how to use this tab, see the chapter about working with business objects in *Getting Started with Agile PLM*.

Attachments Tab

All objects have an Attachments tab. On the Attachments tab, you can attach files and URLs to the object by referencing those files and URLs in a file folder object. On the Attachments tab, you can view, copy (get), or print attached files if you have the appropriate privileges.

Individual attached files are stored in file folder objects and can be attached to multiple objects. The files in a file folder object can be drawings or scanned images, documents, non-viewable files, compressed files, and so on.




For detailed information about working with file folder objects and the Attachments tab, see *Getting Started with Agile PLM*.

You cannot make modifications to the Attachments tab of incorporated items. For more information about incorporated items, see [Incorporating and Unincorporating Items](#) (on page 29).


Attachment tab operations (add, remove, edit) for items are revision-based. Attachments are added to or deleted from a specific ECO-created revision of the item, such as Rev A, Rev B, and so on. ECO-created item revisions have attachment capabilities. MCOs and SCOs are based on a particular item revision, but have no revision of their own, and therefore do not have attachment capabilities. For more information about item revisions and attachments, see [Revisions and Attachment Capabilities](#) (on page 15).

Note	Attachments apply to all manufacturing sites of an item; there are no site-specific attachments.
------	--

Common Attachments tab operations in Java Client include:

- View a file in Viewer – select a row in the Attachments table and click the View Files button .
- View a file in its native application – select a row in the Attachments table and click the Open Files button .
- Get a local copy of a file – select a row in the Attachments table and click the Get Files button .

Common Attachments tab operations in Web Client include:

- View file in Viewer – click its filename link. If the attached file is *not* viewable with Viewer, it opens in the native application, if it is installed on your computer.
- Get a local copy of a file – in the file's row, click the Get button .

History Tab

The History tab shows a summary of actions taken against an object, including a description of the action, which user took the action, the date of the action, and other details.

Note	If you do not have the appropriate Read privilege for an object, you cannot see the contents of the fields on the History tab. See Details about Discovery and Read Privileges (on page 183).
------	---

The types of actions recorded for items are:

- Creation of the item
- Attachment actions: view, open, add, delete, get, check in, check out, cancel checkout, incorporate, unincorporate, and field modifications on the Attachments tab.
- Save As
- Send
- Print
- Modification of the subclass or any field of a released item
- Subscription modification and sharing

Field modifications for preliminary items that have not been released are recorded for modifications to the Relationships tab and Attachments tab only; other field modifications to preliminary items are not recorded.

For modifications to released items, the revision information is included in the history table row in the Rev column.

Working with Item Revisions

The Site and Rev fields above the item tabs let you display item information based on manufacturing site and revision.

When you open an item, the Rev field displays the latest released version.

Note When you open the item from the Affected Items tab of a change order, the revision associated with that change order is displayed.

This section includes the following topics

- [Viewing a Different Revision](#) (on page 13)
- [Introductory Revisions](#) (on page 13)
- [Blank Revisions](#) (on page 14)
- [How the Revision List Works](#) (on page 14)
- [How Rev and Site Lists are Determined](#) (on page 16)
- [Working with Pending Revisions](#) (on page 16)
- [Attachments on Pending Revisions](#) (on page 16)

Viewing a Different Revision

To view a different revision:

1. If you want to see a revision that pertains to a specific manufacturing site, select that site from the Site drop-down list.

Note When you select ALL from the Site drop-down list, the default value in the Rev list is the latest released change for that item.

2. Select a revision from the Rev drop-down list above the tabs. When you select a revision, the corresponding effectivity date is displayed.

When you select a different revision, *all* the tabs display information from the selected revision. For example, if the BOM tab is displayed, and you switch from revision C to revision B, the other tabs also show revision B.

Note Not all tabs are revision-specific; for example, the Where Used tab and the History tab are not revision-specific. When you view tabs that are not revision-specific, the Rev drop-down list is disabled.

Introductory Revisions

The initial revision of an item—that is, the revision of a newly created, unreleased item—is labeled *Introductory*. Introductory revisions have no changes against them, and they are not assigned a revision letter. When an item is in the Introductory stage, it is not under change control and can therefore be modified directly.

Introductory revisions are treated the same as released revisions; they are considered the base revision by Where Used and Object searches, the Where Used tab, changes, and the Save As

feature.

Introductory appears in the Rev drop-down list at the bottom of the list because it is the earliest revision. It is the only revision on the list that is not associated with a change.

See also: [How the Revision List Works](#) (on page 14)

Blank Revisions

You may see revisions in the list that are not *Introductory* and that do not have an assigned revision letter. These are referred to as *blank revisions*.

Blank revisions occur when an MCO is released against an item before an ECO releases the item. That releasing MCO creates a blank revision, as do any subsequent changes that occur before a new ECO revision is created. The Rev list displays the number of the MCO instead of a revision letter. The following is an example of a Rev list that includes a blank revision created by MCO M00001.

```
(A)  C00004
      M00001
Introductory
```

How the Revision List Works

As stated above, a revision labeled *Introductory* in the Rev list indicates the initial revision of the object, with no pending changes. Once the object is listed on a change, a letter sequence of revisions is started.

For released revisions, the number of the releasing ECO is displayed next to its corresponding revision. (Remember, an item can be revised only by an ECO.) For example, for a part, if ECO E54321 resulted in the release of revision C, then revision C in the Rev drop-down list reads

```
C    E54321
```

A revision number or letter inside parentheses indicates that the revision is pending, not yet released:

```
(A)  C00004
```

You may see revisions in the list that are not *Introductory* and that do not have an assigned revision letter. These are referred to as *blank revisions*.

Blank revisions occur when an MCO is released against an item before an ECO releases the item. That releasing MCO creates a blank revision, as do any subsequent changes that occur before a new ECO revision is created. The Rev list displays the number of the MCO instead of a revision letter:

```
M00001
```

MCOs and SCOs are based on item revisions, but neither can create a new revision of a part, and, therefore, neither has attachment capabilities. MCO and SCO modifications, which you can select in the Rev drop-down list, inherit the attachments of the ECO-created revision or the *Introductory* revision upon which they are based.

The MCO or SCO number is displayed next to the corresponding revision on the Rev drop-down list. For example, if there is a pending MCO M12345 against Rev B of a part, then on the Rev drop-down list, that revision is listed as "(B) M12345."

Revisions and Attachment Capabilities

Item attachment operations (add, remove, edit) are revision-based. Attachments can be added to or deleted from only an ECO-created revision or an Introductory revision. MCOs and SCO are based on an item revision, but have no revision of their own, and therefore do not have attachment capabilities. MCO and SCO modifications, which you can select in the Rev drop-down list, inherit the attachments of the ECO-created revision or the Introductory revision upon which they are based.

Note If the ECO-created revision or the Introductory revision is incorporated, you will not be able to add or remove attachments and you will not be able to edit the attachments table. For more information about item incorporation, see [Incorporating and Unincorporating Items](#) (on page 29),

See also [Attachments Tab](#) (on page 11). For detailed information about attachments and file folders, see the chapter about working with attachment files in *Getting Started with Agile PLM*. For information about ECO-redlining attachment files, see *Agile Viewer Addendum*.

The following tables illustrate attachment capabilities (add, remove, edit) for different entries on the item Rev drop-down list.

Rev list entry	Attachment capabilities
(C) ECO-356	Yes, has attachment capabilities, because it is a pending ECO-created Rev.
B SCO-444	No attachment capabilities; it is based on Rev B and inherits Rev B's attachments.
B ECO-233	Yes, has attachment capabilities, because it is an ECO-created Rev.
A MCO-888	No attachment capabilities; it is based on Rev A and inherits Rev A's attachments.
A ECO-222	Yes, has attachment capabilities, because it is an ECO-created Rev.
INTRODUCTORY	Yes, has attachment capabilities, because it is an introductory revision. Introductory revisions have the same features as an ECO-created revision. See Introductory Revisions (on page 13).

Rev list entry	Attachment capabilities
(B) MCO-934	No attachment capabilities; pending MCO based on Rev B and inherits Rev B's attachments.
B ECO-572	Yes, has attachment capabilities, because it is an ECO-created Rev.
A SCO-444	No attachment capabilities; it is based on Rev A and inherits Rev A's attachments.
A MCO-788	No attachment capabilities; it is based on Rev A and inherits Rev A's attachments.
A ECO-333	Yes, has attachment capabilities, because it is an ECO-created Rev.
MCO-766	No attachment capabilities; it is based on the Introductory revision and inherits the Introductory revision's attachments.
INTRODUCTORY	Yes, has attachment capabilities, because it is an introductory revision. Introductory revisions have the same features as an ECO-created revision. See Introductory Revisions (on page 13).

How Rev and Site Lists are Determined

All revisions are shown to all users regardless of their default site or site access. However, when you open an item, the Rev drop-down list is set to the last change for your default site.

An item's default revision shown is based on your default site. Even if you select a different site from the Site drop-down list, the default revision still reflects what you see from your default site.

Working with Pending Revisions

You can create a pending revision of an item. When you create an ECO against an item, the ECO creates a pending revision of that item. Pending revisions let you modify the item under change control, including redline modifying its BOM table and Manufacturers table. You can also create pending revision attachment markups.

A pending revision can be identified by the parentheses around the revision number in the Rev field, for example, (A).

For information about incorporating pending revisions of items, see [Incorporating and Unincorporating Items](#) (on page 29).

Attachments on Pending Revisions

By default, when a pending revision is created, it inherits the same list of attached files that are attached to the current default revision. If any files are then either added to or removed from the current default revision, those modifications are not reflected on the Attachments tab of the pending revision. For additional information about attachments and item revision levels, see *Getting Started with Agile PLM*.

See also: [Removing an Item from the Affected Items Tab](#) (on page 151).

Effects of CopyFilesToRev SmartRule

The CopyFilesToRev (Copy Files to Rev) SmartRule setting determines how pending revision item attachments are created or referenced. The Agile administrator sets the Agile PLM system to either copy, copy with warning, reference, reference with warning or disallow the list of attachments to be copied to a new pending revision.

When you add an item to the Affected Items table of a pending ECO, you create a pending revision of an item. Depending on the Agile PLM Copy Files to Rev SmartRule setting, pending revision attachments are processed as followed:

- Copy - For the item's new pending revision, Agile creates a new file folder and creates a new copy of the attachment file, which is placed in the new file folder.
- Reference - Agile uses the existing file folder and creates a new reference to it on the item's new pending revision Attachments tab.
- Disallow - The new item pending revision is created with no attachments.
- Copy with Warning - The same as the Copy setting, with the option of choosing no attachments for the new pending revision.

When you add items to the pending ECO, you are presented with a warning dialog that

includes a row for each item you are adding.

- To add the item and to copy the attachments, check both the Add checkbox and the Attachments checkbox.
 - To add the item with no attachments, check only the Add checkbox.
- Reference with Warning - The same as the Reference setting, with the option of choosing no attachments for the new pending revision.

When you add items to the pending ECO, you are presented with a warning dialog that includes a row for each item you are adding.

- To add the item and to reference the existing attachments, check both the Add checkbox and the Attachments checkbox.
- To add the item with no attachments, check only the Add checkbox.

When this SmartRule is set to Reference or Reference with Warning, if there are multiple versions of any attachment file, only the reference to the latest version is used for the new reference on the pending revision.

For example, if you create an ECO against Part 456, Rev C (thus creating a pending Rev D), all the attachment files that are attached to Rev C are also attached to pending Rev D. (The file and file folder references on the Attachments tab of released Rev C are duplicated on the Attachments tab of pending Rev D.) Any attachment files that are added to the Attachments tab of Rev C, or any other Rev C Attachments tab modifications (for example, modifying the file folder version numbers) after the creation of the ECO are *not* copied to pending Rev D.

Note	Attachment files that are added to the Introductory revision after the object is associated with a change (that will result in released Rev A) will not be copied to subsequent revs. This SmartRule does not affect MCO or SCO revisions because MCOs and SCOs do not create separate new revisions.
------	---

Creating a Pending Revision

Writing a pending ECO against an item creates a pending revision of the item. A pending revision can be identified by the parentheses around the revision number in the Rev field, for example, (A).

To create a pending revision:

1. Create the item.
2. Create an ECO.
3. Place the item on the Affected Items tab of the change.
4. Give the affected item a revision number.

Note	SCOs are for site-specific changes only; they do not affect common site information, and they do not roll the revision number. SCOs cannot be used to create a pending revision of a newly created item that has never been released.
------	---

For information about creating changes, see [Changes](#) (on page 111).

Modifying Pending Revisions



You modify pending revisions the same way you modify other objects. Because modifying a pending revision could affect a released revision, you must have the appropriate privileges to


modify the Title Block, Page Two, and Page Three fields. If you have privileges to modify preliminary items, you can modify fields on the pending revisions of items. If you have privileges to modify released items only (and you do not have privileges to modify preliminary items), you cannot modify fields on the pending revisions of items. If you have questions about your assigned modify privileges, see the Agile administrator.

See also: [Editing a Released Item](#) (on page 27).

Creating Agile Items

To create an item, you must have the Create Item privilege.

In Java Client, you can create an item with the File | New | Item command, the New Object button , or the Save As command, on the More Actions menu (click the More button  at the top of the object window) and on the right-click shortcut menu.

In Web Client, you can create an item with the Create | Items command  or the Actions | Save As command.

You can also create an item as you add it to the BOM tab of a parent item or the Affected Items tab of a change.

This section contains the following topics:

- [Creating Items in Java Client](#) (on page 18)
- [Creating Items in Web Client](#) (on page 19)
- [Creating an Item Using Save As](#) (on page 20)
- [Creating an Item Using Add](#) (on page 21)

The initial revision of an item—that is, the revision of a newly created, unreleased item—is labeled *Introductory*. For more information about Introductory revisions, see [Introductory Revisions](#) (on page 13).


Once you create an item, that item exists until you delete it. If you create a new item, then decide you do not wish to keep it, be sure to delete the item; otherwise, the new item is still in the database, and the number cannot be reused. See [Deleting Agile Objects](#) (on page 23).

Creating Items in Java Client

The process for creating new objects involves two main steps: creating an empty object, then filling in the object tabs with information specific to the object.

To create and complete an item in Java Client:

1. Using the File menu, choose the object class you want to create. For example:
File | New | Items | Parts
File | New | Items | Documents
2. In the New dialog box, use the Type drop-down list to select the type (subclass) of item you want to create.





3. Assign a number to the item. To do so, either accept the number that appears, click the Autonumber button  to use the next autonumber, or type a number.
If more than one autonumber format can be used, the available autonumber formats appear in a list when you click the Autonumber button. Select the autonumber format you want.
The autonumber format and sequence are determined by the Agile administrator. The Agile administrator also determines whether using autonumbers is required or optional.
4. Complete any required fields.
5. Click OK.
The new item appears with the Title Block tab showing.
6. Fill in information on the item tabs, as desired.
You do not enter information on the Changes, Where Used, or History tabs. Those tabs are completed automatically.


See also: [Creating Items in Web Client](#) (on page 19), [Creating an Item Using Save As](#) (on page 20), [Creating an Item Using Add](#) (on page 21).

Creating Items in Web Client

A wizard leads you through the process of creating an item and specifying the BOM, manufacturing sites, manufacturers, and attachments.

To create and complete an item in Web Client:

1. Using the Create menu, choose the object class you want to create. For example:
Create | Items | Parts
Create | Items | Documents
2. In the Create dialog box, use the Type drop-down list to select the type (subclass) of item you want to create.
3. Assign a number to the item. To do so, either accept the number that appears, click the Autonumber button  to use the next autonumber, or type a number.
When you click the AutoNumber button  to enter the item number, you might see a list of autonumber choices. The autonumber format and sequence are determined by the Agile administrator. The Agile administrator also determines whether using autonumbers is required or optional.
4. To continue using the Create wizard to enter information on each tab of the item, check the Continue Creation in  Wizard checkbox, and click the Continue button. Follow the onscreen instructions to complete the wizard.
5. To create and display the item immediately, uncheck the Continue Creation in  Wizard checkbox and click Finish. The new item appears with the Title Block tab showing. Fill in information on the item tabs, as desired.

Note Agile PLM remembers your most recent selection for the Continue Creation in  Wizard checkbox in any create dialog and it remains preselected for you in the Create dialog box.

You do not enter information on the Changes, Where Used, or History tabs. Those tabs are

completed automatically.

See also: [Creating Items in Java Client](#) (on page 18), [Creating an Item Using Save As](#) (on page 20), [Creating an Item Using Add](#) (on page 21).

Creating an Item Using Save As

Using the Save As feature is a quick way to create an item that is similar to an existing item.

For site-specific items, the original item's manufacturing sites are copied to the new item, as are all components and manufacturer parts on the common and site-specific portions of the BOM and Manufacturers tabs. (Sites for which you do not have privileges are not copied.) If you select a specific site in the Site drop-down list and Save As, only the selected site's data will be copied to the newly created item.

Caution In general, you should not use Save As to create an object in a different class or subclass (type) from the original object. The different classes or subclasses may not have the same tabs or defined fields, and you may lose access to some data in the newly created object.

For example, parts generally have a BOM tab. By default, documents do not. When you save a part as a document, you cannot view the part's BOM in the resulting document unless the Agile administrator has configured your system to permit documents to have BOMs.

Note	If you do not have Discovery privilege for any of the items on the BOM list of the existing item, you can use Save As to create a new item, which includes the BOM list items that you cannot discover. You also will not be able to discover those BOM list items on the newly created item.
-------------	---

If the Agile administrator has set the appropriate attributes, fields in the optional Page Two and Page Three sections are copied to the new item. For information about the behavior of Page Two and Page Three fields in your Agile PLM system, see the Agile administrator.

If the item has one or more attachments, the attachments for the new item are created using the method specified by the Agile administrator in Agile system preferences:


- Create new copy of file(s) — Agile creates a new file folder and creates a new copy of the attachment file, which is placed in the new file folder.
- Reference existing file(s) — Agile uses the existing file folder and creates a new reference to it on the new item's Attachments tab.
- Do not copy file(s) — The new item is created with no attachments.
- Prompt — You are prompted to select one of the above three methods. If the item has no attachments, no prompt appears.

Save As copies data from a field in the existing object to the same field in the new object. If a field or list value in the existing object is not available in the new object, then that field or list value is not copied to the new object.

For items using sites:

- The new item has only the default site associated with it (that is, the site selected in the Sites drop-down list when you performed the Save As action), even if the original item had multiple sites. If the new item needs additional sites, you must add sites to the new item manually.

- If you select All from the Site drop-down list of the original item and then perform a Save As action, all the sites from the original item are copied to the new item.
- If the original item does not have a default site, after the Save As action, the resulting new item also does not have a default site.

In Java Client, you can create an item using the File | Save As command or the Save As command on the More Actions menu (click the More button  at the top of the object window) and on the right-click shortcut menu.

In Web Client, you can create an item using the Actions | Save As command.

For more information about creating items or other objects using Save As, see *Getting Started with Agile PLM*.

See also: [Creating Items in Java Client](#) (on page 18), [Creating Items in Web Client](#) (on page 19), [Creating an Item Using Add](#) (on page 21).


Creating an Item Using Add

When you click the Add button on certain tabs of items and changes, such as the Affected Items or BOM tab, you can create a new item to add to the tab.

To create an item to add to the tab using Java Client:

1. On the tab to which you want to add a new item, click the Add drop-down menu button and choose the Create option. The New object dialog appears.
2. Select the site you want. To create and add an item to the common portion of the BOM, select Common.

If you have already selected the site you want in the item's Site drop-down list, it is preselected for you in the dialog.

3. From the Type drop-down list, select a type (subclass).
4. Assign a number to the item. To do so, either accept the number that appears, click the Autonumber button  to use the next autonumber, or type a number.

If more than one autonumber format can be used, the available autonumber formats appear in a list when you click the Autonumber button. Select the autonumber format you want.

5. Complete any required fields.
6. Click OK.


The new item appears in the BOM table.

7. To fill in the rest of the new item's tabs, open the item and fill in the information.

To create an item to add to the tab using Web Client:

1. If you want to add a site-specific item to the BOM tab, select the site you want in the item's Site drop-down list.
2. On the tab to which you want to add a new item, click the Add drop-down menu button and choose the Create New option. The New object dialog appears.
3. Select the site you want. To create and add an item to the common portion of the BOM, select Common.

If you have already selected a specific site in the item's Site drop-down list, that site is preselected for you in the dialog.

4. From the Type drop-down list, select a type (subclass).
5. Assign a number to the item. To do so, either accept the number that appears, click the Autonumber button  to use the next autonumber, or type a number.

If more than one autonumber format can be used, the available autonumber formats appear in a list when you click the Autonumber button. Select the autonumber format you want.

6. Complete any required fields.
7. Click Add.

The new item appears in the BOM table.

8. To fill in the rest of the new item's tabs, open the item and fill in the information.

See also: [Creating Items in Java Client](#) (on page 18), [Creating Items in Web Client](#) (on page 19), [Creating an Item Using Save As](#) (on page 20).

Creating a Pending Revision

Writing a pending ECO against an item creates a pending revision of the item. A pending revision can be identified by the parentheses around the revision number in the Rev field, for example, (A).

To create a pending revision:

1. Create the item.
2. Create an ECO.
3. Place the item on the Affected Items tab of the change.
4. Give the affected item a revision number.

Note	SCOs are for site-specific changes only; they do not affect common site information, and they do not roll the revision number. SCOs cannot be used to create a pending revision of a newly created item that has never been released.
------	---

For information about creating changes, see [Changes](#) (on page 111).

Modifying Pending Revisions

You modify pending revisions the same way you modify other objects. Because modifying a pending revision could affect a released revision, you must have the appropriate privileges to modify the Title Block, Page Two, and Page Three fields. If you have privileges to modify preliminary items, you can modify fields on the pending revisions of items. If you have privileges to modify released items only (and you do not have privileges to modify preliminary items), you cannot modify fields on the pending revisions of items. If you have questions about your assigned modify privileges, see the Agile administrator.

See also: [Editing a Released Item](#) (on page 27).

Deleting Agile Objects

Java Client and Web Client support “soft” and “hard” deletes. When you soft-delete an object in the database, it is not permanently deleted. A soft-deleted object is marked “Deleted” in the database, and its object number is reserved. You cannot create another object with the same type and number as a soft-deleted object.

Note You *can* undelete a soft-deleted object, if you have the appropriate privileges. If you need to do so, but do not have privileges, contact the Agile administrator.

This section contains the following topics:

- [Soft-Deleting an Object](#) (on page 25)
- [Undeleting an Object](#) (on page 25)
- [Hard-Deleting an Object](#) (on page 25)

When you run a search, soft-deleted objects do not appear in the search results table. To locate soft-deleted objects, you must run the predefined deleted object searches in the Recycle Bin Searches folder.

Note You have access to the Recycle Bin Searches folder if Recycle Bin Searches is included in the Searches field of your user profile. If you have the appropriate privileges, you can edit your user profile and add Recycle Bin Searches to the list of searches in the Searches field. If you do not have the appropriate privileges to modify the Searches field in your user profile, ask the Agile administrator to modify your user profile.

A hard-deleted object is permanently removed from the database.

Caution You *cannot* undelete a hard-deleted object.

Before you can delete an object, it must meet the conditions described in the following table.

Note You cannot delete an object unless all of its relationships and subscriptions are removed.


Class or base class of object	You can delete this kind of object that meets the following conditions:
Item	<ul style="list-style-type: none"> ▫ The item has no released changes against it. ▫ The item is not listed on the Affected Items tab of any pending change. (You must first remove the item from the Affected Items tab of each pending change before you can delete the item.) ▫ The item has no content on its BOM tab for the current revision or any pending revisions. ▫ The item has no content on its Manufacturers tab for the current revision or any pending revisions ▫ The item is not used on any other item's Bill of Materials, that is, the item to be deleted is not a child item on the BOM tab of a parent item revision, including the latest released revision, past released revisions, or pending revisions of the parent item.

Class or base class of object	You can delete this kind of object that meets the following conditions:
Change	<ul style="list-style-type: none">▫ You are the change analyst or component engineer, and the Agile administrator has given change analysts or component engineers the appropriate privileges to delete a change.▫ The change is at the Pending status type or the Unassigned status.▫ You have Discovery and Read privileges for any items on the Affected Items table, otherwise, you cannot delete the change. <p>Note To delete a change that has already been released, you must first unrelease the change. You need the appropriate privileges to unrelease a change by using the Workflow tab to switch it to a different status.</p>
Manufacturer	<ul style="list-style-type: none">▫ It is not listed on the Manufacturers tab of an item. (Check the Where Used tab of the manufacturing object.)▫ If the object is a manufacturer, no manufacturer parts are associated with it. <p>Note If all manufacturer parts associated with a manufacturer have been deleted, then the manufacturer can be deleted as well. However, you will not be allowed to undelete the soft-deleted manufacturer parts until the soft-deleted manufacturer object is undeleted.</p>
Site	<p>Note Unlike other Agile objects, site objects can be soft deleted, but soft-deleted sites cannot be undeleted or hard deleted. If you are no longer using a site, Agile recommends that you disable it.</p> <ul style="list-style-type: none">▫ The site does not appear on any item's Sites tab.▫ The site is not associated with any other Agile object.▫ The site has a lifecycle of Disabled. <p>Note If it meets the conditions listed above, a disabled site can be soft-deleted even when it is listed in the Sites or Default Site field of user profiles. The deleted site is automatically removed from the Sites list in any user profile where it is listed.</p> <p>Once the site has been associated with an item, you can change its status to Disabled, but you cannot delete it.</p>
Package	<ul style="list-style-type: none">▫ You are the program manager, and the Agile administrator has given program managers the appropriate privileges to delete a package.▫ The package is at the Pending status type or the Unassigned status.
Transfer Order	<ul style="list-style-type: none">▫ The Agile administrator has given you the appropriate privileges to delete a transfer order.▫ The transfer order is at the Pending status type or the Unassigned status.
PSR or QCR	<ul style="list-style-type: none">▫ The Agile administrator has given change analysts or component engineers the appropriate privileges to delete a PSR or QCR.▫ The PSR or QCR is at the Pending status type or the Unassigned status.▫ You have Discovery and Read privileges for any items on the Affected Items table, otherwise, you cannot delete the PSR or QCR. <p>Note To delete a PSR or QCR that has already been released, you must first unrelease it. You need the appropriate privileges to unrelease a PSR or QCR by using the Workflow tab to switch it to a different status.</p>

Class or base class of object	You can delete this kind of object that meets the following conditions:
RFQ	<ul style="list-style-type: none"> ▫ The RFQ has no released changes against it.

Soft-Deleting an Object

To soft-delete an object in Java Client:

1. Select and open the object you want to delete.
2. Click the Delete button , and respond Yes to the confirmation prompt.

The object is soft-deleted. It is no longer available for use. However, until it is hard-deleted, its number or name is reserved in the Agile database and cannot be reused.

To soft-delete an object in Web Client:

1. Select and open the object you want to delete.
2. Choose Actions > Delete, and respond OK to the confirmation prompt.


The object is soft-deleted. It is no longer available for use. However, until it is hard-deleted, its number or name is reserved in the Agile database and cannot be reused.

See also: [Deleting Agile Objects](#) (on page 23), [Undeleting an Object](#) (on page 25), and [Hard-Deleting an Object](#) (on page 25).

Undeleting an Object

You can undelete soft-deleted objects.

To undelete an object in Java Client:

1. Run the appropriate Deleted <objects> search from the Recycle Bin Searches folder.
2. Open the deleted object you want to restore.
3. Click the Undelete button .

To undelete an object in Web Client:

1. Run the appropriate Deleted <objects> search from the Recycle Bin Searches folder.
2. Open the deleted object you want to restore.
3. Choose Actions > Undelete.


See also: [Deleting Agile Objects](#) (on page 23), [Soft-Deleting an Object](#) (on page 25), and [Hard-Deleting an Object](#) (on page 25).

Hard-Deleting an Object

Soft-deleted objects still exist in the database. To remove an object permanently, you hard-delete it. While an object is still only soft-deleted, you can undelete it. Run the appropriate Deleted *object*

search from the Recycle Bin Searches folder.

To hard-delete a soft-deleted object (if you have the appropriate privileges) in Java Client:

1. Run the appropriate Deleted <objects> search from the Recycle Bin Searches folder.
2. Open the object.
3. Click the Delete Object button , and respond Yes to the confirmation prompt.

To hard-delete a soft-deleted object (if you have the appropriate privileges) in Web Client:

1. Run the appropriate Deleted <objects> search from the Recycle Bin Searches folder.
2. Open the object.
3. Choose Actions > Delete, and respond OK to the confirmation prompt.

See also: [Deleting Agile Objects](#) (on page 23), [Undeleting an Object](#) (on page 25), and [Soft-Deleting an Object](#) (on page 25).

Editing Agile Items

You can edit preliminary and released items in different ways. Preliminary items can be edited directly, but released items must be edited with a change order.

This section contains the following topics:

- [Editing an Unreleased Item](#) (on page 26)
- [Editing a Released Item](#) (on page 27)
- [Changing an Item's Subclass](#) (on page 28)

Editing an Unreleased Item


You can edit numbers and much of the other information about an item Title Block tab if the item has *not* been released. For additional information about editing an item that has not been released, see [Working with Pending Revisions](#) (on page 16) and [About Modifying the BOM Table](#) (on page 86).

Note When you renumber a part that is a child of another item, the connection between the parent and child is maintained. If the parent item has been released, you will see a warning asking you if you want to continue.

Whether the item is released or unreleased, you cannot edit item tabs that are completed automatically, such as the Where Used tab, the Changes tab and the History tab.

For example, to renumber an unreleased item using Java Client:


1. Open the item.
2. Select the number in the Number field, and type a new number.

Or click  to assign a new autonumber automatically.
3. When your modifications are complete, click Save to keep them, or click Close to close the object window without saving the changes.

Other fields can be modified in a similar way.

For example, to renumber an unreleased item using Web Client:

1. Open the item.
2. Click Edit.
3. Select the number in the Number field, and type a new number.

Or click  to assign a new autonumber automatically.
4. When your modifications are complete, click Save to keep them, or click Cancel to close the Edit page without saving the changes.

Other fields can be modified in a similar way.

Editing a Released Item

If you have sufficient privileges, you can edit most fields on the item object Title Block tab even after an item is released, including:

- The Number field.
See [Editing an Unreleased Item](#) (on page 26).
- The Description field.
See [Editing a Released Item's Description Field](#) (on page 27).

For more information about editing a released item, see [Redlining the BOM of a Released Item](#) (on page 104).

With sufficient privileges, you can also add or modify attachments (on the Attachments tab) after an item is released.

Note If you have questions about your privileges, ask the Agile administrator.

Editing a Released Item's Description Field

Note The Agile administrator may have configured Agile PLM so that a released item's Description field can be changed only by using the Affected Items tab of a change order.

If you have sufficient privileges, you can edit the Description field of the latest released revision of an item or of a pending ECO revision.

- When you edit a released item's Description field, the new description appears only on the latest released revision of the item.
- If the Description field has been modified several times, only the most recent modification appears in the item's Description field.
- If the item has pending revisions, a warning message appears and allows you to choose whether or not to copy the new description to the pending revisions as well.

Note	If the change order Affected Items tab of the pending revision displays both the Old Item Description (latest released revision) and the New Item Description (pending revision), the Old Item Description field on the Affected Items table will be updated to reflect the actual item description of the latest released revision. The Affected Items table New Item Description (pending revision) remains unchanged.
------	--

- To modify the Description field of a pending revision, use one or both of the following methods. The methods available on your Agile system depend upon how the Agile administrator has configured the Agile system and which privileges you have.
 - Open the item, select the pending revision in the Revision drop-down list. Then edit the Description field and save your edits. (Requires the appropriate privileges.)
 - Use the Affected Items tab of the change order. Select the item's row on the Affected Items table and click Edit. Edit the (new) item description field, and save your edits. (Requires the appropriate privileges.)
- Description field modifications are recorded on the item's History tab after the item is released.

Important The item Description field cannot be modified through an MCO because an MCO does not create a new item revision. The MCO uses the Description field information from the ECO revision or Introductory revision on which it is based.

Changing an Item's Subclass

If your administrator has created additional subclasses, and you have the appropriate privileges, you can change the subclass of an item. For example, you can change the subclass of a particular document from Specification to Data Sheet.

For information about how to change the subclass of an item, see [Changing an Item's Subclass](#) (on page 185).


Releasing an Agile Item to Production

Items are not released to production directly. Rather, a change (an ECO) is created against the item, and that change is released through the change control process, described in *Getting Started with Agile PLM*. For more information about ECOs and other Agile changes, see [Changes](#) (on page 111).

To release an item to production:

1. Follow the steps in [Creating Changes](#) (on page 126) to create an ECO that releases the item.
2. Route the ECO as described in [Changes](#) (on page 111).
3. When the change has progressed through the required statuses, it is ready for release. Usually, this includes at least one Review status type, when users sign off the change.

If AutoPromote is set, the change is released automatically when the change has been signed off and all required values to enable release have been filled in.

If AutoPromote is not set, click the Next Status button ( in Java Client) to release the change.

Note	If you have the appropriate privileges, you can use the Workflow tab to move the change directly to the Released status type in the workflow.
------	---

When the change is released, the item is also released.

For more information about working with workflows, see *Getting Started with Agile PLM*.

Unreleasing an Item

If you have sufficient privileges, and the workflow allows it, you can unrelease a released item.

Caution! *Do not* unrelease items if you use Agile ChangeCAST or Agile Content Service (ACS).

To unrelease an item:

1. Open the item.
2. Click the Changes tab.
3. Open the change that released the item.

(If there are subsequent changes to the item, you must first unrelease those changes in the reverse order from which they were made.)

4. On the Workflow tab, click the Pending status type in the status chart.

Note	Switching a change to any status in the workflow that occurs before the first Released status type unreleases the change and, therefore, unreleases the item. If there is no such status displayed as an available status to select in the change status flowchart (Pending, Submit, Review, or Hold type), either you do not have the necessary privileges to select that status to unrelease the change, or the change's workflow does not allow unreleasing the change. (For information about how to view the sequential list of statuses in a workflow, see the chapter on workflows in <i>Getting Started with Agile PLM</i> .)
------	---

The Change Status dialog box (Java Client) or page (Web Client) opens.

5. Fill in the Notify field.
6. Enter any comments in the Comments field.
7. Click OK.

Incorporating and Unincorporating Items

If you have sufficient privileges, you can incorporate an item. When you incorporate an item, you lock its attachments so no unauthorized changes can be made. If you incorporate an item with no attachments, then none can be added to it.

This section includes the following topics:

- [Overview of File Folders and Item Attachments](#) (on page 30)
- [Overview of Incorporation](#) (on page 30)
- [Pre-incorporating an Item](#) (on page 31)
- [Incorporating an Item](#) (on page 31)
- [Unincorporating an Item](#) (on page 31)

Overview of File Folders and Item Attachments

Note For detailed information about attachments and file folder objects, see *Getting Started with Agile PLM*, Working with Attachments and Working with File Folders. See also Attachments Tab and [Revisions and Attachment Capabilities](#) (on page 15).

All objects have an Attachments tab. On the Attachments tab, you can attach files and URLs to the item by referencing those files and URLs in a file folder object. Individual attached files are stored in file folder objects and can be attached to multiple objects. On an item's Attachments tab, the file folder Version is listed in the attachments table. Each time you check out and check in an attachment from the item's Attachments tab, the file folder Version is advanced by one number. If you have the appropriate privileges, you can also edit the attachments table and select a specific Version of the file folder.

Because multiple objects, including items, can reference the same file folder, it is possible for different items to reference different Versions of the same file folder. Item 123 can reference Version 3 of file folder FF444, and Item 987 can reference Version 6 of file folder FF444.

Overview of Incorporation

When you incorporate an item revision, you lock the item's attachments to the specific file folder Version currently displayed on the item's Attachments tab. Incorporation is an action that applies to item objects only. Non-item business objects, including file folder objects, cannot be incorporated.

Note Only ECO-created revisions and Introductory revisions can be incorporated. For more information about attachments and item revisions, see [Revisions and Attachment Capabilities](#) (on page 15).

For example, if the item's attachment is file SPEC.doc, and it is stored in FF004, and the file folder Version on the item's Attachments tab is Version 3, when you incorporate the item, the item's attachments are now locked to Version 3 of FF004. In a similar manner, if the Version selected on the item's Attachments tab is Latest-4, when you incorporate the item revision, the file folder Version reverts to Version 4, and is now locked on that Version for the incorporated item. If the item has multiple attachments in multiple file folders, all the file folder Versions are locked when you incorporate.

Important Regardless of how many Versions a file folder has, once you incorporate an item revision, it always refers to the locked file folder Version.

Due to checkout and checkin actions that can be performed from the Attachments tabs of any objects that reference the same file folder, as well as checkout and checkin actions on the Files tab of the file folder object itself, it is possible for the file folder to be modified and additional file folder Versions to be created.

Once an item is incorporated, you can no longer check out its attachments from the item's Attachments tab. Copies can be taken of attachments for the purpose of viewing and working with them, but the attachments cannot be amended on that revision of the item without unincorporating. (Amending an item's attachments includes adding or deleting attachments and changing the file folder Version number shown in the attachments table.) Likewise, you cannot incorporate an item that has any files checked out.

Before you can add or edit the attachment files of an incorporated item or the file folder Versions

referenced by an incorporated item, the item must first be unincorporated. Once the changes are made, the item can be incorporated again. Appropriate privileges are required to either incorporate or unincorporate items.

The Incorporated/Unincorporated status refers to *all* the attachments to the item for a specific revision. When you incorporate an item, only that revision with its attachments is incorporated. For example, if you have three unincorporated revisions of an item (revisions C, D, and E), when you incorporate revision D, revisions C and E remain *unincorporated*.

For information about working with attachments and file folder objects, see *Getting Started with Agile PLM*.

See also: [Incorporating and Unincorporating Items](#) (on page 29).

Pre-incorporating an Item

An item with a pending change can be incorporated before it is released, in which case it is referred to as “pre-incorporated.” Pre-incorporating an item provides a way to mark a revision as tentatively complete, and to “freeze” attachments from checkout. (It is still possible to “get” a copy of an attachment, but the files attached to an incorporated item revision cannot be modified.)


Pre-incorporation is performed the same way as incorporation, except that it is performed on an unreleased item. For instructions, see [Incorporating an Item](#) (on page 31).

See also: [Incorporating and Unincorporating Items](#) (on page 29).

Incorporating an Item

You cannot incorporate an item that has any attachment files checked out.

To incorporate an item using Java Client:

1. Open the item.
2. Click the More button  at the top of the object window to display the More Actions menu and choose Incorporate.

Or, right-click in the window, and choose Incorporate from the shortcut menu.

To incorporate an item using Web Client:

1. Open the item.
2. Choose Actions | Incorporate.

If an item is incorporated before it is released, the incorporation process is performed the same way, but it is known as pre-incorporation. See [Pre-incorporating an Item](#) (on page 31).


See also: [Incorporating and Unincorporating Items](#) (on page 29).

Unincorporating an Item

When you unincorporate an item, just that particular revision is unincorporated.

To unincorporate an item using Java Client:

1. Open the item.

2. Click the More button  at the top of the object window to display the More Actions menu and choose Unincorporate.

Or, right-click in the window, and choose Unincorporate from the shortcut menu.

To unincorporate an item using Web Client:

1. Open the item.
2. Choose Actions | Unincorporate.

See also: [Incorporating and Unincorporating Items](#) (on page 29).

Where Used Tab

The item object Where Used tab lists all the assemblies that use the item. The information on this tab is filled in automatically.

The Where Used tab includes two tables:

- Where Used — displays the latest released revision of the assemblies where the item is used. If the assembly has never been released, the Introductory revision is displayed. For more information, see [Introductory Revisions](#) (on page 13).
- Pending Change Where Used — displays the pending revisions of the assemblies where the item is used, including the associated change order number.

To view or hide the Pending Change Where Used table:

Use the View drop-down list to select either Show Pending or Hide Pending.

Note	When you first view the Where Used tab, the Pending Change Where Used table is hidden by default.
------	---

To view an item from the Where Used tab using Java Client:

Double-click the item's row.

To view an item from the Where Used tab using Web Client:

Click the item number.

Note	If you do not have Discovery privilege for an item, it does not appear on the Where Used tab. You may see a message telling you how many items are not displayed. For more information, see Details about Discovery and Read Privileges (on page 183).
------	--

For information about site information displayed in the Where Used tables, see [Sites and the Where Used Tab](#) (on page 32).


Sites and the Where Used Tab

The item object Where Used table displays all the assemblies where the item is used. Assemblies can be listed multiple times, once per site. The Sites column in the Where Used table shows common (blank) and site-specific portions of the BOM that include the item.

For more information about the where used tables, see [Where Used Tab](#) (on page 32).

Printing Item Tabs

You can print object tabs and other data from your Agile PLM system. You can print the current tab or all tabs. Attachments are printed from their native applications or the Viewer.

In Java Client, with the object open, use the Print button .

In Web Client, with the object open, choose Actions | Print.

For additional information about printing objects, see *Getting Started with Agile PLM*.

Sites and Distributed Manufacturing

This chapter includes the following:

▪ What is Agile Distributed Manufacturing?	35
▪ What Are Sites?	37
▪ How Sites Can Be Used	38
▪ How Sites Work	39
▪ Where Sites Are Documented	40
▪ Site Objects	41
▪ Creating Sites	45
▪ Associating a Site with an Item	46
▪ Deleting Site Objects	48
▪ Editing Sites	48
▪ Printing Sites	49

What is Agile Distributed Manufacturing?

Note For information about implementing and configuring Agile multi-site manufacturing, see *Administrator Guide*. For information about using Agile multi-site manufacturing, see *Product Collaboration User Guide*, in particular, chapter 2, "Sites and Distributed Manufacturing."

When the Agile administrator enables the Agile PLM Sites license, the Agile Site object is available and Agile PLM multi-site manufacturing functions become available. Agile multi-site manufacturing capabilities are used to assist a company that builds its products in multiple locations (distributed manufacturing). Before taking this step, you must determine and plan how Agile PLM multi-site manufacturing will be integrated with your ERP system.

Warning Agile PLM multi-site manufacturing functionality is built differently than ERP sites. Agile Site objects and ERP sites are similar, but they are not identical. You should work with an Oracle Consulting - Agile practice representative to plan your Agile PLM to ERP integration before you enable the Agile Sites license. The type of information that you want to track in Agile PLM and how you choose record that information in Agile PLM may depend on how product information is stored in your ERP system.

Agile multi-site manufacturing helps a company that builds its products in multiple locations to do so by enabling parts and documents in those locations that are specific to the manufacturing process. In Agile PLM, revisions are global item attributes. If a part is used in two manufacturing sites, it must share the revision level, although the effectivity dates and disposition settings can be different.

The Agile multi-site manufacturing features allow you to annotate product data with three types of site relationships:

- Item object-to-Site relationship

An item can be associated with one or more sites by adding the site object to the sites table on

the item Sites tab. Item-site relationships are similar, but not identical to ERP item-site relationships. You can see if an Agile part is enabled in any sites by viewing its Sites tab.

- Parts that are not released in any site have only global item effectivity dates and dispositions.
- Parts released in sites are can have both site-specific item effectivity dates and dispositions and global item effectivity dates and dispositions.

▫ BOM row-to-Site relationship

BOM row-site relationships are unique to Agile PLM. A child part can relate to its parent with no site relationship or through one or more specific sites. Each BOM row has either no site relationship or one site relationship. Use multiple rows, one for each site, to represent more than one site relationship for the same child part.

- A child part that reports to its parent without a specific BOM row-site relationship is considered a common part, that is, a part common to all manufacturing sites.
- A child part that reports to its parent with a BOM row-site relationships is a site-specific part, that is, a part that is specific to the related manufacturing site.

▫ AML table row-to-Site relationship

On an part's Manufacturers tab, you can specify site-specific AMLs (Approved Manufacturer List). Rows on the part manufacturer table can be common (specify no site) or a site-specific (associated with a site listed on the part's Sites tab). BOM row-site relationships and AML row-site relationships are independent of one another.

- An manufacturer part without a specific AML row-to-site relationship is a common manufacturer part and can be used at any manufacturing site.
- A manufacturer part with an AML row-to-site relationship is a site-specific manufacturer part, which allows the manufacturer part to be used at the specified manufacturing site.

Other important Agile PLM sites and ERP sites differences to keep in mind:

- In many ERP systems, a part can appear in different sites and have independent revisions. Agile considers all revision to be a global attribute of the part, therefore, site-based revisions are not supported in Agile PLM. To accommodate this need, simply prefix or suffix the part number with a unique string, for example SJC-P1000 and NYC-P100. These are unique parts which have global revision, but because these parts aren't used in other sites their revisions appear to be site-specific.
- The item-site relationship and the BOM row-site relationship are independent of one another in that you can add a part to a BOM as a site-specific BOM row without first adding the site to the part. Unlike typical ERP systems, Agile does not require that a part must first be released in a site before it can be added to a site-specific BOM row.
- When adding a row to a BOM where the parent has Sites that are not on the child, Agile PLM prompts the user to add the Sites to the child. This occurs only on the initial add of the BOM row - either in authoring mode (direct editing of a part) or in redlining mode (modifying a part through change redline). The user can choose only to Copy the sites onto the child in order to add the row to the BOM; choosing Close will not add the BOM row. If additional Sites are subsequently added to the parent, the newly added Sties are not automatically copied to the child. If Sites are removed from the child, no check is made on whether there is inconsistency between Sites on the parent and the child.
- The SmartRule Child Released First is enforced by the Release Audit when a part is released. When a parent part is released, this rule checks the BOM components for Site association and

whether the BOM components are also released. The Release Audit verifies whether or not the item has been released by a Change or Manufacturer Change after a Site was added. In order to correctly pass this SmartRule, the Item must be released after adding a Site.

What Are Sites?


In Agile PLM, *site objects* represent manufacturing sites. Companies that practice distributed manufacturing use several different manufacturing sites for their products. For example, Widget Corporation manufactures its products at the corporate location in Austin, Texas, but also at manufacturing plants in Taiwan, Singapore, Mexico City, and Milpitas, California.

Site objects ensure that each ERP has only the relevant information for its production needs. For example, companies can manage what is sent to each internal ERP site or contractor in a Make vs. Buy site association.

Site objects help ease the production transfer from one manufacturing site to another. For example, the Widget Corporation can transfer an entire product from their Taiwan prototype site to their Mexico City production site by adding the production site association to all the parts in the Taiwan BOM that are not in the Mexico City BOM, then send the BOM to Mexico City through an engineering change order (ECO) or a site change order (SCO).

Site objects also help to formalize the site effectivity process by allowing a user to create a proposed effectivity date change (SCO) against a part revision. For example, if a site production date has to be changed to a later date, an SCO against the part provides a simple record of approvals and reasons for changing the effective date.

The following diagram illustrates how sites can be used in Agile PLM. The three sites in this diagram vary in ERP system, effectivity date, and manufacturer. Also, Site 3 has added site-specific build instructions.



How Sites Can Be Used

You can use sites to record and manage site-specific AMLs, BOMs, and effectivity dates.

This section includes the topics:

- [Different AMLs at Each Site](#) (on page 38).
- [Different BOMs at Each Site](#) (on page 38).
- [Different Effectivity Dates and Dispositions at Each Site](#) (on page 39).

Different AMLs at Each Site

Often, different sites use different manufacturers and manufacturer parts to build the same products. Reasons for the differences could be cost (for example, it may be more cost-effective for a site to use a nearby manufacturer) or status of a manufacturer, to name two examples. The AML for an assembly can include different manufacturer parts for the various manufacturing sites.

See also: [How Sites Work](#) (on page 39).

Different BOMs at Each Site

The BOM of an assembly can include items that pertain only to specific sites. The common BOM lists all items that make up the core assembly, and that BOM is the same for all sites; but the

appropriate users assigned to each manufacturing site can add site-specific items to the BOM (thus creating a site-specific portion of the BOM). Often, these additional items are documents, such as assembly instructions specific to how something is built at a site.

See also: [How Sites Work](#) (on page 39).

Different Effectivity Dates and Dispositions at Each Site

Items may have different effectivity dates and dispositions at each site. This enables, for example, the Austin site to begin using revision B of an item while Singapore continues to use revision A until stock has run out.

Effectivity dates and dispositions are specified on the Affected Items tab of an ECO or an SCO. If you want to create a new revision when you assign the new effectivity date or disposition, use an ECO. To assign site-specific effectivity dates and dispositions without incrementing the revision, use an SCO.

See also: [How Sites Work](#) (on page 39).

How Sites Work

Site objects, similar to manufacturer objects, hold information about each site. Users with appropriate privileges can create additional sites.

This sections includes the topics:

- [Site Information on BOMs and AMLs](#) (on page 39).
- [Sites Tab of Items](#) (on page 39).
- [Changes and Sites](#) (on page 40).
- [Controlling Access to Sites](#) (on page 40).
- [Common BOM/AML Sections](#) (on page 40).

Site Information on BOMs and AMLs

When you view an item's BOM or AML (Manufacturers tab), you can choose to view it for all sites or for a specific site. When you view the BOM or AML for a specific site, the common BOM or AML is included in the list.

See also: [How Sites Work](#) (on page 39), [Viewing BOMs by Site](#) (on page 82), [Viewing AML Information by Site](#) (on page 68).

Sites Tab of Items

Each item includes a Sites tab. The Sites tab lists the sites where that item can be used. If a site is not listed on an item's Sites tab, then that item cannot be included in the portion of a BOM specific to that site. If all the sites of the parent BOM are not listed on an item's Sites tab, then that item cannot be included in the common portion of a BOM. For a detailed explanation, see [Common BOM/AML Sections](#) (on page 40).

See also: [How Sites Work](#) (on page 39), [How Sites Can Be Used](#) (on page 38).

Changes and Sites

Changes can affect all sites of an item or a specific site. The Affected Items tab lets you select sites to affect as you add affected items. Use site change orders (SCOs) to create site-specific changes to an item without changing the revision.

See also: [How Sites Work](#) (on page 39), [Changes and Manufacturing Sites](#) (on page 122), [Site Change Orders](#) (on page 124).

Controlling Access to Sites

The use of sites is controlled by your organization's licenses, roles, privileges, and default site property (which determines which site you see by default). You can create as many sites as you want.

Your organization may have implemented sites in such a way that users can access only the information pertaining to certain sites.

Your user profile Sites list controls which site objects you can discover in the Agile database and which item site-related rows (BOM tab, Manufacturers tab) you can discover. The ability to read site object attributes is controlled by your Read privileges.

Users with Administrator privilege have the ability to assign all sites when modifying a user's User Profile attributes. However, when searching for sites in Web Client or Java Client, the Administrator user can discover only the sites listed in the Sites list of his own User Profile.

See also: [How Sites Can Be Used](#) (on page 38), [How Sites Work](#) (on page 39).

Common BOM/AML Sections

The common section of the BOM distinguishes information that is shared between all the sites listed on the Sites tab of the item. All the parts in the common section of the BOM of an assembly must have listed on their Sites tabs all the sites that are listed on the Sites tab of the assembly. That is, they have those sites in common.

For example, if part 300 is to appear on the Milpitas-specific portion of the BOM of assembly 234, then part 300 and assembly 234 must both have the Milpitas site listed on their Sites tabs. If assembly 234 has three sites (Milpitas, India, and San Jose) on its Sites tab, for part 300 to appear on the common portion of the BOM of assembly 234, part 300 must also have at least those three sites (Milpitas, India, and San Jose) included on its Sites tab. That is, they must have those sites in common. (Part 300's Sites tab may also include additional sites that do not relate to assembly 234.) A SmartRule (Items Released First) controls whether Agile checks an item's BOM components for the appropriate site association at release. Compliance with the SmartRule is checked when an ECO, SCO, or MCO releases the assembly. You can also use the change Audit Release feature to check for compliance before release.

See also: [Creating a Common BOM](#) (on page 6), [Creating a Site-Specific BOM](#) (on page 7).

Where Sites Are Documented

You can find information about sites in the following sections:

Topic	Section or chapter
Site objects	The rest of this chapter
Sites tab of items	This chapter and Chapter 1, Items (on page 1)
Viewing site-specific information	The following chapters: Chapter 1, Items (on page 1) Chapter 4, Bills of Material (on page 77) Chapter 6, Affected Items of Changes (on page 131) Chapter 3, Manufacturing Objects (on page 51)
Site-specific BOMs	Chapter 4, Bills of Material (on page 77)
Site-specific AMLs	Chapter 3, Manufacturing Objects (on page 51)
SCOs	Chapter 5, Changes (on page 111), and Chapter 6, Affected Items of Changes (on page 131)
Effects of changes on sites	Chapter 5, Changes (on page 111), and Chapter 6, Affected Items of Changes (on page 131)
Redlining site-specific information	Chapter 6, Affected Items of Changes (on page 131)
Site-specific effectivity dates and dispositions	Chapter 6, Affected Items of Changes (on page 131)

Site Objects

A site object contains general information about a site. Unlike items, sites do not need to go through a release process.

This section includes the following topics:

- [General Info Tab - Sites](#) (on page 42)
- [Attachments Tab](#) (on page 44)
- [History Tab](#) (on page 44)

To locate and open an item, follow the instructions in *Getting Started with Agile PLM*.

The following table lists the tabs for sites.

The Agile administrator may have added additional sections to the Title Block or General Information tab, called Page Two and Page Three by default (Web Client). In Java Client, these are separate tabs. These sections or tabs contain custom fields defined by the administrator.

Site tab name	Tab information includes
General Info	General information about the site
Attachments	Attached drawings, files, and URLs pertaining to the site
History	Actions taken on the site, for example, when attachments were added and removed

General Info Tab - Sites

The General Info tab has fields that contain basic information about a site. Some fields are filled in automatically; you complete the rest. You may not be able to edit the content of some fields.

This section includes the following topics:

- [General Info Tab Fields - Sites](#) (on page 42)
- [Site Lifecycle Phase](#) (on page 43)
- [AML Required on Buy Field](#) (on page 43)
- [Site AML Allowed Field](#) (on page 43)

General Info Tab Fields - Sites

By default, the site object General Info tab contains the fields listed in the following table.

Field	Definition
Name	The name of the site. This field must be filled in with a unique value.
Type	The subclass (type) of the site object.
Lifecycle Phase	The current state of the site: Enabled or Disabled.
Site ERP Code	The ERP system in use at the site, if applicable.
Address, Geography, Province/Region/State, Country/Area, City, Postal Code, Phone, URL, Fax,	Contact information for the site.
Contact	The name of the contact person for the site.
Email	The email address of the contact person.
Buyer	The buyer code for the item at this site. Select one from a list of codes that have been assigned for sites.
Planner	The planner code for the item at this site. Select one from a list of codes that have been assigned for sites.
Color	The color associated with this site. Choose from a list of colors. This color will be used on the BOM , Manufacturers , and Affected Items tabs to distinguish common items from site-specific items. The same color can be used for more than one site.
Site AML Allowed	For items specified as Buy, indicates whether a site-specific manufacturer value is required, allowed, or disallowed.
AML Required on Buy	Indicates whether a manufacturer value is required for an item when the item is specified as a Buy (as opposed to a Make) for this site. Whether an item is Buy or Make is shown by the Make/Buy field on the Sites tab of the item.

See also: [Site Objects](#) (on page 41), [Site Lifecycle Phase](#) (on page 43), [AML Required on Buy Field](#) (on page 43), [Site AML Allowed Field](#). (see "Site AML Allowed Field" on page 43)

Site Lifecycle Phase

- A site can be in one of the following states, as indicated in the Lifecycle Phase field on the site's General Info tab:
- Enabled – When a site is enabled, users can define all site properties of the site itself. Also, users can associate the site with an item, define item-site properties, create site-specific BOMs and AMLs, and create changes for site-specific items.
- Disabled – All sites are disabled when they are first created. When a site is disabled, users cannot create site-specific BOMs, AMLs, or changes. However, disabled sites do show up in searches and reports. Any in-process changes that involve a site that's been disabled are allowed to continue through release, but users will not be able to edit the disabled site's site-specific Affected Item table rows, and users cannot make any redline add or redline edit modifications to in-process changes when the site has been disabled.

To change a site's lifecycle phase, select a lifecycle phase from the drop-down list.

See also: [General Info Tab Fields - Sites](#) (on page 42).

AML Required on Buy Field

The AML Required on Buy field of a site determines whether an AML is required for an item when the item is specified as a *Buy* for a given site.

Note	Whether an item is specified as a Buy is determined by the value in the Make/Buy field on the item's Sites tab.
------	---

When an item is released, the system checks to see which sites the item is being released for, as indicated on the Affected Items tab of the releasing change. The system then checks the Make/ Buy field on the item's Sites tab to determine if any of the sites are specified as Buy. If an item is specified as a Make for all sites, this rule is ignored.

Possible AML Required on Buy values are Yes or No (the default)

- No – The system checks to see if the item being released has either a common AML or an AML that is specific for the sites that are specified as Buy sites for the item. At time of release, the system does not check if the item does not have an AML for the site. The item can still be released.
- Yes – The item being released must have either a common AML or an AML that is specific to the sites that are specified as Buy sites for the item.

When AML Required on Buy is set to Yes, if an autopromotion attempts to release the item (via a change), but the item does *not* have a site-specific AML for the appropriate sites, the promotion fails, and the appropriate person is notified.

See also: [General Info Tab Fields - Sites](#) (on page 42).

Site AML Allowed Field

This field, used when the item is specified as a Buy for a given site, governs whether an AML for an item:

- Must be specific for the site
- Can be modified for a specific site
- Can use only the common site AML

Note	Whether an item is specified as a Buy for a given site is determined by the value in the Make/Buy field on the item's Sites tab.
------	--

When an item is released, the system checks to see which sites the item is being released for, as indicated on the Affected Items table of the releasing change. The site's Site AML Allowed field is then checked to determine if any of these sites are required or allowed to have a site-specific AML.

Possible Site AML Allowed values are Allowed (the default), Required, and Disallowed:

- Allowed – The item being released is allowed to have a site-specific AML for the site, but it is not required. The item can be released.
- Required – The item being released *must* have a site-specific AML for the sites specified as Buy sites for the item. The item cannot be released until this condition is satisfied.

If an auto-promotion attempts to release the item (through a change), but the item does *not* have a site-specific AML for the appropriate sites, the promotion fails, and the appropriate person is notified.

- Disallowed – The item being released cannot have a site-specific AML for the site. If the item has a site-specific AML, it cannot be released.

If an autopromotion attempts to release the item (via a change), and the item includes a site-specific AML, the promotion fails, and the appropriate person is notified.

If a site-specific AML is created for an item (through modification to the AML or redline of the AML), when the item is released, the system checks the Site AML Allowed field of the sites to determine if any of the sites have Site AML Allowed set to Disallowed. If a site is disallowed, you cannot release a site-specific AML for that site.

See also: [General Info Tab Fields - Sites](#) (on page 42).

Attachments Tab

All objects have an Attachments tab. On the Attachments tab, you can attach files and URLs to the object by referencing those files and URLs in a file folder object. On the Attachments tab, you can view, copy (get), or print attached files if you have the appropriate privileges.

Individual attached files are stored in file folder objects and can be attached to multiple objects. The files in a file folder object can be drawings or scanned images, documents, non-viewable files, compressed files, and so on.

For detailed information about working with file folder objects and the Attachments tab, see *Getting Started with Agile PLM*.

See also: [Site Objects](#) (on page 41).

History Tab

The History tab shows a summary of actions taken against an object, including a description of the

action, which user took the action, the date of the action, and other details.

Note If you do not have the appropriate Read privilege for an object, you cannot see the contents of the fields on the History tab. See [Details about Discovery and Read Privileges](#) (on page 183).

The types of actions recorded for sites are:

- Creating the site
- Attachment actions: view, open, add, delete, and get
- Save As
- Send
- Print
- Change subclass
- Modification of any field of a site



See also: [Site Objects](#) (on page 41).


Creating Sites

This section includes the topics:

- [Creating Manufacturing Sites](#) (on page 45).
- [Creating a Site Using the Save As Feature](#) (on page 46).

To create a site, you must have the Create Site privilege.

In Java Client, you can create a site with the File | New | Site command or the New Object button , or the Save As command, on the More Actions menu (click the More button  at the top of the object window) and on the right-click shortcut menu.

In Web Client, you can create a site with the Create | Site command  or the Actions | Save As command.

Note The site name must be unique to a site, just as an item number must be unique to an item.

Choose a color to make it easier to distinguish common items from site-specific items on the BOM, Manufacturers, and Affected Items tabs. In Java Client, the site colors also appear on the item Where Used tab and Changes tab. For more information about site colors, see [General Info Tab Fields - Sites](#) (on page 42).

When you create a site, you automatically have access to information specific to that site. The new site is included in the Sites field in your user profile.

Creating Manufacturing Sites

The process for creating new objects involves two main steps: creating an empty object, then filling

in the object tabs with information specific to the object. For more information about creating sites and other objects, see *Getting Started with Agile PLM*.

See also: [Creating Sites](#) (on page 45).

Creating a Site Using the Save As Feature

Using the Save As feature is a quick way to create a site that is similar to an existing site.

All General Information and Page Two field values and Page Three (depending on Agile system settings) field values are copied to the new site. The new site's lifecycle phase is Disabled. The Attachments are created using the preferred method selected by the Agile administrator (Create New, Reference Existing, Do Not Copy Files, or by prompting; see also [Creating an Item Using Save As](#) (on page 20)). The History tab of the original site reflects that the new site was copied from it.

For more information about creating a site using Save As, see *Getting Started with Agile PLM*.

See also: [Creating Sites](#) (on page 45).

Associating a Site with an Item

This section includes the following topics:

- [Fields on the Sites Tab](#) (on page 46)
- [Adding Sites to the Sites Tab](#) (on page 47)
- [Removing Sites from the Sites Tab](#) (on page 48)

To make an item available to site-specific BOMs, you must add the sites to the item's Sites tab. If a site is not listed on an item's Sites tab, you cannot define a site-specific BOM or AML for the item. A site can be listed only once on the Sites tab.

The Sites tab is not under change control, so you don't need to create a change to modify the information on this table.

Fields on the Sites Tab

The following table lists default fields on the Sites tab of items.

Field	Definition
Site Name	The name of the site. Not editable from the Sites tab.
Buyer	The buyer code for the item at this site. Select one from a list of codes that have been assigned for sites.
Planner	The planner code for the item at this site. Select one from a list of codes that have been assigned for sites.
Make/Buy	Indicates whether this site makes or buys the item.
Cost	Yes or No. Indicates, for this site, whether there is a cost associated with the item.
Quote As	Select from list. Indicates, for this site, how the item is to be quoted, for example, assembly or component.

Field	Definition
Currency	Default currency for this site.
Standard Cost	This site's standard cost for the item.
Target Cost	This site's target cost set for the item.
First Released Change	The change that first released the item to this site. This is automatically filled in when the item is released. Not editable from the Sites tab.
Site Lifecycle Phase	The current state of the site: Enabled or Disabled. Not editable from the Sites tab.
Site Type	The subclass of the site. Not editable from the Sites tab.

See also: [Adding Sites to the Sites Tab](#) (on page 47), [Removing Sites from the Sites Tab](#) (on page 48).

Modifying the Make/Buy Field on the Item Sites Tab

If you have the appropriate modify privileges, you can modify the Make/Buy field in an item's Sites table, even if the item has been released. However, the Make/Buy setting is not revision-specific. When you modify the Make/Buy setting on any item revision, it is also modified for all revisions. The following restrictions apply when modifying the Make/Buy setting:

- When the item is included on the affected items table of a change order, the release audit validates the site's Site AML Allowed and AML Required on Buy settings with the item Sites tab Make/Buy setting for that revision. Past revisions are not audited. (A release audit is performed automatically when the change order is released.)
- Because the Make/Buy setting is not revision-specific and can be changed without using a change order, any validation violations caused by a modification to Make/Buy remain on the latest released revision of the item and may not be detected until the next time the item is added to a change order and the change order is release audited.



For more information, see [AML Required on Buy Field](#) (on page 43) and [Site AML Allowed Field](#) (on page 43).

Adding Sites to the Sites Tab

When you add sites to the Sites tab of an item, you select the sites from a list. That list includes all enabled sites that you have access to—sites with a lifecycle phase of Enabled that are included in the Sites field of your user profile. Disabled sites do not appear in the list because disabled sites cannot be added to the Sites tab of an item.

After you add a site to the Sites tab of an item, you can select the site on the Sites table and edit it to enter values for the other fields in the Sites table. You cannot change the Site Name value in the Sites table; to change which site is listed, delete the site and add a new one.

To add a site to the Sites tab in Java Client:

1. On the Sites tab of an item, you can use the Add button in two ways:
 - Click the Add button  to display dialog box that allows you to select multiple sites. When you have made your selections, click OK.
 - Click the drop-down arrow portion of the add button  to select the site name you

want in the drop-down list.

To add a site to the Sites tab in Web Client:

1. On the Sites tab of an item, click the Add button.
The selection dialog appears.
2. Move the sites you want to include from the Available Values list to the Selected Values list. When you are finished, click OK


See also: [Removing Sites from the Sites Tab](#) (on page 48).

Removing Sites from the Sites Tab

You can remove a site from an item's Sites tab, as long as the item has not been released to that site and you have the appropriate privileges. Deleting a site from the Sites tab does not delete the site object from the database.

If you try to remove a site that is referenced by a site-specific BOM or AML, the system displays a warning; removing such a site also removes the corresponding site-specific BOMs and AMLs and site-specific Affected Item table rows and site-specific redlines on changes.

To remove a site from an item's Sites tab in Java Client:

1. Select the site that you want to remove.
2. Click the Remove  button on the Sites tab.

To remove a site from an item's Sites tab in Web Client:

1. Select the site that you want to remove.
2. Click the Remove button on the Sites tab.

See also: [Adding Sites to the Sites Tab](#) (on page 47).

Deleting Site Objects

For important details about deleting site objects, see [Deleting Agile Objects](#) (on page 23).

Editing Sites

Any user with the necessary privileges can modify values entered for a site. Sites are not required to go through the change control process; all modifications go into effect immediately.

To edit a site in Java Client:

1. Display the site's General Info tab.
2. Make the changes you want.
3. Click Save.

To edit a site in Web Client:

1. Display the site's General Info tab.

2. Click Edit.
3. Make the changes you want.
4. Click Save.


Keep the following in mind regarding some of the fields on the General Info tab:

- Name – If you change a site name, the change is made to the Sites tab of the items where the site is listed and to any other tabs where the site is listed, such as the BOM tab. You cannot change the site name to the same name as another site.
- Buyer or Planner – A buyer or planner cannot be removed if listed on the Site table of an item.
- AML Required on Buy and Site AML Allowed – If you edit AML Required on Buy or Site AML Allowed, released items are not affected. The new values are enforced with any new items and newly released changes.

See also: [Creating Sites](#) (on page 45).

Printing Sites

You can print object tabs and other data from your Agile PLM system. You can print the current tab or all tabs. Attachments are printed from their native applications or the Viewer.

In Java Client, with the object open, use the Print button .

In Web Client, with the object open, choose Actions | Print.

For additional information about printing objects, see *Getting Started with Agile PLM*.

Manufacturing Objects

This chapter includes the following:

▪ What Is Agile AML?	51
▪ Setting Up Manufacturing Data.....	53
▪ Manufacturing Objects: Manufacturers and Manufacturer Parts	54
▪ Creating and Managing Manufacturing Objects	58
▪ Deleting Manufacturing Objects.....	66
▪ Manufacturers Tab of an Item.....	67
▪ Viewing AML Information by Site.....	68
▪ Associating a Manufacturer Part with Its Corresponding Item.....	68
▪ Important Considerations When Working with Manufacturing Objects.....	69
▪ Working with Manufacturing Data on Preliminary Items	69
▪ Modifying Manufacturing Data from the Redlines Tab.....	72
▪ Printing Manufacturing Objects and AMLs	76

What Is Agile AML?

This section covers the following topics:

- [What Does Agile AML Do?](#) (on page 51)
- [About Manufacturing Objects](#) (on page 52)
- [Many-to-One Relationships in Agile AML](#) (on page 52)

The Agile Approved Manufacturers List (AML) solution enables an organization to manage information related to manufacturers and the parts they produce.

What Does Agile AML Do?

Agile PLM provides a way to track the relationships between items and their manufacturers and to create an approved manufacturers list (AML). This means you can quickly find, for instance, which manufacturers are producing a particular part, their identification information for that part, where that part is used, and contact information for the manufacturer.

An item's AML is represented by the rows of information on the Manufacturers tab of the item. Each row represents a manufacturer part. See [Manufacturers Tab of an Item](#) (on page 67).

Additionally, you can use manufacturer change orders (MCOs) to change manufacturing data.

Note To change site-specific manufacturing data, use a site change order (SCO).

About Manufacturing Objects


The AML features let you work with the following manufacturing objects:

- The manufacturer – this object holds data about product manufacturers, including contact information and where their parts are used in your assemblies.
- The manufacturer part – this object describes product parts from the manufacturers' point of view, with information such as their part numbers and their names for that part, as well as information about where this part is used in your assemblies and which manufacturing sites use this manufacturer part.

For more information about manufacturing objects, see [Manufacturing Objects: Manufacturers and Manufacturer Parts](#) (on page 54).

Many-to-One Relationships in Agile AML

AML capabilities allow you to track complex, many-to-one relationships. The following figure shows an example of a more complex situation such as those commonly found in real-life manufacturing.



In this example, one part has more than one manufacturer part, and some manufacturers provide more than one manufacturer part.

Note Depending on the Agile Administrator setting for the Multiple Items Per Manuf Part SmartRule, your Agile PLM system may be configured so that a manufacturer part can be added to the Manufacturers tab of only one item. Contact the Agile administrator if you have questions about manufacturer parts associated with multiple items.

Sites and AML Data

A manufacturer part can apply to all manufacturing sites where the product is built, some sites, or just one site. The common portion of the AML lists AML information that is shared between all the sites assigned to the item. Each site can add other manufacturing information to the AML table that is site-specific—for example, manufacturers that are used by the site because they're located nearby. Also, a manufacturer part may be Preferred at one site and Alternate at another site. Manufacturer parts used by multiple sites are listed multiple times on the AML tab, once for each site.

The AML Required on Buy field of a site determines whether a manufacturer part is required for an item when the item is specified as a *Buy* for a given site. For more information about AML Required on Buy, see [AML Required on Buy Field](#) (on page 43).

Note	Whether an item is specified as a Buy is determined by the value in the Make/Buy field on the item's Sites tab.
------	---

Setting Up Manufacturing Data

To track manufacturing data in Agile PLM, you must first set up the manufacturers in your database and then create the manufacturer parts that they produce for use in your assemblies.

Order is important. You cannot create a manufacturer part until you have created the corresponding manufacturer.

The process is performed in the following sequence:

1. Create the manufacturer.
For example, create a manufacturer named *Acme*.
2. Create the manufacturer part.
Create manufacturer part number *AM230PS*, specifying *Acme* as the manufacturer.
3. Add the manufacturer part to the internal part's Manufacturers tab.
For example, on part *P001232*, go to the Manufacturers tab and add *Acme AM230PS*.

Once the relationships have been established, it is easy to track manufacturing data activity.

From this point on, manufacturing data can be managed through the redlining process. This is discussed in [Redlining through ECOs, MCOs, and SCOs](#) (on page 127).

Note	Manufacturing objects are not subject to the change control process and can be created, edited, and deleted by any user granted the necessary privileges. Those changes go into effect immediately.
------	---

To set up manufacturer data in the database:

1. Create the manufacturer. This represents the manufacturer of the purchased part.
See [Creating and Managing Manufacturing Objects](#) (on page 58).
2. Create the manufacturer part. This represents the part that the manufacturer produces.
See [Creating and Managing Manufacturing Objects](#) (on page 58).

3. Match the manufacturer part to the corresponding item by adding it to the item's Manufacturers tab.

See [Adding a Manufacturer Part to the Manufacturers Tab](#) (on page 69).

Manufacturing Objects: Manufacturers and Manufacturer Parts

This section covers the following topics:

- [Manufacturing Object Tabs](#) (on page 54)
- [About Manufacturers](#) (on page 56)
- [About Manufacturer Parts](#) (on page 57)

Manufacturing Object Tabs

Manufacturing objects have several of the same tabs as items (Where Used, Attachments, and History), but they also have differences. For example, they have a General Info tab in place of the Title Block tab, and they do not have a Changes or BOM tab.

The table below lists the default fields on the tabs of these two manufacturing objects.

The Agile administrator may have added additional sections (Web Client) or tabs (Java Client), called Page Two and Page Three by default. These sections or tabs contain custom fields defined by the administrator.

Manufacturers		Manufacturer parts	
Tab	Fields include	Tab name	Fields include
General Info tab	Name, Lifecycle Phase, Mfr. Type, Contact, URL, D-U-N-S Number, contact information	General Info tab	Manufacturer Name, Manufacturer Part Number, Description, Mfr. Part Type, Lifecycle Phase The following fields are related to Agile PG&C. For more information, see the <i>Agile Product Governance and Compliance User Guide</i> . Compliance Calculated Date, Part Family, Mass, Overall Compliance

Manufacturers		Manufacturer parts	
Tab	Fields include	Tab name	Fields include
Where Used_tab (on page 55)	Item Number, Item Description, Mfr. Part Number, Mfr. Part Lifecycle Phase	Where Used_tab (on page 55)	Where Used table includes: Item Sites, Item Number, Item Description, Mfr. Tab Preferred Status, Mfr. Tab Reference Notes Pending Change Where Used table also includes: Pending Change
Attachments tab	Attachment Number, Attachment Description, File Name, File Version, File Size, File Type, Modified Date, Last View Date, Checkout User, Checkout Date, Checkout Folder	Attachments tab	Attachment Number, Attachment Description, File Name, File Version, File Size, File Type, Modified Date, Last View Date, Checkout User, Checkout Date, Checkout Folder
History tab	Action, User, Local Client Time, User Action Time (optional), Comments, Details	History tab	Action, User, Local Client Time, User Action Time (optional), Comments, Details
		Prices tab	This tab relates to Agile PCM. For more information, see the <i>Product Cost Management User Guide</i> .
		Compliance tab Suppliers tab	These tabs relate to Agile PG&C. For more information, see <i>Agile Product Governance and Compliance User Guide</i> .

Where Used Tab

The manufacturer Where Used tab lists all the manufacturer part numbers for the manufacturer and the items that use the manufacturer parts. The information on this tab is filled in automatically.

The manufacturer part Where Used tab lists all the items that use the manufacturer part. The information on this tab is filled in automatically.

The Where Used tab includes two tables:

- Where Used — displays the latest released revision of the items where the manufacturer part is used.
- Pending Change Where Used — displays the pending revisions of the items where the

manufacturer part is used, including the associated change order number.

To view or hide the Pending Change Where Used table:

Use the View drop-down list to select either Show Pending or Hide Pending.

Note	When you first view the Where Used tab, the Pending Change Where Used table is hidden by default.
------	---

To view an item from the Where Used tab using Java Client:

Double-click the item's row.

To view an item from the Where Used tab using Web Client:

Click the item number.

Sites and the Manufacturer Part Where Used Tab

When you view the Where Used tab of a manufacturer part, the table displays where-used information according to item number and manufacturing site. Click the Item Sites column header to sort the table by site.

See also: [How Sites Work](#) (on page 39).

Manufacturer Part Prices Tab

Note	If your company has the necessary licenses, and you have been granted the necessary privileges, you can perform the Prices tab processes described here.
------	--

The Prices tab displays the price information for this manufacturer part. The information on this tab is filled in automatically. Click the price object number (in the Number column) to open that price object. For more information see the *Product Cost Management User Guide*.

Where Used Tab and the Discovery Privilege

If you do not have Discovery privilege for an item, site, or manufacturing object, it does not appear on the Where Used tab. The Agile administrator can specify whether or not to display a warning message telling you how many objects are not displayed. (For sites, this applies only to the Where Used tab of manufacturer parts. The Where Used tab of manufacturers does not include a column for site information.) For more information, see [Details about Discovery and Read Privileges](#) (on page 183).

Read Privilege

Your Read and Enforce Field Level Read privileges determine which fields you are able to view. For more information, see [Details about Discovery and Read Privileges](#) (on page 183).

About Manufacturers

Manufacturer objects contain information about manufacturers with which your organization collaborates.

Creating a manufacturer is the first step in adding a new manufacturer part to the Agile PLM

database. After you create the manufacturer, create the manufacturer part in association with that manufacturer. When you then associate the manufacturer part with an item, the manufacturer part is referenced on the manufacturer's Where Used tab.

You can modify a manufacturer object directly at any time, if you have the necessary privileges. Manufacturers are not under change control.

To find manufacturers in your Agile PLM database, use the same search process as you use for any other object. For more information about searches, see *Getting Started with Agile PLM*.

See also: [Lifecycle Phase of a Manufacturer](#) (on page 57), [D-U-N-S Number](#) (on page 57).

Lifecycle Phase of a Manufacturer

The lifecycle phase field on the General Info tab of the manufacturer object indicates its lifecycle phase. The following table lists the default manufacturer lifecycle phases. The Agile administrator may define a customized list of lifecycles for your Agile PLM system.

Lifecycle name	Lifecycle definition
Approved	This is an approved manufacturer.
Disqualified	This manufacturer is no longer qualified for use.
Obsolete	This manufacturer is no longer available for use.

See also: [Lifecycle Phase of a Manufacturer Part](#) (on page 58).

D-U-N-S Number

The D-U-N-S Number field allows companies to list the DUNS of their suppliers in the system.

D-U-N-S stands for Data Universal Numbering System. A D-U-N-S number is a unique nine-digit sequence that identifies an organization.

See also: [Manufacturing Object Tabs](#) (on page 54).

About Manufacturer Parts

The manufacturer part object displays information about a part produced by a specific manufacturer, including the manufacturer's part number, lifecycle phase, where it is used, and a history of actions affecting that manufacturer part.

The combination of the manufacturer name and manufacturer part number must be unique to that manufacturer part. In other words, you cannot create another manufacturer part for the same manufacturer using the same manufacturer part number. Agile PLM does support the situation in which different manufacturers are using an identical part number, however.

You can modify a manufacturer part object directly at any time, if you have the necessary privileges. Manufacturer parts are not under change control.

To find manufacturer parts in your Agile PLM database, use the same search process as you use for any other object. For more information about searches, see *Getting Started with Agile PLM*.

After you create a manufacturer part, you can add it to the Manufacturers tab of the Agile part to which it corresponds. For more information about working with manufacturer parts, see [Creating and Managing Manufacturing Objects](#) (on page 58).

Lifecycle Phase of a Manufacturer Part

The lifecycle phase field on the General Info tab of the manufacturer part object indicates its lifecycle phase. The following table lists the default manufacturer part lifecycle phases. The Agile administrator may define a customized list of lifecycles for your Agile PLM system.

Lifecycle name	Lifecycle definition
Active	This manufacturer part is available for use.
Obsolete	This manufacturer part should no longer be used.



See also: [Lifecycle Phase of a Manufacturer](#) (on page 57).

Creating and Managing Manufacturing Objects

This section covers the following topics:

- [Creating Manufacturers](#) (on page 58)
- [Creating Manufacturer Parts](#) (on page 60)
- [Modifying Manufacturing Objects](#) (on page 66)

Creating Manufacturers

In Java Client, you can create an manufacturer with the File | New | Manufacturers command or with the New Object button , or the Save As command, on the More Actions menu (click the More button  at the top of the object window) and on the right-click shortcut menu.

In Web Client, you can create a manufacturer with the Create | Manufacturers command or the Actions | Save As command.

Unlike items, manufacturers do not need to go through the release process. They are immediately available for use.

Note	The manufacturer name must be unique to one manufacturer, just as an item number must be unique to an item.
------	---

Although different manufacturers can use the same manufacturer part number, the combination of manufacturer plus manufacturer part number must be unique to one manufacturer part.

The process for creating new objects involves two main steps: creating an empty object, then filling in the object tabs with information specific to the object.

To create and complete a manufacturer using Java Client:

1. Choose File | New | Manufacturers.
2. In the New dialog box, use the Type drop-down list to select the type (subclass) of manufacturer you want to create.
3. Type a unique name for the manufacturer.
4. Complete any required fields.



5. Click OK.


The new manufacturer appears with the General Info tab showing.

6. Fill in information on the manufacturer tabs, as desired.

You do not enter information on the Where Used and History tabs. Those tabs are completed automatically.

To create a manufacturer using Web Client:


1. Choose Create | Manufacturers.
2. In the New dialog box, use the Type drop-down list to select the type (subclass) of manufacturer you want to create.
3. Type a unique name for the manufacturer.
4. Complete any required fields.
5. To continue using the Create wizard to enter information on each tab of the manufacturer, check the Continue Creation in  Wizard checkbox, and click the Continue button. Follow the onscreen instructions to complete the wizard.
6. To create and display the manufacturer immediately, uncheck the Continue Creation in  Wizard checkbox and click Finish. The new manufacturer appears with the General Info tab showing. Fill in information on the manufacturer tabs, as desired.

Note	Agile PLM remembers your most recent selection for the Continue Creation in  Wizard checkbox in any create dialog and it remains preselected for you in the Create dialog box.
------	---

See also: [Modifying Manufacturing Objects](#) (on page 66).

Creating a Manufacturer Using the Save As Feature

Using the Save As feature is a quick way to create a manufacturer that is similar to an existing manufacturer.

In Java Client, you can create a manufacturer using the File | Save As command, the Save As command on the More Actions menu (click the More button  at the top of the object window) or the Save As command on the right-click shortcut menu.

In Web Client, you can create a manufacturer using the Actions | Save As command.

In general, you should not use Save As to create an object in a different class or subclass (type) from the original object. The different classes or subclasses may not have the same tabs or defined fields, and you may lose access to some data in the newly created object.

To create a manufacturer using the Save As command in Java Client:

1. Select and open an existing manufacturer.
2. Choose File | Save As.
3. If appropriate, select a different manufacturer type (subclass) from the list.
4. Enter the new manufacturer's name.
5. Complete any required fields.

6. Click OK.

The new manufacturer opens with the General Info tab on top.

To create a manufacturer using the Save As command in Web Client:


1. Select and open an existing manufacturer.
2. Choose Actions | Save As.
3. If appropriate, select a different manufacturer type (subclass) from the list.
4. Enter the new manufacturer's name.
5. Complete any required fields.
6. Click Save.

The new manufacturer opens with the General Info tab on top.

See also: [Modifying Manufacturing Objects](#) (on page 66).

Creating Manufacturer Parts

To create manufacturer parts, you must have the Create Manufacturer Parts privilege.

In Java Client, you can create an manufacturer with the File | New | Manufacturer Parts command or with the New Object button . You can also use the File | Save As command when open manufacturer part is open.

In Web Client, you can create a manufacturer part with the Create | Manufacturer Parts command. From an open manufacturer object, you can create a manufacturer part with the Actions | Create Manufacturer Parts command. You can also use the Actions | Save As command from an open manufacturer part.

You can also create a manufacturer part on-the-fly as you add information to the Manufacturers tab of an item.

Unlike items, manufacturer parts do not need to go through the release process. They are immediately available for use.

Note	Different manufacturers can use the same manufacturer part number; however, the combination of manufacturer plus manufacturer part number must be unique to one manufacturer part.
------	--

See also:

- [Manufacturer Part Creation Wizards](#) (on page 60)
- [Manufacturer Name Automatic Validation](#) (on page 63)
- [Creating a Manufacturer Part Using the Save As Feature](#) (on page 64)
- [Modifying Manufacturing Objects](#) (on page 66)

Manufacturer Part Creation Wizards

Wizards lead you through the process of creating a manufacturer part.

This section includes the topics:

- [Creating a Manufacturer Part in Java Client](#) (on page 61)
- [Creating a Manufacturer Part in Web Client](#) (on page 62)

See also: [Creating a Manufacturer Part Using the Save As Feature](#) (on page 64).

Creating a Manufacturer Part in Java Client

To create and complete a manufacturer part using Java Client:

1. Choose File | New | Manufacturer Part.
2. In the New dialog box, use the Type drop-down list to select the type (subclass) of manufacturer part you want to create.
3. Select the manufacturer of the new manufacturer part.

In the Manufacturer Name field, type the manufacturer name or a portion of the manufacturer name. Press the Tab key or click the Validate checkmark:

Java Client ☒, Web Client ☒

- If you enter a valid and unique manufacturer name, Agile selects that manufacturer name and the Validate checkmark is disabled. Press the Tab key to continue with the next step.
- If you did not enter a valid and unique manufacturer name, the resolution dialog appears.

In the resolution dialog, select the manufacturer you want and click OK.

If the manufacturer you want does not appear in the search results, you can perform another search or you can create a new manufacturer:

- Search – In the resolution dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited manufacturer (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.) In the search results, select the manufacturer you want, and click OK.
- Create – If you need to create a new manufacturer for the manufacturer part, click the Create link in the Select Objects dialog box. A dialog box opens that allows you to select the manufacturer type (subclass) in the Type drop-down list and enter the manufacturer name. Click OK. The resolution dialog box closes and the newly created manufacturer is selected.

For further details, see [How to Use Manufacturer Name Automatic Validation](#) (on page 63).

Type a number for the manufacturer part.

4. Complete any required fields.
5. Click OK.

The new manufacturer part appears with the General Info tab showing.

6. Fill in information on the manufacturer part tabs, as desired.

You do not enter information on the Where Used and History tabs. Those tabs are completed automatically.

Creating a Manufacturer Part in Web Client

To create a manufacturer part using Web Client:

1. Choose Create | Manufacturer Part. (You can also choose Actions | Create Manufacturer Part from within a manufacturer.)
2. In the New dialog box, use the Type drop-down list to select the type (subclass) of manufacturer part you want to create.
3. Select the manufacturer of the new manufacturer part.

In the Manufacturer Name field, type the manufacturer name or a portion of the manufacturer name. Press the Tab key or click the Validate checkmark:

Java Client ☐, Web Client ☒



- If you enter a valid and unique manufacturer name, Agile selects that manufacturer name and the Validate checkmark is disabled. Press the Tab key to continue with the next step.
- If you did not enter a valid and unique manufacturer name, the resolution dialog appears.


In the resolution dialog, select the manufacturer you want and click OK.

If the manufacturer you want does not appear in the search results, you can perform another search or you can create a new manufacturer:

- Search – In the resolution dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited manufacturer (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.) In the search results, select the manufacturer you want, and click OK.
- Create – If you need to create a new manufacturer for the manufacturer part, click the Create link in the Select Objects dialog box. A dialog box opens that allows you to select the manufacturer type (subclass) in the Type drop-down list and enter the manufacturer name. Click OK. The resolution dialog box closes and the newly created manufacturer is selected.

For further details, see [How to Use Manufacturer Name Automatic Validation](#) (on page 63).

4. Type a number for the manufacturer part.
5. Complete any required fields.
6. To continue using the Create wizard to enter information on each tab of the manufacturer part, check the Continue Creation in  Wizard checkbox, and click the Continue button. Follow the onscreen instructions to complete the wizard.
7. To create and display the manufacturer part immediately, uncheck the Continue Creation in  Wizard checkbox and click Finish. The new manufacturer part appears with the General Info tab showing. Fill in information on the manufacturer part tabs, as desired.

Note Agile PLM remembers your most recent selection for the Continue Creation in  Wizard checkbox in any create dialog and it remains preselected for you in the Create dialog box.

You do not enter information on the Where Used and History tabs. Those tabs are completed automatically.

Manufacturer Name Automatic Validation

Whenever you create a manufacturer part, or add to or edit the table of an item's Manufacturers tab, Agile PLM provides an automatic search and validation process to quickly search for and select the manufacturer you want to specify.





This section includes the topics:

- [Where is Manufacturer Name Automatic Validation Used?](#) (on page 63)
- [How to Use Manufacturer Name Automatic Validation](#) (on page 63)





Where is Manufacturer Name Automatic Validation Used?

Agile PLM uses automatic manufacturer name validation whenever you create a manufacturer part or you edit manufacturer part information.

With the appropriate privileges, you can create a manufacturer part by using the following Agile PLM features:

- Object Create
 - Java Client: File | New | Manufacturer Part or choose  More | New Manufacturer Part from
 - Web Client: Create | Manufacturer Part or choose Actions | Create Manufacturer Part from within a manufacturer.
- Item object Manufacturers tab, Add | Create button. 
- Change object Affected Items tab, Redline Manufacturers tab, Add | Create button. 
- Change object Affected Items tab, manufacturer part bulk change process: (Java Client) Manufacturer Part Bulk Change , (Web Client) Bulk Change | Manufacturer Part.

With the appropriate privileges, you can edit manufacturer part information by using the following Agile PLM features:

- Item object Manufacturers tab, Edit button. 
- Change object Affected Items tab, Redline Manufacturers tab, Edit button: (Java Client) , (Web Client) 
- Change object Affected Items tab, manufacturer part bulk change process: (Java Client) Manufacturer Part Bulk Change , (Web Client) Bulk Change | Manufacturer Part.

How to Use Manufacturer Name Automatic Validation

Whenever manufacturer name automatic validation is used, follow these steps:

1. In the Manufacturer Name field of the create or edit dialog, type the name of the manufacturer or a portion of the name for which you want to search.



If you enter a valid and unique manufacturer name, Agile selects that manufacturer name and the Validate checkmark is disabled. Press the Tab key to move to the next field in the dialog.

Note	You may leave the Manufacturer Name field blank. When the resolution dialog appears, use the search options to search for the manufacturer you want or create a new manufacturer.
------	---

For example, if you want to find the manufacturer name Motorola, you can type any of the following text strings to begin your search. Agile performs a Starts With search for any manufacturer name that starts with the letters you typed.

mot
motorla
mo

Note Agile automatically adds an asterisk character * to the end of the text string.

2. When you move the cursor out of the Manufacturer Name field, the validation process begins and the validation dialog appears. You can move the cursor out of the name field using any of the following methods:
 - Press the Tab key.
 - Click the Validate checkmark in the Manufacturer Name field: Java Client , Web Client .
 - Click another field in the dialog.
 - Attempt to exit the edit dialog by clicking OK (Java Client) or Save (Web Client).
 - Attempt to exit the create dialog by clicking OK (Java Client), or Continue or Finish (Web Client).
3. In the resolution dialog, select a manufacturer name in the search results and click OK. The resolution dialog closes and the selected manufacturer name appears in the Manufacturer Name field of the create or edit dialog.

If the manufacturer name you want does not appear in the search results, you can:

- Run another search.

Select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.)
- Create a new manufacturer object.

Click the Create button in the resolution dialog to create a manufacturer object; see [Creating Manufacturers](#) (on page 58).

See also: [Where is Manufacturer Name Automatic Validation Used?](#) (on page 63)

Creating a Manufacturer Part Using the Save As Feature

Using the Save As feature is a quick way to create a manufacturer part that is similar to an existing manufacturer part.

Note In general, you should not use Save As to create an object in a different class or subclass (type) from the original object. The different classes or subclasses may not have the same tabs or defined fields, and you may lose access to some data in the newly created object.

To create a manufacturer part using the Save As command in Java Client:

1. Select and open an existing manufacturer part.

2. Choose File | Save As.
3. If appropriate, select a different manufacturer part type (subclass) from the list.
4. Select the manufacturer of the new manufacturer part.

Note If you want to use the same manufacturer, you do not need to modify the Manufacturer Name field.

In the Manufacturer Name field, type the manufacturer name or a portion of the manufacturer name. Press the Tab key or click the Validate checkmark:

Java Client , Web Client 

- If you enter a valid and unique manufacturer name, Agile selects that manufacturer name and the Validate checkmark is disabled. Press the Tab key to continue with the next step.
- If you did not enter a valid and unique manufacturer name, the resolution dialog appears.

In the resolution dialog, select the manufacturer you want and click OK.

If the manufacturer you want does not appear in the search results, you can perform another search or you can create a new manufacturer:

- **Search** – In the resolution dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited manufacturer (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.) In the search results, select the manufacturer you want, and click OK.
- **Create** – If you need to create a new manufacturer for the manufacturer part, click the Create link in the Select Objects dialog box. A dialog box opens that allows you to select the manufacturer type (subclass) in the Type drop-down list and enter the manufacturer name. Click OK. The resolution dialog box closes and the newly created manufacturer is selected.

For further details, see [How to Use Manufacturer Name Automatic Validation](#) (on page 63).

Enter the new manufacturer part number.

5. Complete any required fields.
6. Click OK.

The new manufacturer part opens with the General Info tab on top.


7. Make any necessary modifications to the other tabs.

To create a manufacturer part using the Save As command in Web Client:

1. Select and open an existing manufacturer part.
2. Choose Actions | Save As.
3. If appropriate, select a different manufacturer part type (subclass) from the list.
4. Select the manufacturer of the new manufacturer part.

Note If you want to use the same manufacturer, you do not need to modify the Manufacturer Name field.

In the Manufacturer Name field, type the manufacturer name or a portion of the manufacturer name. Press the Tab key or click the Validate checkmark:

Java Client , Web Client 

- If you enter a valid and unique manufacturer name, Agile selects that manufacturer name and the Validate checkmark is disabled. Press the Tab key to continue with the next step.
- If you did not enter a valid and unique manufacturer name, the resolution dialog appears.

In the resolution dialog, select the manufacturer you want and click OK.

If the manufacturer you want does not appear in the search results, you can perform another search or you can create a new manufacturer:

- Search – In the resolution dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited manufacturer (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.) In the search results, select the manufacturer you want, and click OK.
- Create – If you need to create a new manufacturer for the manufacturer part, click the Create link in the Select Objects dialog box. A dialog box opens that allows you to select the manufacturer type (subclass) in the Type drop-down list and enter the manufacturer name. Click OK. The resolution dialog box closes and the newly created manufacturer is selected.

For further details, see [How to Use Manufacturer Name Automatic Validation](#) (on page 63).

Enter the new manufacturer part number.

5. Complete any required fields.
6. Click Save.

The new manufacturer part opens with the General Info tab on top.

7. Make any necessary modifications to the other tabs.

See also: [Creating a Manufacturer Part in Java Client](#) (on page 61), [Creating a Manufacturer Part in Web Client](#) (on page 62).

Modifying Manufacturing Objects

Any user with the necessary privileges and licenses can modify information about a manufacturing object. Manufacturing objects are not required to go through the change control process; all modifications go into effect immediately.

Caution If you change a manufacturer part number or manufacturer name, these changes are automatically made to the Manufacturers tab of the items where the manufacturer or manufacturer part is listed and to any other tabs where the manufacturer is listed, such as the Where Used tab.

See also: [Creating Manufacturers](#) (on page 58), [Creating Manufacturer Parts](#) (on page 60).

Deleting Manufacturing Objects

For important details about deleting manufacturing objects, see [Deleting Agile Objects](#) (on page 23).

Manufacturers Tab of an Item

This section includes the following topics:







- [Manufacturers Tab Buttons](#) (on page 67)
- [Manufacturers Tab Fields](#) (on page 67)

The Manufacturers tab displays information taken from related manufacturing objects. For more information, see [Manufacturers Tab](#) (on page 9).

See also: [Working with Manufacturing Data on Preliminary Items](#) (on page 69), [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).

Manufacturers Tab Buttons


The following table lists the buttons on the Manufacturers tab of an item.

Button	Description
 Edit (Java Client)	Lets you edit the AML row by displaying the selected rows in edit mode. The editable fields are in the form of text boxes, list boxes, and so on.
 Edit (Web Client)	
 Remove (Java Client)	Removes the selected rows from the table.
 Remove (Web Client)	
 Add Create (Java Client) Add Create New (Web Client)	Adds a manufacturer part at the end of the table. It can be an existing manufacturer part or one you create while adding it. (Use the button drop-down list to choose either the Search or Create add method.) You can use this button if there is no ECO or MCO created against the item.
 Add Search	

See also: [Working with Manufacturing Data on Preliminary Items](#) (on page 69).

Manufacturers Tab Fields

The following table lists the default fields on the Manufacturers tab of an item. The Agile administrator may have created additional fields.

Field name	Description
	Has Attachment The appearance of this icon indicates that the manufacturer part has an attachment. Click this icon to open the manufacturer part with its Attachments tab displayed.
Mfr. Name	The name of the manufacturer.
Mfr. Part Number	The number assigned to the manufacturer part by the part's manufacturer.
Mfr. Part Description	The description assigned to the manufacturer part by the part's manufacturer.

Field name	Description
Mfr. Part Lifecycle Phase	Indicates whether the manufacturer is an active manufacturer of the part.
Preferred Status	Indicates whether the manufacturer is preferred or an alternate for this part.
Sites	Lists the sites that use the manufacturer part.
Reference Notes	Notes about the manufacturer.
AML Split (visible only if the Agile administrator has enabled it)	Lets you define the percentage allocated for the manufacturer part at the selected site.

See also: [Working with Manufacturing Data on Preliminary Items](#) (on page 69), [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72), [Viewing AML Information by Site](#) (on page 68).

Viewing AML Information by Site

You can view the AML for a specific site by selecting a site from the Site drop-down list above the tabs. Sites included in the list are the ones specified on the item's Sites tab that are also listed in the Sites field of your user profile.

When you select a site, the Manufacturers tab displays the common AML plus the AML of the site you selected. To view the AML for all sites at once, select ALL in the Site list.

You can perform actions only on the items associated with the selected site. For example, if you select San Francisco in the Site drop-down list, you see all manufacturer parts that are part of the common and San Francisco portions of the AML.

The Rev and Site drop-down lists work independently. For more details, see [Working with Item Revisions](#) (on page 13).

Associating a Manufacturer Part with Its Corresponding Item

After you have created a manufacturer and a manufacturer part, you associate them with a part in the Agile PLM system. You do this by adding the manufacturer part to the Manufacturers tab of the Agile part only for preliminary items. Otherwise, this requires a change through an MCO, ECO, or SCO. This establishes the link between “your” part and “their” part, which makes it possible to track their part's use throughout the system.

You can list more than one manufacturer part from the same manufacturer, or from more than one manufacturer. For example, if a manufacturer makes two parts that you sometimes use for that assembly, you can mark one as Preferred and the other as Alternate. (You can do the same thing if two different manufacturers supply a part.)

Note	If you want a manufacturer part to apply to a specific site, before adding the manufacturer part to the Manufacturers tab, select that site from the Site drop-down list above the tabs.
------	--

Depending on the state of an item (and your licenses and privileges), you can modify Manufacturers tab data by one of these methods:

- Add or modify directly on the Manufacturers tab of items. This method is for preliminary items with no pending ECOs or MCOs. See [Adding a Manufacturer Part to the Manufacturers Tab](#) (on page 69).
- Use an ECO, MCO, or SCO to modify manufacturing data on the redlines tab. This method is for released items or items with pending ECOs or MCOs. See [Adding a Manufacturer Part on the Redline Manufacturers Tab](#) (on page 74).

Important Considerations When Working with Manufacturing Objects

Once a manufacturing object has been used on an item's Manufacturers tab, any alterations you make to the manufacturing object are also made on that item's Manufacturers tab. Because manufacturing objects are not required to go through the change control process, all modifications that are made go into effect immediately. Because these alterations are not made by means of a change, they won't be passed to the ERP system by ChangeCAST or Agile Content Service. To avoid potential problems between the Agile PLM and ERP systems, it is important to bear this in mind when making changes to any manufacturing object that is in use on an item's Manufacturers tab.

See also: [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).

Working with Manufacturing Data on Preliminary Items




The following sections describe how to modify data directly on the Manufacturers tab of an item has not been released and does not have a pending revision:


- [Adding a Manufacturer Part to the Manufacturers Tab](#) (on page 69)
- [Deleting a Manufacturer Part from the Manufacturers Tab](#) (on page 71)
- [Modifying a Manufacturer Part on the Manufacturers Tab](#) (on page 71)

Adding a Manufacturer Part to the Manufacturers Tab




You can add manufacturer parts to the Manufacturers tab of an item.


To add a manufacturer part to the Manufacturers tab in Java Client:

1. On the Manufacturers tab, select the site for which you want to add the manufacturer part from the Site drop-down list.
2. In the Add button drop-down list, choose either Add | Create  or Add | Search .
3. If you chose Add | Create :
 - a. Fill in the required information in the New dialog box. See [Creating Manufacturers](#) (on page 58).

- If you enter information for a manufacturer part that already exists, Agile displays a prompt asking if you want to use the existing manufacturer part when you click OK in step c.
- b. If you have not already done so, select the site to which you want to associate the manufacturer part for this item. Select Common if you want to associate the manufacturer part with this item for all sites assigned to this item.
 - c. Click OK.
4. If you chose Add | Search  :
 - a. In the Select Objects dialog box, select a search method to search for an existing manufacturer part, or select a bookmarked or recently visited manufacturer part (Shortcuts). If you choose to perform a simple search, enter the value to search for. (For more information about searches, see *Getting Started with Agile PLM*.)
 - b. If you have not already done so, select the site to which you want to associate the manufacturer part for this item. Select Common if you want to associate the manufacturer part with this item for all sites assigned to this item.
 - c. Click OK.

To add a manufacturer part to the Manufacturers tab in Web Client:


1. On the Manufacturers tab, select the site for which you want to add the manufacturer part from the Site drop-down list.
2. In the Add button drop-down list, choose either Add | Create New  or Add | Search .
3. If you chose Add | Create New  :
 - a. Fill in the required information in the New dialog box. See [Creating Manufacturers](#) (on page 58).

If you enter information for a manufacturer part that already exists, Agile displays a prompt asking if you want to use the existing manufacturer part when you click OK in step c.
 - b. If you have not already done so, select the site to which you want to associate the manufacturer part for this item. Select Common if you want to associate the manufacturer part with this item for all sites assigned to this item.
 - c. Click OK.
4. If you chose Add | Search  :
 - a. In the Add Manufacturer Parts dialog box, select a search method to search for an existing manufacturer part, or select a bookmarked or recently visited manufacturer part (Shortcuts). If you choose to perform a simple search, enter the value to search for. (For more information about searches, see *Getting Started with Agile PLM*.)
 - b. If you have not already done so, select the site to which you want to associate the manufacturer part for this item. Select Common if you want to associate the manufacturer part with this item for all sites assigned to this item.
 - c. Click OK.

See also: [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).


Deleting a Manufacturer Part from the Manufacturers Tab

To delete a manufacturer part from the Manufacturers tab of an item still in the Preliminary state in Java Client:

1. On the Manufacturers tab, select the manufacturer part row to be deleted.
2. Click the Remove button  on the Manufacturers tab.

Note Be sure to use the Remove button on the Manufacturers tab, not the Delete button in the item window. If you use the Delete button, the entire item is deleted.

To delete a manufacturer part from the Manufacturers tab of an item still in the Preliminary state in Web Client:

1. On the Manufacturers tab, select the manufacturer part row to be deleted.
2. Click the Remove  button on the Manufacturers tab.


Note Be sure to use the Remove button on the Manufacturers tab, not the Delete button in the item window. If you use the Delete button, the entire item is deleted.

See also: [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).


Modifying a Manufacturer Part on the Manufacturers Tab

You can directly edit manufacturer part information from the Manufacturers tab of an item if the item is in the preliminary state, has never been released, and has no pending ECOs or MCOs against it.

To edit values for a manufacturer part in Java Client:

1. Open the item to be edited.
2. On the Manufacturers tab, select the rows that you want to edit.
3. Click the Edit button , and change the data as necessary in the Edit dialog box.
You can use the navigation buttons in the open Edit dialog box to select other rows to edit.
4. Click OK.

To edit values for a manufacturer part in Web Client:

1. Open the item to be edited.
2. On the Manufacturers tab, select the rows that you want to edit.
3. Click  Edit, and change the data as necessary.
4. Click Save.

See also: [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).

Modifying Manufacturing Data from the Redlines Tab

If you have the appropriate privileges and Agile system SmartRule settings allow it, you can modify AML information through the Redline Manufacturers tab of an ECO, MCO, or SCO.

This section contains the following topics:

- [Overview of Redlining Manufacturing Data](#) (on page 72)
- [Redline Manufacturers Tab](#) (on page 72)
- [Adding a Manufacturer Part on the Redline Manufacturers Tab](#) (on page 74)
- [Adding Nonexistent Manufacturer Parts on the Redlines Tab](#) (on page 74)
- [Deleting a Manufacturer Part from the Redlines Tab](#) (on page 74)
- [Editing Manufacturer Part Information on the Redline Manufacturers Tab](#) (on page 74)
- [Undoing Changes to the Redline Manufacturers Tab](#) (on page 76)

Overview of Redlining Manufacturing Data

On some systems, depending on how the Agile administrator has configured settings, you can make redline changes from ECOs, SCOs, and MCOs. MCOs can redline only manufacturer parts data; ECOs can redline manufacturer parts data, BOMs, and attachments; SCOs can redline manufacturer parts data and BOMs for specific sites only.

MCOs and SCOs do not advance, or roll, the revisions of the affected items; ECOs do.

Redlining manufacturing data from an ECO or SCO is the same as the process from an MCO. However, because you can use ECOs to redline manufacturing data, BOMs, or attachments, the ECO redlines include a Redline BOM tab, a Redline Manufacturers tab, and an Redline Attachments tab. The SCO redlines include a Redline BOM tab and a Redline Manufacturers tab.

Note	If a change includes conflicting redlines made from multiple manufacturing sites, those conflicting redlines are removed from the BOM and Manufacturers table for all associated sites.
------	---

For more information about changes, see the chapter [Changes](#) (on page 111).

Redline Manufacturers Tab

You display the Redline Manufacturers tab from the Affected Items tab of an ECO, MCO, or SCO.






To open the redlines for an item's AML in Java Client:

1. Open the change through which you want to redline an item's AML.
2. In the Affected Items table, select the item you want to redline.



The View drop-down list has two settings: Hide Sites and Show Sites. When you select Hide Sites, the items are listed once on the Affected Items table. When you select Show Sites, the

items are listed multiple times, once for each site. Simply select one row in the table; if needed, you can select a different site setting on the Redline Manufacturers tab.

3. In the bottom pane of the Affected Items tab, display the Redline Manufacturers tab.
4. In the Site drop-down list, select the site for which you want to redline manufacturer part information. Select ALL to redline manufacturer part information for all the item's sites.
5. Select a row in the Redline Manufacturers table and use the buttons to make the modifications you want. See the following table for details.

Java Client button	Action
Redline Manufacturer 	Displays the selected row in the Redline Manufacturer dialog box so that you can redline editable fields. Use the buttons in the upper left corner to view and edit other rows in the table. Click OK when you are finished.
 Add Create  Add Search	Lets you redline-add a manufacturer part to the item.
Remove 	Redline-deletes the selected rows from the Redline Manufacturers table.
Undo Redlines 	Clears the redlines from the selected rows. See Undoing Changes to the Redline Manufacturers Tab (on page 76).






To open the redlines for an item's AML in Web Client:

1. Open the change through which you want to redline an item's AML.
2. On the Affected Items tab of the change, click the Do Redlining  icon in front of the item for which you want to view or create redlines. If the item has already been redlined, click the  icon to view the redlines or to create additional redlines.

The redline tabs for this item are displayed.

3. Click the Redline Manufacturers tab to display it, if it is not displayed.

Select a row in the Redline Manufacturers table and use the buttons to make the modifications you want. See the following table for details.


Web Client button	Action
 Edit	Displays the selected rows in edit mode so that you can redline editable fields.
 Delete	Redline-deletes the selected rows from the Redline Manufacturers table.
 Undo Redlines	Clears the redlines from the selected rows. See Undoing Changes to the Redline Manufacturers Tab (on page 76).
 Add Create New  Add Search	Lets you redline-add a manufacturer part to the item.

If a row in the table has a red line through every cell, it means that manufacturer part was deleted from the Manufacturers table. If just a few of the cells have a short red line through them, it means the manufacturer part was modified. Any cell that was modified has a red line through the old value; the new value appears in red.



See also: [Changes](#) (on page 111), [Affected Items of Changes](#) (on page 131).

Adding a Manufacturer Part on the Redline Manufacturers Tab

To add a manufacturer part to the Redline Manufacturers tab:

1. Follow the instructions in [Redline Manufacturers Tab](#) (on page 72).
2. When the Manufacturers Redline tab is displayed, use the Add button drop-down list to choose Add | Search  to search for a manufacturer part.
3. Continue as described in [Adding a Manufacturer Part to the Manufacturers Tab](#) (on page 69).

Adding Nonexistent Manufacturer Parts on the Redlines Tab


Use the Add button drop-down list to choose Add | Create  (Java Client) or Add | Create New  (Web Client) to create a new manufacturer part to add to the Manufacturers tab. If you use this option, you must also select a manufacturer from a list of existing manufacturers or, if needed, create a new manufacturer. See [Adding a Manufacturer Part to the Manufacturers Tab](#) (on page 69).

Deleting a Manufacturer Part from the Redlines Tab


Redline-deleting a manufacturer part has these behaviors:

- If the selected row is red, redline-deleting it removes the row.
- If the selected row is black, redline-deleting it puts a red line through the row.

To delete a manufacturer part in Java Client:

1. Select the row to delete.
2. Click the Remove button  on the Redline Manufacturers tab.

To delete a manufacturer part in Web Client:

1. Select the row to delete.
2. Click the  Delete button on the Redline Manufacturers tab.

See also: [Overview of Redlining Manufacturing Data](#) (on page 72).

Editing Manufacturer Part Information on the Redline Manufacturers Tab

An item's AML (approved manufacturers list) is represented by the rows of information on the item object Manufacturers tab. Each row in AML table represents a manufacturer part. If the item has not

yet been released, you can edit this table on the item Manufacturers tab, for example, add or remove manufacturer parts, modify editable fields, including any editable custom fields that the Agile administrator has enabled. Your assigned roles and privileges determine which AML table fields you are allowed to edit. See [Modifying a Manufacturer Part on the Manufacturers Tab](#) (on page 71).

If the item has been released or has a pending revision, you must use the Redline Manufacturers tab to modify the item's AML (Manufacturers tab). You display the Redline Manufacturers tab from the Affected Items tab of an ECO or MCO.

On the Redline Manufacturers tab you can make the same modifications that you are allowed to make on an unreleased item's Manufacturers tab, including modifying any editable custom fields that the Agile administrator has enabled.

If the Agile administrator has enabled them, the item Manufacturers tab may also include *read-through* fields that display additional information derived from the manufacturer object or the manufacturer part object, for example, the manufacturer address fields or the manufacturer part Page Two fields. On both the item Manufacturers tab and the Redline Manufacturers tab, a read-through field contains a read-only copy of attribute data from a manufacturer or manufacturer part.


Note You cannot use the item Manufacturers tab or Redline Manufacturers tab to modify the read-through fields nor to modify the attributes of the manufacturer part objects. The Manufacturers tab and Redline Manufacturers tab are used only for defining the item's AML – the relationship between the item and the manufacturer parts.

To modify the attributes of a manufacturer or manufacturer part, you must open the manufacturer or manufacturer part and then modify it with the edit feature. See [Modifying Manufacturing Objects](#) (on page 66).


For more information about read-through fields and about which fields are editable on the item Manufacturers tab, see the *Administrator Guide*.

Note Your assigned roles and privileges also determine which attributes you are allowed to edit.

To edit a field on the redlines tab in Java Client:

1. Select one or more rows to edit, and click the Redline Manufacturer button .
2. In the Redline Manufacturers dialog box, make the required changes in the fields. Use the buttons in the upper left corner to display and edit other rows in the table.
3. When you are finished, click OK.

To edit a field on the redlines tab in Web Client:

1. Select one or more row, and click  Edit.
The row information is in edit mode.
2. Make the required changes in the fields.
3. Click Save.

Agile PLM draws a red line through the old information and enters the new information, in red, below the old information.

See also: [Changes](#) (on page 111), [Affected Items of Changes](#) (on page 131).

Undoing Changes to the Redline Manufacturers Tab

The Undo Redlines button lets you undo modifications to the redlines tab. The Undo Redlines button removes the red elements from the selected rows.

To undo a deletion (where Agile PLM has drawn a red line through the entire row):

1. Select a deleted row.
2. Click the Undo Redlines button.

(In Java Client: )

To undo a modification (where Agile PLM has drawn a short red line through the modified value):


1. Select the modified row.
2. Click the Undo Redlines button.

(In Java Client: )

See also: [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).

Printing Manufacturing Objects and AMLs

You can print object tabs and other data from your Agile PLM system. You can print the current tab or all tabs. Attachments are printed from their native applications or the Viewer.

In Java Client, with the object open, use the Print button .

In Web Client, with the object open, choose Actions | Print.

For additional information about printing objects, see *Getting Started with Agile PLM*.

Bills of Material

This chapter includes the following:

▪ About Bills of Material	77
▪ BOM Tab	77
▪ Common and Site-specific Portions of the BOM	81
▪ Viewing BOMs by Site	82
▪ Opening Items on a BOM	82
▪ Revisions Listed on BOMs	86
▪ About Modifying the BOM Table	86
▪ Working with Reference Designators	96
▪ Redlining the BOM of a Released Item	104
▪ Printing BOM Data	110

About Bills of Material

A bill of material (BOM) is a listing of all the subassemblies, parts, and raw materials that go into a parent assembly. It shows the quantity of each part required to make an assembly. Items on a BOM can be single items or assemblies of several items.

Documents may or may not have BOMs, depending on your system settings.

BOM items can apply to all manufacturing sites where the product is built, some sites, or just one site. The common portion of the BOM lists all the parts that the assembly shares between sites. Each site can add other objects to the BOM table that are site-specific—for example, documents containing assembly instructions that are specific to how something is built at that site. When you select Show Sites on the BOM tab, BOM items used by multiple sites are listed multiple times on the BOM tab, once for each site.

See also: [Sites and Distributed Manufacturing](#) (on page 35).




BOM Tab

This section includes the following topics:

- [How the Agile Administrator Controls What You See](#) (on page 78)
- [BOM Tab Buttons](#) (on page 78)
- [BOM Table Fields](#) (on page 80)

The BOM tab lists all the items on a BOM.

The BOM table displays the items on the BOM in a graphical hierarchy, using icons to indicate whether an item number represents:

-  A part
-  A document
-  An assembly

How the Agile Administrator Controls What You See

The Agile administrator may assign to you:

- Discovery privileges, which determine and limit which Agile objects you can find, or discover, in the Agile PLM database.
- Read privileges, which determine and limit which discovered Agile objects you can open and read and which specific fields you can view on the Agile objects that you can open and read.
- Sites, which determine and limit the site-specific information you can see and modify on BOMs and AMLs.

If you do not have the Discovery privilege for an item, that item may not be displayed on the BOM table, depending on which SmartRule setting the Agile administrator has selected. For the BOM table only, the SmartRule setting is also applied to the fields for which you do not have Read privilege.

The items on the BOM for which you do not have Discovery privilege and the fields on the BOM table for which you do not have Read privilege are indicated by one of the following methods:

- Only the item number and rev are displayed on the BOM table. You cannot open the item if you do not have Discovery privilege.
- Only the item description is displayed on the BOM table. You cannot open the item if you do not have Discovery privilege.
- The item is not displayed on the BOM table. A message at the top of the BOM table tells you how many items have not been displayed.

There is no indicator for inaccessible site information.

If you have questions about your Discovery or Read privileges or the sites assigned to you, see the Agile administrator.

See also: [Opening Items on a BOM](#) (on page 82).


BOM Tab Buttons

This section includes the topics:















- [Java Client BOM Tab Buttons](#) (on page 79)
- [Web Client BOM Tab Buttons](#) (on page 79)

See also: [BOM Table Fields](#) (on page 80).

Java Client BOM Tab Buttons

You can print, send, export, and perform other activities from the BOM tab. Use the buttons on the top of the object window, including the More Actions menu (click the More button ). Or, right-click in the item window to open the shortcut menu, and choose the command you want.

The following table explains the BOM tab buttons that appear in Java Client.













Button	Description
	Go To — Finds and highlights a specific BOM item based on the criteria you enter in the Go To dialog box. The Go To search can be limited to a particular BOM column and to the specified number of levels. For example, specifying level 3 searches through levels 1, 2, and 3.
	Expand Tree or Collapse All — Select from menu. Expands or collapses all the subassemblies in the BOM. When expanded, all levels of the BOM are displayed.
	Edit — Allows you to edit the a row in the BOM. You can edit the find number, quantity, reference designator and BOM notes. This button is available for introductory items that are not yet released, and have no changes pending against them.
   	Add — Adds an item or an empty row to the BOM table. Depending on which option you choose, you can:  Create an item while adding it.  Search for an existing item.  Type in Known Number(s) of one or more existing items.  Add Blank Row — adds a blank row to the BOM table that can be filled in later. By default, the new item or row has a find number of zero (0) and a quantity of one (1).
	Remove — Removes the selected rows from the BOM table.
	View Redline — Opens the change that released this revision of the item, and displays the Affected Items tab and redline tabs. This button is disabled on pending revisions.
	Select a BOM Item — double-click in a blank row with this symbol to select or create an item number to fill in the blank row.

See also: [BOM Table Fields](#) (on page 80), [Web Client BOM Tab Buttons](#) (on page 79).

Web Client BOM Tab Buttons

The following table explains the BOM tab buttons that appear in Web Client.


Note	The Actions menu lets you print, email, export, and perform other activities from the BOM tab.
------	--




Button	Description
 Edit	Lets you redline the BOM by displaying the selected rows on an Edit page. The editable fields are in the form of text boxes, list boxes, and so on.
 Remove	Removes the selected rows from the BOM table.
 Add  Add  Add  Add	<p>Add — Adds an item or an empty row to the BOM table. Depending on which option you choose, you can:</p> <ul style="list-style-type: none">  Create an item while adding it.  Search for an existing item.  Type in Known Number(s) of one or more existing items.  Add Blank Row — adds a blank row to the BOM table that can be filled in later. <p>By default, the new item or row has a find number of zero (0) and a quantity of one (1).</p>
Multi-level... Expand Collapse	<p>Multi-level Expand expands all the subassemblies in the BOM. All levels of the BOM are displayed.</p> <p>Multi-level Collapse collapses all expanded BOM levels. Only the top level of the BOM is displayed.</p>
Go To	<p>Takes you to a specific BOM item based on the criteria you enter in the Go To dialog box.</p> <p>The Go To search can be limited to a particular BOM column and to the specified number of levels. For example, specifying level 3 searches through levels 1, 2, and 3.</p>
	Click this symbol to create a new item to fill in the blank row.
 Show BOM Tree	<p>Displays the BOM tree in the navigation pane to the left of the object page. You can expand and collapse subassemblies and click any item number to open that item. This button appears above the item tabs and is always visible, regardless of which tab is displayed.</p> <p>The BOM tree view does not automatically refresh to match the BOM table. For example, if you expand the BOM table, the BOM tree in the navigation pane remains collapsed until you use the BOM tree controls.</p>

See also: [BOM Table Fields](#) (on page 80), [Java Client BOM Tab Buttons](#) (on page 79).

BOM Table Fields

BOM table fields and icons appear as listed in the following table.

Field name	Description
	<p>Has Attachment</p> <p>The appearance of this icon indicates that the item has an attachment.</p> <p>Click this icon to open the BOM item with its Attachments tab displayed.</p>

Field name	Description
	The appearance of this icon indicates that the item contains manufacturing data. Click this icon to open the BOM item with its Manufacturers tab displayed.
	The appearance of this icon indicates that the item has a pending change. Click this icon to open the BOM item with its Changes tab displayed.
Item Number	The Item Number field contains the item's number. Click an item number to open that item page.
	The appearance of this icon indicates that the item has a PSR (Product Service Request) or QCR (Quality Change Request) that is not closed. Click this icon to open the BOM item with its Quality tab displayed.
Item Description	The Item Description field contains the description of that item.
Item Rev	The Item Rev field shows the revision number of the BOM item. The latest released revision is displayed.
Qty	The Qty field shows the quantity of that item used in the assembly or subassembly.
Find Num	The Find Num field shows the internal number used to locate that item in an Agile BOM.
Ref Des	The Ref Des field contains the reference designators.
Sites	The Sites field shows which manufacturing site the item is associated with. Items associated with multiple sites are listed on the BOM once per site.
BOM Notes	The BOM Notes field contains notes about the item.

Note The Effective From date is different from the Rev Release Date field on the Title Block tab. The rev release date is the release date of the ECO that released the current revision of the item.

Common and Site-specific Portions of the BOM

If your company is using distributed manufacturing, the BOM table may include both common portions and site-specific portions. The sites listed on an item's Sites tab determine whether or not the item can be added to the common or site-specific portions of the BOM table.

In order to appear on common portion of the BOM table, an item's Sites tab must include all the sites that appear on the parent item assembly's Sites tab. For example, parent assembly 4444 includes the sites India and San Jose on its Sites tab. Items added to the common portion of the BOM table must also include at least India and San Jose on their Sites tab. If these items include additional sites on their Sites tab it does not prevent them from being included on the common portion of the BOM table of assembly 4444.

In a similar manner, items added to a site-specific portion of the BOM table must include at least that site on their Sites tab. For example, in order to be included on the India site-specific portion of

the BOM table, items must include at least India on their Sites tab. If these items include additional sites on their Sites tab, it does not prevent them from being included in the India portion of the BOM table of assembly 4444.

Items that appear on the top level of the BOM must adhere to these rules. Items that appear on the BOM tables of subassemblies must appropriately match the sites list of their own parent item, but they do not need to match the top assembly item's site list.

Important When you are creating or modifying a BOM table (adding by Search or Type in Known Numbers), if the appropriate sites are not associated with the added or modified item's Sites tab, you will see a warning telling you that the item does not have the correct site association. Accept the warning to add the item anyway or cancel the action.

You will need to add the site associations to the child items before the assembly item is released. When an assembly is released, the item is audited for the proper site association of the items on the BOM table. Depending on Agile system SmartRule settings, you might not be able to release a change order or site change order if the site associations are not correct. See also [Site-Specific Effectivity and Obsolete Dates](#) (on page 124).

If you use Add | Create (Java Client) or Add | Create New (Web Client), the appropriate site associations are automatically added during the create process.

See also: [Sites and Distributed Manufacturing](#) (on page 35).

Viewing BOMs by Site

You can view the BOM for a specific manufacturing site by selecting a site from the Site drop-down list above the tabs. Sites included in the list are the ones specified on the item's Sites tab. (For information about manufacturing sites, see [Sites and Distributed Manufacturing](#) (on page 35).)

When you select a site, the BOM tab displays the common BOM plus the BOM of the site you selected. To view the BOM for all sites at once, select ALL in the Site list.

If your organization assigns colors to sites, the rows in the BOM table may appear in different colors, distinguishing one site from another. Site colors are assigned on the site General Info tab.

You can perform actions only on the items that are displayed in the BOM table. For example, if you select San Francisco in the Site drop-down list, you see all items that are part of the common and San Francisco portions of the BOM, and you can modify the common portion of the BOM and the San Francisco portion of the BOM. However, you cannot modify the Hong Kong portion of the BOM; it is not displayed.

The Rev and Site drop-down lists work independently. For more details, see [Working with Item Revisions](#) (on page 13).

Opening Items on a BOM

In general, you can open any item listed on a BOM by double-clicking its row (Java Client) or clicking its item number (Web Client). When you open an item, its page appears.

This section includes the following topics:

- [Opening a Part, Assembly, or Document from the BOM Tab](#) (on page 83)

- [Expanding and Collapsing an Assembly](#) (on page 83)
- [Using BOM Go To](#) (on page 84)

Opening a Part, Assembly, or Document from the BOM Tab

Java Client:

You can open any item listed on a BOM by double-clicking its row.

Web Client:


You can open any item listed on a BOM by clicking its item number.

You can also view the BOM of a pending revision by selecting the pending revision (marked with parentheses, for example, Rev (B)) from the Rev drop-down list above the tabs.


See [Working with Item Revisions](#) (on page 13) for more information about viewing different revisions of the same item.


Expanding and Collapsing an Assembly

To expand an assembly or subassembly, click  before its item number.

To collapse an assembly or subassembly, click  before its item number

Close-up of the BOM tree, Java Client:




Close-up of the BOM tree, Web Client:

See also: [Opening Items on a BOM](#) (on page 82).

Using BOM Go To

The BOM Go To feature allows you to search for a specific item in the BOM tree.

To use the BOM Go To feature in Java Client:

1. Click the item's BOM tab to display it.
2. If you want to limit your search to a specific assembly, expand the BOM as needed, and select the assembly you want in the BOM table. Otherwise, go to the next step.
3. Click the Go To button. 
4. In the Go To dialog box, define your search:
 - a. Enter the text you want to find. The Go To search finds any item that includes (contains) the specified text in its attribute fields. You can use any type of character, including numerals and punctuation.
 - b. In the drop-down list, choose which BOM table column you want to search. You can choose all columns or one specific column.
 - c. Check Match case if you want to perform a case-sensitive search where text capitalization matters.
 - d. Choose how many BOM levels you want to search: Enter a number or check All levels.
 - e. If you selected an assembly in step 2, check Limit the search to the selected assembly to limit your search to the selected assembly. If you did not select an assembly, this checkbox is

disabled.

5. To start the search, click Find.

The search results are displayed in a search results dialog box. If it is not already expanded, the BOM table in the object window is expanded to show the number of levels specified in the search criteria dialog box.

You can sort the search results in the following ways:

- Drag and drop the column headers to rearrange the order in which the columns are displayed.
 - In the Add: [Available Columns] drop-down list, choose more columns to display. For example, add the Sites column to the results table so you can sort items by their sites.
 - To remove displayed columns, use the Remove: [Displayed Columns] drop-down list.
6. If you want to modify the search criteria and run the search again, click Criteria. The search results dialog box closes and the search criteria dialog box is displayed with the settings you last specified. To redefine the search, go to step 4 above.
 7. Find the item you want in the search results table. Use the Next and Previous buttons to scroll up and down the search results list. You can also click an item's row to select it. The selected item in the search results table is highlighted. At the same time, that item is also highlighted in the BOM table in the object window. Whenever you select a different item in the search results table, that item is then highlighted in the BOM table.
 8. When you have found the item you want, click Close in the search results dialog box. The last item you selected in the search results table remains highlighted in the BOM table in the object window.

To use the BOM Go To feature in Web Client:

1. On the BOM tab, click the Go To.
2. In the Go To Item in BOM dialog box, define your search:
 - a. Enter the text you want to find. The Go To search finds any item that includes (contains) the specified text in its attribute fields. You can use any type of character, including numerals and punctuation.
 - b. In the drop-down list, choose which BOM table column you want to search. You can choose all columns or one specific column.
 - c. Check Match Case if you want to perform a case-sensitive search where text capitalization matters.
 - d. Choose how many BOM levels you want to search: Enter a number or check All levels.
3. To start the search, click Find Next. The first item that matches the search criteria is highlighted in the BOM table.
4. Use the Find Next and Find Previous buttons to scroll up and down the BOM table, highlighting items that match the search criteria.
5. When you have found the item you want, click Close in the Go To Item in BOM dialog box. The last item you highlighted in the BOM table remains highlighted.

See also: [Opening Items on a BOM](#) (on page 82).

Revisions Listed on BOMs

The revision number (or letter) that appears in the Item Rev field of the BOM table is calculated by checking the release date of the parent item (if already released), then locating the latest revision of the child item prior to that date and analyzing it. If the parent item hasn't been released, the most recent revision of the child item is found. For details, see [Details About Revision Display on BOMs](#) (on page 187).

Caution Be aware that the unrelease and release of child items may affect the child revisions displayed on the parent BOM.

BOMs of Items Affected by an ECO

When you create an ECO against an item, Agile PLM creates a new revision of any item affected by that ECO. The new revision has an updated BOM based on the redlines.

For example, consider the following scenario in which someone does the following:

1. Creates an ECO that modifies part 1000-02 by replacing the currently used 1.0 GB disk with a 2.1 GB hard disk.
2. Releases the ECO.
3. Examines the BOM of item 1000-02.

When the ECO is released, Agile PLM displays the changed item as a new revision of item 1000-02. The new revision incorporates the modifications made by the ECO.

See also: [Changes](#) (on page 111), [Affected Items of Changes](#) (on page 131).

About Modifying the BOM Table

If an item is not yet released, and has no changes pending against it, you can modify the BOM table directly (add, delete, or edit items).

If the item has been released or has a pending MCO against it, you must write an ECO against the item and redline its BOM. (If the item already has a pending ECO against it, you can redline the BOM through the pending ECO without creating another ECO.) See [Redlining the BOM of a Released Item](#) (on page 104).

The following table illustrates how an item's BOM table can be modified as a preliminary item and as a production released item.

Phase 1	Phase 2	Phase 3	Phase 4
Part_123 Lifecycle = Preliminary Revision = Introductory	Part_123 Lifecycle = Preliminary Revision = (A) ECO_001	Part_123 Lifecycle = Production Revision = A ECO_001	Part 123 Lifecycle = Production Revision = (B) ECO_005

Phase 1	Phase 2	Phase 3	Phase 4
No pending changes.	Pending ECO_001 has not yet been released. It creates pending Revision (A).	ECO_001 releases Part_123.	ECO_005 creates pending revision (B) of Part_123.
Part_123 has not yet been released. You may modify the BOM table as explained in Adding Items to the BOM Table of a Preliminary Item (on page 87).	Modify the BOM table of Part_123. by redlining the BOM through ECO_001.	You cannot modify the BOM table of Part_123 because it has been production released.	Part_123 is production released. You must make all changes to the BOM table by creating a change and redlining the BOM.

This section includes the following topics:

- [Modifying Site-Specific Portions of the BOM of a Preliminary Item](#) (on page 87)
- [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87)
- [Modifying the BOM Table of a Preliminary Item](#) (on page 95)
- [Removing Items from the BOM Table](#) (on page 96)

Modifying Site-Specific Portions of the BOM of a Preliminary Item

If your organization practices distributed manufacturing, you can modify each manufacturing site's portion of the BOM separately. To modify a site-specific item on the BOM, select the site in the Site drop-down list, then select the site-specific item you want to modify or edit. See [Modifying the BOM Table of a Preliminary Item](#) (on page 95). When adding an item to the BOM, you select the site you want. See [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87).

Note Modifying the site-specific portion of the BOM of a released item does not require a revision change and can be done through an SCO. Modifying the common portion of the BOM of a released item requires a revision change and can be done only through an ECO. For more information about modifying the BOM of an item that has been released, see [Changes](#) (on page 111) and [Affected Items of Changes](#) (on page 131).

Adding Items to the BOM Table of a Preliminary Item

There are several different ways to add items to the BOM tab. You can:

- Type in the number of an item. See [Type in the Number of an Item to Add to the BOM Table](#) (on page 88).
- Select one of the available search methods and search for the items you want to add. See [Search for Items to Add to the BOM Table](#) (on page 88).

- Create a new item. See [Adding Nonexistent Items to the BOM Table](#) (on page 94).
- Add a blank row, and select an item for that row later. See [Adding a Blank Row to the BOM Table](#) (on page 90).
 - Edit the blank row to enter BOM row details, including a temporary Item Number or item descriptions. See [Editing a Blank Row](#) (on page 91).
 - Complete a blank row by selecting the item you want to use. See [Completing a Blank Row in the BOM Table](#) (on page 92).

See also: [About Modifying the BOM Table](#) (on page 86).

Type in the Number of an Item to Add to the BOM Table

If you know the number of the item you want to add to the BOM table, you can use the Type in Known Numbers option. The process is similar in both Java Client and Web Client.

Note	If you enter a non-existent item number, Agile displays a warning. If you accept the warning, Agile adds a placeholder row with the non-existent item number. See also Adding a Blank Row to the BOM Table (on page 90).
------	--

To add one or more known items to the BOM table:

1. Click the BOM tab.
2. If you want to add a site-specific item to the BOM tab, select the site you want in the item's Site drop-down list. To add items to the common portion of the BOM, select ALL.
3. Click the Add drop-down menu button and choose the Type in Known Numbers option. A dialog appears.
4. In the Item Number(s) field, enter the item numbers you want, each number on a separate row.
For example, type P00002, then press the Enter key to place the cursor on the next row. Now type P00044.
5. In the Add for Site drop-down list, select the site you want. To add an item to the common portion of the BOM, select Common.
If you have already selected the site you want in the item's Site drop-down list, it is preselected for you in the dialog.
6. Click Add.
The item appears in the BOM table.
7. To add items for a different site, select the site you want in the item's Site drop-down list and repeat the procedure.

For information about other methods of adding items to the BOM table, see [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87).

Search for Items to Add to the BOM Table

You can use a saved search or define either a simple search or an advanced search to find items to add to the BOM table. You can also select items in your Bookmarks folder or Recently Visited folder.

To search for and add one or more items to the BOM table in Java Client:

When you add an item to the BOM, it is added below the selected item.

1. Click the BOM tab.
2. If you want to add a site-specific item to the BOM tab, select the site you want in the item's Site drop-down list. To add items to the common portion of the BOM, select ALL.
3. Click the Add drop-down menu button and choose the Search option. The Add BOM dialog appears.
4. To edit the item information immediately after adding items, ensure that Edit rows after adding is checked.
5. Search for one or more existing items. In the Add BOM dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.)
6. In the search results, select the items you want by moving them into the Selected Item(s) list.
You can run multiple searches to find and select additional items.
7. If you have not already done so, select a site in the Site field. To add the selected items to the Common portion of the BOM, select Common. If you previously selected a specific site in the item's Site drop-down list, that site is preselected for you in the dialog.
8. Click OK.
9. If Edit rows after adding was checked, edit the item information in the Editing Added Rows dialog and click OK.

All the items in the Selected Item(s) list are added to the BOM. The BOM tab Site column is automatically completed with the selected site as the associated site. If you added items to the Common portion of the BOM, then the Site column is blank to indicate that the item is common to all sites, instead of being specific to one site.
10. To add items for a different site, select the site you want in the item's Site drop-down list and repeat the procedure.

Note	You cannot add a site-specific row to the BOM table for an item that belongs to a subclass for which the Site-Specific BOM property is set to Disallow. If you have questions, contact the Agile administrator.
------	---

To search for and add one or more items to the BOM table in Web Client:

1. Click the BOM tab.
2. If you want to add a site-specific item to the BOM tab, select the site you want in the item's Site drop-down list.
3. Click the Add drop-down menu button and choose the Search option.
The Add BOM Items wizard appears.
4. Search for one or more existing items. In the Add BOM Items dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.)

5. In the search results, select the items you want by moving them into the Selected list.
You can run multiple searches to find and select additional items.
6. If you have not already done so, select a site in the Add for Site field. To add the selected items to the Common portion of the BOM, select Common. If you previously selected a specific site in the item's Site drop-down list, that site is preselected for you in the dialog.
7. Click OK.
8. If Edit rows after adding was checked, edit the item information in the displayed dialog and click Save.

All the items in the Selected list are added to the BOM. The BOM tab Site column is automatically completed with the selected site as the associated site. If you added items to the Common portion of the BOM, then the Site column is blank to indicate that the item is common to all sites, instead of being specific to one site.
9. To add items for a different site, select the site you want in the item's Site drop-down list and repeat the procedure.

For information about other methods of adding items to the BOM table, see [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87).

Adding a Blank Row to the BOM Table

You can add a blank row to the BOM table as a place holder, editing the BOM Notes field to specify which type of object you want to add later.

For example, Bob is creating a BOM for a computer. He is not sure which specific power cord he wants to use. He adds a blank row to the BOM, then edits the blank row. He specifies the find number, reference designator, and quantity. In the BOM Notes field, he types a note about the type of power cord that should be included in the BOM. Later, when he views the BOM again, Bob sees the blank row. It reminds him that he must select the appropriate item number to complete the information needed in that BOM row. See also [Completing a Blank Row in the BOM Table](#) (on page 92).

To add a blank row to the BOM table in Java Client:

When you add a blank row to the BOM, it is added above the selected rows.

1. Click the BOM tab.
2. If you want to add the blank row to a site-specific portion of the BOM, select the site from the item's Site drop-down list. If you want to add the blank row to the common portion of the BOM, select ALL in the item's Site drop-down list. (Items or blank rows must be associated with the site for which you want to add them. See [Associating a Site with an Item](#) (on page 46) for information.)

Note	You cannot add a site-specific row to the BOM table for an item that belongs to a subclass for which the Site-Specific BOM property is set to Disallow. If you have questions, contact the Agile administrator.
------	---

3. Click the Add drop-down menu button and choose the Add a blank row option.

A blank row is added to the appropriate section of the BOM table with a default find number and a default quantity. The default find number is zero (0). The default quantity is set by the Agile administrator.

To add a blank row to the BOM table in Web Client:

1. Click the BOM tab.
2. If you want to add the blank row to a site-specific portion of the BOM, select the site from the item's Site drop-down list. If you want to add the blank row to the common portion of the BOM, select ALL in the item's Site drop-down list. (Items or blank rows must be associated with the site for which you want to add them. See [Associating a Site with an Item](#) (on page 46) for information.)

Note You cannot add a site-specific row to the BOM table for an item that belongs to a subclass for which the Site-Specific BOM property is set to Disallow. If you have questions, contact the Agile administrator.

3. Click the Add drop-down menu button and choose the Blank Row option.

A blank row is added to the appropriate section of the BOM table. By default, the find number is zero (0) and the quantity is one (1).


For information about other methods of adding items to the BOM table, see [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87).

Editing a Blank Row

In the same manner that you can edit any BOM row, you can also edit a blank row, which allows you to fill in some BOM table fields before you specify the object you want to add. For example, you can fill in the Quantity, Find Number, Reference Designators, and additional custom fields that the Agile administrator had defined.

You can also provide a temporary Item Number or a temporary description for the item by following the instructions below.

To edit a blank row (including entering or editing a temporary Item Number or Item Description) using Java Client:

1. Select one or more BOM rows, including the blank rows you want to modify and click the Edit button .

The Edit BOM window appears.

2. Make the modifications in the table.
3. To provide a temporary description for the blank row, in the BOM Description field, type the text you want to use as the temporary item description.


The Item Description field of a blank row cannot be edited. However, Agile uses the text in BOM Description field as a temporary description of the item when you save your modifications.

4. To provide a temporary item number, in the Item Number field, type a number that does not exist in the Agile database.
5. When you are finished, click OK.

If you entered a temporary item number, Agile displays a Warnings and Errors dialog box which includes a warning that the item number does not exist. To finish specifying the temporary item number, check the Accept checkbox and click OK.

If you entered text for a temporary description in the BOM Description field, that text is now also displayed in the Item Description field of the blank row.

To edit a blank row (including entering or editing a temporary Item Number or Item Description) using Web Client:

1. Select one or more BOM rows, including the blank rows you want to modify and click the  Edit button.

The BOM tab is now in edit mode. The editable fields are in the form of text boxes, list boxes, and so on.
2. Make the modifications you want.
3. To provide a temporary description for the blank row, in the BOM Description field, type the text you want to use as the temporary item description.

The Item Description field of a blank row cannot be edited. However, Agile uses the text in BOM Description field as a temporary description of the item when you save your modifications.
4. To provide a temporary item number, in the Item Number field, type a number that does not exist in the Agile database.
5. When you are finished, click Save.

If you entered a temporary item number, Agile displays a Warnings and Errors dialog box which includes a warning that the item number does not exist. To finish specifying the temporary item number, check the Accept checkbox and click Save.

If you entered text for a temporary description in the BOM Description field, that text is now also displayed in the Item Description field of the blank row.


For information about methods of adding items to the BOM table, see [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87).

Completing a Blank Row in the BOM Table

You can complete a blank row in a BOM table using the procedures below. The following conditions apply:

- You can perform a blank BOM row replacement in the item BOM table provided that there is no pending change against the item.
- You can perform a blank BOM row replacement in the change order Redline BOM tab provided that the change order has not been released.
- Temp BOM row replacement (a blank BOM row with a name) can take place outside of the BOM table edit process:
 - When you create an item with that Temp name, for example, from the main Create menu.
 - When an existing item is renamed to the same name as the Temp BOM item.
 - On a Save As of an exiting item to a new item with the same name as the Temp BOM item.

To complete a blank row in the BOM table using Java Client:

1. On the BOM table, double-click the blank row, which displays this symbol: .
2. In the Replace Temporary Item dialog box, select the method you want to use:

Create a new Item

- a. In the Replace Temporary Item dialog box, select Create a new Item and click OK.
- b. In the New dialog box, select the item type in the Type drop-down list, fill in the required fields, and click OK. If an autonumber is not required, the New dialog Number field is prepopulated with the temporary number; you can use the temporary number or you can replace it. If an autonumber is required, the temporary number is automatically replaced with an autonumber.

Search for an Item


- a. In the Replace Temporary Item dialog box, select Search for an Item and click OK.
- b. In the Select Objects dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.)

You can run multiple searches until you find the item you want.
- c. In the search results, select the one item you want by moving it into the Selected Object(s) list and click OK.

Replace it with Item

- a. In the Replace Temporary Item dialog box, select Replace it with Item.
- b. Enter the item number of an existing item and click OK.

To complete a blank row in the BOM table using Web Client:

1. On the BOM table, click this symbol in the blank row .
2. In the Replace Temporary Item dialog box, select the method you want to use:

Create a New Item

- a. In the Replace Temporary Item dialog box, select Create New Item and click OK.
- b. In the Create New Item dialog box, select the item type in the Type drop-down list, fill in the required fields, and click OK. If an autonumber is not required, the New dialog Number field is prepopulated with the temporary number; you can use the temporary number or you can replace it. If an autonumber is required, the temporary number is automatically replaced with an autonumber.

Search for a Replacement

- a. In the Replace Temporary Item dialog box, select Search for a Replacement and click OK.
- b. In the Search for Items dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.)
- c. You can run multiple searches until you find the item you want.
- d. In the search results, select the one item you want by moving it into the Selected list and click OK.

Replace it with Item


- a. In the Replace Temporary Item dialog box, select Replace it with Item.
- b. Enter the item number of an existing item and click OK.

For information about methods of adding items to the BOM table, see [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87).

Adding Nonexistent Items to the BOM Table


You can add to a BOM an item that hasn't been created yet.

Adding nonexistent items to the BOM table using Java Client:


1. Click the BOM tab.
2. If you want to add a site-specific item to the BOM tab, select the site you want in the item's Site drop-down list. To add an item to the Common portion of the BOM, select ALL.
3. Click the Add drop-down menu button and choose the Create option. The New dialog appears.
4. In the New dialog box, use the Type drop-down list to select the type (subclass) of item you want to create.
5. Assign a number to the item. To do so, either accept the number that appears, click the Autonumber button  to use the next autonumber, or type a number.
6. In the Add for Site drop-down list, select the site you want. To add an item to the common portion of the BOM, select Common.

If you have already selected the site you want in the item's Site drop-down list, it is preselected for you in the dialog.

7. Complete any required fields.
8. Click OK.

Note	If you create a new item and decide you do not wish to keep it, you should delete it from the database with the Delete button  in the object window. For more information about deleting items from the BOM, see Removing Items from the BOM Table (on page 96).
------	---

Adding nonexistent items to the BOM table using Web Client:

1. Click the BOM tab.
2. If you want to add a site-specific item to the BOM tab, select the site you want in the item's Site drop-down list. To add an item to the Common portion of the BOM, select ALL.
3. Click the Add drop-down menu button and choose the Create New option. The New dialog appears.
4. In the New dialog box, use the Type drop-down list to select the type (subclass) of item you want to create.
5. Assign a number to the item. To do so, either accept the number that appears, click the Autonumber button  to use the next autonumber, or type a number.
6. In the Add for Site drop-down list, select the site you want. To add an item to the common portion of the BOM, select Common.

If you have already selected the site you want in the item's Site drop-down list, it is preselected for you in the dialog.

7. Complete any required fields.

8. Click OK.

Note If you create a new item and decide you do not wish to keep it, you should delete it from the database with the Delete command on the Actions menu. For more information about deleting items from the BOM, see the section, [Removing Items from the BOM Table](#) (on page 96).

For information about other methods of adding items to the BOM table, see [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87).

Modifying the BOM Table of a Preliminary Item

You can directly modify the BOM table of an item that has *not* been released and has no pending changes.

When you create a new item and then click the BOM tab, the object window displays a blank BOM tab.

To modify items in the BOM table of a preliminary item in Java Client:

1. Open the unreleased item.
2. Click the BOM tab.
3. If the BOM information you need is on a site-specific portion of the BOM, select the site from the Site drop-down list.
4. Select one or more items to modify.

Click the Edit button .

The Edit BOM window appears.

5. Make the modifications in the table.
When you are finished, click OK.

To modify items in the BOM table of a preliminary item in Web Client:

1. Open the unreleased item.
2. Click the BOM tab.
3. If the BOM information you need is on a site-specific portion of the BOM, select the site from the Site drop-down list.
4. Select one or more items to modify.
5. Click the Edit button.


The BOM tab is now in edit mode. The editable fields are in the form of text boxes, list boxes, and so on.

6. Make the modifications you want.
When you are finished, click Save.

See also: [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87).

Removing Items from the BOM Table

To remove an item from the BOM table in Java Client:

1. If you want to remove an item from a site-specific portion of the BOM that is not currently displayed, select the site (or ALL) from the Site drop-down list to display the site-specific rows.
2. Select one or more items to remove from the BOM table.
3. Click the Remove button on the BOM tab .

The items are deleted from the BOM table.

Note	Be sure to use the Remove button on the Manufacturers tab, not the Delete button in the item window. If you use the Delete button, the entire item is deleted.
------	--

To remove an item from the BOM table in Web Client:

1. If you want to remove an item from a site-specific portion of the BOM that is not currently displayed, select the site (or ALL) from the Site drop-down list to display the site-specific rows.
2. Select one or more items to remove from the BOM table.
3. Click the Remove button on the BOM tab.

The items are deleted from the BOM table.

Note	Be sure to use the Remove button on the Manufacturers tab, not the Delete button in the item window. If you use the Delete button, the entire item is deleted.
------	--

See also: [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87).

Working with Reference Designators

Reference designators are commonly used in the electronics industry as a labeling system to refer to components. If your company uses reference designators, you can assign and edit reference designators in Agile BOMs.

This section includes the following topics:

- [Viewing Reference Designators](#) (on page 96)
- [Adding Reference Designators](#) (on page 98)
- [Deleting Reference Designators](#) (on page 103)
- [Modifying Reference Designators](#) (on page 103)

Viewing Reference Designators

Reference designators may appear in the BOM table in an expanded display (R1, R2, R3) or a collapsed display (R1-R3). The Agile administrator sets the following system preference to select the method of reference designator display used on your Agile system.

This section includes the topics:

- [Reference Designators Allow Range Expand Collapse Preference Setting](#) (on page 97)
- [Viewing Reference Designators in Java Client](#) (on page 97)
- [Viewing Reference Designators in Web Client](#) (on page 98)

Reference Designators Allow Range Expand Collapse Preference Setting

Depending on the setting of the Reference Designators Allow Range Expand Collapse system preference, ranges of reference designators appear in the Ref Des field as either collapsed or expanded. For example, the range of reference designators R1, R2, R3, R4, R5 appear as follows:

- Expanded: R1, R2, R3, R4, R5

Each reference designator is displayed in the Ref Des field.

- Collapsed: R1-R5

Ranges of three or more reference designators are represented by the first reference designator in the sequence (R1), followed by the Reference Designator Range Indicator character (- the hyphen character), followed by the last reference designator in the sequence (R5). The hyphen character is the default reference designator character, however, the Agile administrator may choose a different character, if needed.

If the reference designators include leading zeros, in collapsed mode the reference designators are displayed in groups according to the number of leading zeros. For example, the 100 reference designators:

R0001, R0002, R0003, R0004, ... R0099, R0100

Are displayed in collapsed mode as:

R0001-R0009, R0010-R0099, R0100

See also: [Adding Reference Designators](#) (on page 98), [Viewing Reference Designators](#) (on page 96).

Viewing Reference Designators in Java Client

When there are many reference designators to display, Java Client displays one line of reference designators, followed by an ellipsis (...) to indicate that there are more reference designators in the Ref Des field.

To display all the reference designators in the Ref Des field:

Click the Ref Des field cell in the BOM table.

A drop-down pane appears. The entire list of reference designators are displayed in this pane. If needed, a scroll bar is included in the pane.

Regardless of the Expand/Collapse system preference setting, the reference designators are displayed in expanded mode in the pane. Each reference designator appears in the pane.

See also: [Bills of Material](#) (on page 77), [Adding Reference Designators](#) (on page 98).

Viewing Reference Designators in Web Client

When there are many reference designators to display, Web Client displays several lines of reference designators in the Ref Des cell and a scroll bar in the cell allows you to scroll through the reference designators.

To display all the reference designators in the Ref Des field:

Use the scroll bar in the Ref Des cell in the BOM table to scroll up and down to view the reference designators. In addition, you can resize the Ref Des column width.

The reference designators are displayed according to the Expand/Collapse system preference setting.

See also: [Bills of Material](#) (on page 77), [Adding Reference Designators](#) (on page 98).

Adding Reference Designators

This section includes the topics:

- [Reference Designator Entry Format Guidelines](#) (on page 99)
- [Leading Zeros in Reference Designators](#) (on page 99)
- [Multi-segmented Reference Designator Entry Format Guidelines](#) (on page 100)
- [Editing the Reference Designator Field](#) (on page 102)
- [Duplicate Reference Designators and Sites](#) (on page 102)

You can enter, delete, and modify reference designators, either individually or several at once. If you have very few reference designators, you can enter them one by one (that is, R1, R2, R3). If you need to enter a larger set, you may use the format (Rx–Ry), where x and y are any numbers, but whose difference is less than 5000 (for example: R6–R2055).

Reference designators are limited to 5000 per BOM row. If you need more than 5000 reference designators, add a duplicate item to the BOM with a different find number (same item number) to define additional reference designators.

Reference designators are not sorted until you complete edits to the current item.

If the number in the Qty field does not match the number of reference designators, you see a message indicating that the reference designators and quantity don't match.

If Qty is blank (null), Agile treats the contents of the Qty field as a 0 (zero), and verifies that the number of reference designators match, that is, that the number of reference designators is also 0 (zero). If there are any reference designators in the Ref Des field and Qty is blank, you see a message indicating that the reference designators and quantity don't match.

If Qty is not an integer, Agile treats the contents of the Qty field as text characters and does not verify that Qty and the number of reference designators match. Decimal numbers (for example, 7.8) are not integers and are therefore considered a text entry.

The length of an individual reference designator may be a minimum of 1 character and a maximum of 19 characters.

Duplicate reference designators are not allowed in the same unique single BOM row. If you enter

the same reference designator twice (for example: A1, A1), Agile PLM resolves this to one reference designator (A1).

A unique BOM row is defined by a unique find number. If BOM table rows have the same find number, the Duplicate Ref Des SmartRule is ignored for those BOM table rows. However, if Find Number is blank for multiple BOM rows, Agile PLM validates Duplicate Ref Des SmartRule as if all those rows have Find Number = 0. For more information about the Duplicate Ref Des SmartRule, see the *Administrator Guide*.

See also: [Deleting Reference Designators](#) (on page 103), [Modifying Reference Designators](#) (on page 103).

Reference Designator Entry Format Guidelines

The following rules apply when entering reference designators:

- Entering ranges — You can always use ranges when entering reference designators, regardless of the setting of the Reference Designators Allow Range Expand Collapse system preference. If the preference is set to Expand, the reference designators are displayed in expanded format after you save your edits. For example:

Enter: R1-R5

Expanded Display: R1, R2, R3, R4, R5

Collapsed Display: R1-R5

Note	Whenever you edit the reference designator field, the existing reference designators are displayed in Expand format while the BOM table row is in edit mode. If, during the same edit session, you navigate away from the Ref Des edit field, and return to the Ref Des edit field again, any ranges you entered previously are now displayed in Expanded format.
------	---

For more information, see [Reference Designators Allow Range Expand Collapse Preference Setting](#) (on page 97).

- To add groups of reference designators that begin with different letters, you must separate each letter group with commas. For example, to enter the 10 designators A1, A2, A3, B4, B5, B6, B7, C8, C9, and C10, you would type:

A1-A3 , B4-B7 , C8-C10

See also: [Working with Reference Designators](#) (on page 96), [Adding Reference Designators](#) (on page 98).

Leading Zeros in Reference Designators

You can use leading zeros when you enter individual reference designators or ranges of reference designators. For example,

R001, R002, R010

B001-B100

- The number of numeric characters in each segment of the range do not need to match. For example:

R0001-R100

- When the number of numeric characters in each segment of the range do not match, the

number of numeric characters in the first segment is used for all the reference designators in the range. In the above example, the range is saved as:

R0001, R0002, R0003, R0004, ... R0099, R0100

When you exit edit mode, the reference designators are displayed according to the Reference Designators Allow Range Expand Collapse preference setting. For more information, see [Reference Designators Allow Range Expand Collapse Preference Setting](#) (on page 97).

See also: [Working with Reference Designators](#) (on page 96), [Adding Reference Designators](#) (on page 98).

Multi-segmented Reference Designator Entry Format Guidelines

Note These rules apply when using a suffix, as defined below.

Reference designators may be separated into a maximum of three parts:

<Prefix> <Number> <Suffix>

- Prefix — may be any character that is not defined as the range indicator (for example, [- hyphen] the default range indicator) or a delimiter (for example, [, comma] used to separate – delimit – a list of reference designators).
- Number — must be a number (numerals 0 through 9)
- Suffix — may be any character that is not designated as the range indicator or a delimiter, and does not start with 0 (zero).

Only the last number string is considered the reference designator *<Number>*. For example,

A10B30D

<Prefix> = A10B *<Number>* = 30 *<Suffix>* = D

A segmented reference designator may also include characters that divide the segments as long as they meet the requirements outlined above. If the Agile administrator has selected a non-hyphen character as the range indicator, then the hyphen character can be used. Contact the Agile administrator if you have questions about which characters you may use in a multi-segmented reference designator. For example:

A*10*B30D

<Prefix> = A*10B* *<Number>* = 30 *<Suffix>* = D

Note If the Agile administrator has selected a non-hyphen character as the range indicator, then the hyphen character can be used. Contact the Agile administrator if you have questions about which characters you may use in a multi-segmented reference designator.

See also: [Working with Reference Designators](#) (on page 96), [Adding Reference Designators](#) (on page 98).

Entering Multi-segmented Reference Designator Ranges

When you enter a range, Agile evaluates the formats of the begin-range designator and the end-range designator to ensure that the formats are compatible and, therefore, the range is valid.

When you enter a multi-segmented range, both the prefix and the suffix must be identical in the begin-range designator and end-range designator. (For details, refer to step 3 below.)

The number segment may use leading zeros as described in [Leading Zeros in Reference Designators](#) (on page 99).

Agile uses the following rules to evaluate the number portions of a multi-segmented range and the validity of the entered range:

1. Agile determines the number segments by scanning from right to left to find the first whole number in both the begin-range designator and the end-range designator.
2. Agile evaluates the begin-range number and the end-range number to ensure that they are the same formats.
 - a. The numbers are the same precision (number of characters) from the end of the designator.
 - b. The end-range designator number is greater than the begin-range designator number.
3. Agile evaluates the suffixes and prefixes to ensure that they match:
 - a. The string of characters to the right of the whole number (suffix) are the same in both the begin-range designator and the end-range designator.
 - b. The string of characters to the left of the whole number (prefix) are the same in both the begin-range designator and the end-range designator.

Optionally, the prefix can be omitted in the end-range designator. Agile will use the same prefix as the start-range designator. This satisfies the rule that both prefixes must be the same. The following two ranges are equivalent:

A1B1C - A1B3C

<Prefix> = A1 <Number> = 1 <Suffix> = C

-

<Prefix> = A1 <Number> = 3 <Suffix> = C

A1B1C - 3C

<Prefix> = A1 <Number> = 1 <Suffix> = C

-

<Prefix> = <use start-range designator prefix> <Number> = 3 <Suffix> = C

The following table shows examples of valid multi-segmented reference designator ranges; the range indicator is - (hyphen):


Range entered as:	Reference designators saved as:
A1B*A3B	A1B*A3B
A*07*FG - A*10*FG	A*07*FG, A*08*FG, A*09*FG, A*10*FG
A*001*TT - A*3*TT	A*001*TT, A*002*TT, A*003*TT
A*07 - A*10	A*07, A*08, A*09, A*10
A*001 - A*3	A*001, A*002, A*003
A1B1 - A1B3	A1B1, A1B2, A1B3
A1B1C - A1B3C	A1B1C, A1B2C, A1B3C
A1B1C - 3C	A1B1C, A1B2C, A1B3C
A1B1CD - A1B3CD	A1B1CD, A1B2CD, A1B3CD

Range entered as:	Reference designators saved as:
A1B1CD - 3CD	A1B1CD, A1B2CD, A1B3CD
A1B1C1 - A1B1C3	A1B1C1, A1B1C2, A1B1C3

See also: [Working with Reference Designators](#) (on page 96), [Adding Reference Designators](#) (on page 98).

Editing the Reference Designator Field

To add reference designators in Java Client:

1. Select the item to modify. You can select multiple items.
2. Click the Edit button .
The Edit BOM window appears.
3. Click the Ref Des field you want to modify. A drop-down edit pane appears.
4. Type the reference designators in this pane. Make any other required modifications to the row.

Note

If you need to, you can enter a new number in the Qty field.
5. When you are finished, click OK.

To add reference designators in Web Client:

1. Select the row or rows you want to edit.
2. Click Edit on the BOM tab to display the Edit page.
3. Type the reference designators in the Ref Des field. Make any other required modifications to the row.

Note

If you need to, you can enter a new number in the Qty field.
4. When you have finished your edits, click Save.

See also: [Working with Reference Designators](#) (on page 96), [Adding Reference Designators](#) (on page 98).

Duplicate Reference Designators and Sites

The same reference designator can be used in more than one site-specific portion of the BOM, regardless of the Duplicate Ref Des SmartRule setting. (See the *Administrator Guide*.) For example, reference designator B22 can be used for Part 123 in the India portion of the BOM and also for Part 556 in the San Jose portion of the BOM.

If the SmartRule is set to Disallow, then the same reference designator cannot be used in the common portion of the BOM and in a site-specific portion of the BOM, for example, using reference designator C55 for both Part 333 on the common portion of the BOM and for Part 678 on the Milpitas portion of the BOM. Nor can the same reference designator be used more than once in the same site-specific portion of the BOM, for example, using reference designator D46 for both Part 989 on the Milpitas portion of the BOM and for Part 765, also on the Milpitas portion of the BOM.


See also: [Working with Reference Designators](#) (on page 96), [Adding Reference Designators](#) (on page 98).

Deleting Reference Designators

You can delete reference designators either individually or several at once.

Note Be sure to use the keyboard Delete key, not the Remove button on the BOM tab. If you click the BOM Remove button, the entire item is removed from the BOM.

To delete reference designators in Java Client:

1. Select the item to modify by clicking its row.
2. Click the Edit button .
The Edit BOM window appears.
3. Click the Ref Des field you want to modify. A drop-down edit pane appears.
4. Select the appropriate reference designators.
To select the appropriate single reference designator, use the Shift and arrow keys. To select several contiguous reference designators, use the Ctrl+Shift and arrow keys.
5. Press the keyboard Delete key.
6. When you have finished your edits, click OK.

To delete reference designators in Web Client:

1. Select the row or rows you want to edit.
2. Click Edit on the BOM tab to display the Edit page.
3. Click the Ref Des field.
4. Select the appropriate reference designators.
To select a single reference designator, either double-click the appropriate reference designator, or use the Shift and arrow keys. To select several contiguous reference designators, use the Ctrl+Shift and arrow keys.
5. Press the keyboard Delete key.
6. When you have finished your edits, click Save.


Caution Be sure to use the keyboard Delete key, not the Remove button on the BOM tab. If you click the BOM Remove button, the entire item is removed from the BOM.

See also: [Working with Reference Designators](#) (on page 96), [Adding Reference Designators](#) (on page 98).

Modifying Reference Designators

You can modify reference designators, either singly or several at once.

To modify reference designators in Java Client:

1. Select one or more items to modify.
2. Click the Edit button .
The Edit BOM dialog box appears.

3. Click the Ref Des field you want to modify. A drop-down edit pane appears.
4. Select the appropriate reference designators.
 - To select a single reference designator, position your cursor in the list of reference designators and use the Shift and arrow keys.
 - To select several contiguous reference designators, use the Ctrl+Shift and arrow keys.
 - To add a reference designator, position the pointer at the end of the list of reference designators.

Note	Although you may position the cursor anywhere in the list to add a reference designator, it is not necessary to insert the reference designator in a particular place in the list because the list is sorted after you save your modifications.
------	---

5. Type the modified reference designator.
6. When you are finished, click OK.

To modify reference designators in Web Client:

1. Select the row or rows you want to edit.
2. Click Edit on the BOM tab to display the Edit page.
3. Click the Ref Des field.
4. Select the appropriate reference designators.
 - To select a single reference designator, either double-click the appropriate reference designator, or use the Shift and arrow keys.
 - To select several contiguous reference designators, use the Ctrl+Shift and arrow keys.
 - To add a reference designator, position the cursor at the end of the list of reference designators.

Note	Although you may position the cursor anywhere in the list to add a reference designator, it is not necessary to insert the reference designator in a particular place in the list because the list is sorted after you save your modifications.
------	---

5. Type the modified reference designator.
6. Click Save.

See also: [Working with Reference Designators](#) (on page 96), [Adding Reference Designators](#) (on page 98).

Redlining the BOM of a Released Item

This section includes the following topics:

- [Overview of BOM Redlining](#) (on page 105)
- [Redline BOM Tab](#) (on page 105)
- [Adding an Item to a Redline BOM Table](#) (on page 107)
- [Removing an Item from a Redline BOM Table](#) (on page 108)
- [Editing Item Information on a Redline BOM Table](#) (on page 108)

- [Undoing Changes to a Redline BOM Table](#) (on page 109)

Overview of BOM Redlining

If an item is released, or has pending changes against it, you must create a change against that item and redline it to modify the BOM table. You can use an ECO or SCO to redline the BOM:

- Use an ECO to modify common or site-specific portions of the BOM on the *latest* released revision of the item. Using an ECO creates a new revision of the item.
- Use an SCO to modify site-specific portions of the BOM on the latest released revision. Using an SCO does not create a new revision of the item. For more information about SCOs, see [Site Change Orders](#) (on page 124).

When you add an item that has pending changes to the Affected Items tab, Agile PLM displays a warning that informs you that the item has a separate pending change, and allows you to choose whether or not to add it to the Affected Items tab. If you choose to add it, you can open the item from the Affected Items table. To view the pending changes, click the item's Changes tab.

Note If you do not have the Discovery privilege for an item on the BOM table, you cannot redline that item. You cannot replace an item on the BOM table with an item that you cannot discover.

If you have the appropriate privileges, you can modify a redlined BOM. For details, see the following sections:

- [Editing Item Information on a Redline BOM Table](#) (on page 108)
- [Adding an Item to a Redline BOM Table](#) (on page 107)

Note You can add nonexistent items to the Redline BOM table. See [Adding Items to the BOM Table of a Preliminary Item](#) (on page 87).

- [Removing an Item from a Redline BOM Table](#) (on page 108)

Redline BOM Tab

You display the Redline BOM tab from the Affected Items tab of an ECO or SCO.

To display the Redline BOM tab for an item in Java Client:


1. Open the ECO or SCO through which you want to redline an item's BOM.
2. Click the Affected Items tab of the change.
3. In the Affected Items table, click the row of the item for which you want to view or create redlines.

In the redline pane under the Affected Items table, the Redline BOM tab, Redline Manufacturers tab, and Redline Attachments tab (on ECOs only) appear, displaying the item's BOM data, manufacturing data, and attachments respectively.

Note If your Agile PLM system does not use the Manufacturers tab or, on documents, the BOM tab, then those redline tabs do not appear in the redlines pane.

4. Display the Redline BOM tab, if it is not displayed.

To display the Redline BOM page for an item in Web Client:

1. Open the ECO or SCO through which you want to redline an item's BOM.
2. Click the Affected Items tab of the change.
3. Click the  icon in front of the item for which you want to create redlines.

If the item has already been redlined, the  icon appears in front of the item row. Click this icon to view or modify existing redlines.

The Redline BOM tab, Redline Manufacturers tab, and Redline Attachments tab (on ECOs only) appear on the Redlines page, displaying the item's BOM data, manufacturing data, and attachments respectively.










Note If your Agile PLM system does not use the Manufacturers tab or, on documents, the BOM tab, then those redline tabs do not appear in the redlines page.



4. Click the Redline BOM tab to display it (if it is not already displayed).
 - If a row in the table has a red line through every cell in the row, it means that item was deleted from the BOM.
 - If just a few of the cells have a short red line through them, it means the item was modified, but not deleted. For example, redlines in only the Qty and Find Number cells indicate that the Qty and Find Number of that BOM item have been modified, while other values remain unchanged.
 - Any cell that was modified has a red line through the old value; the new value appears in red. For example, in the Qty cell, a numeral seven with a redline through it 7 and a red numeral ten 10 indicates that the old quantity was 7 and the new quantity is 10.

For information about other BOM redlining actions, see [Redlining the BOM of a Released Item](#) (on page 104).












Redline BOM Tab Buttons

The following table lists the buttons on the Redline BOM tab in Java Client:

Button	Use
	Redline BOM — Displays the selected rows in an Redline BOM window so that you can change editable fields.
   	Add — Adds an item or an empty row to the Redline BOM table. Depending on which option you choose, you can: <ul style="list-style-type: none">  Create an item while adding it.  Search for an existing item.  Type in Known Number(s) of one or more existing items.  Add Blank Row — adds a blank row to the Redline BOM table that can be filled in later. By default, the new item or row has a find number of zero (0) and a quantity of one (1). See Adding Items to the BOM Table of a Preliminary Item (on page 87).

Button	Use
	Remove — Removes the selected row from the Redline BOM table.
	Undo Redlines — Clears the redlines from the selected rows. See Undoing Changes to a Redline BOM Table (on page 109).

The following table lists the buttons on the Redline BOM tab in Web Client:

Button	Use
 Edit	The Edit button displays the selected rows on an Edit page so that you can change editable fields.
 Delete	The Delete button removes the selected row from the Redline BOM table.
 Undo Redlines	The Undo Redlines button clears the redlines from the selected rows. See Undoing Changes to a Redline BOM Table (on page 109).
 Add  Add  Add  Add	Add — Adds an item or an empty row to the Redline BOM table. Depending on which option you choose, you can: <ul style="list-style-type: none">  Create an item while adding it.  Search for an existing item.  Type in Known Number(s) of one or more existing items.  Add Blank Row — adds a blank row to the Redline BOM table that can be filled in later. <p>By default, the new item or row has a find number of zero (0) and a quantity of one (1). See Adding Items to the BOM Table of a Preliminary Item (on page 87).</p>

For information about BOM redlining actions, see [Redlining the BOM of a Released Item](#) (on page 104).

Adding an Item to a Redline BOM Table

To add an item to the Redline BOM table in Java Client:

- Click the Add drop-down menu button and choose one of the add options: Create, Type in Known Numbers, Search, or Add Blank Row.
- Adding items to the Redline BOM table is similar to adding items to the BOM table. For more information about how to complete the dialogs, see:
 - [Adding Nonexistent Items to the BOM Table](#) (on page 94)
 - [Type in the Number of an Item to Add to the BOM Table](#) (on page 88)
 - [Search for Items to Add to the BOM Table](#) (on page 88)
 - [Adding a Blank Row to the BOM Table](#) (on page 90) and [Completing a Blank Row in the BOM Table](#) (on page 92)

To add an item to the Redline BOM table in Web Client:

1. Click the Add drop-down menu button and choose one of the add options: Create New, Search, Type in Known Numbers, or Blank Row.
2. Adding items to the Redline BOM table is similar to adding items to the BOM table. For more information about how to complete the dialogs, see:
 - [Adding Nonexistent Items to the BOM Table](#) (on page 94)
 - [Type in the Number of an Item to Add to the BOM Table](#) (on page 88)
 - [Search for Items to Add to the BOM Table](#) (on page 88)
 - [Adding a Blank Row to the BOM Table](#) (on page 90) and [Completing a Blank Row in the BOM Table](#) (on page 92)


For information about other BOM redlining actions, see [Redlining the BOM of a Released Item](#) (on page 104).

Removing an Item from a Redline BOM Table


You use the buttons on the Redline BOM tab to remove one or more rows and items.

- If a selected row is red (indicating that the row is redline-added to the BOM), it is removed.
- If a selected row is black, a red line is drawn through it, thus redline-deleting the item from the BOM.

To remove an item from a redline BOM table in Java Client:

1. Select one or more rows to delete.
2. Click the Remove button  on the Redline BOM tab .

To remove an item from a redline BOM table in Web Client:

1. Select one or more rows to delete.
2. Click the  Delete button on the Redline BOM tab .

For information about other BOM redlining actions, see [Redlining the BOM of a Released Item](#) (on page 104).

Editing Item Information on a Redline BOM Table

On the Redline BOM tab you can modify any editable BOM tab field, including any editable custom fields that the Agile administrator has enabled. Editable BOM tab fields usually describe or define the relationship between the parent item (the item BOM you are redlining) and the child item (the item that appears on the BOM table). For example, the Qty, Find Number, and Ref Des fields define the relationship between the assembly (parent item) and the BOM item (child item).

When you modify information on the Redline BOM tab, Agile PLM enters the new information, in red, below the old information.

When you redline the BOM Notes field, you can add, replace, or edit text. In the BOM Notes field, the new text and any redlined text are displayed.

You cannot modify the Redline BOM table Sites, Item Description, and Item Rev fields.

Redlining reference designators in the Redline BOM table is the same as editing reference designators on the BOM table. For more information, see [Working with Reference Designators](#) (on page 96). Any new reference designators appear in red. Any deleted reference designators have a red line drawn through them.

Note You cannot use the Redline BOM tab to modify the attributes of the items that are listed on the BOM table. You cannot use the Redline BOM tab to modify non-editable BOM table fields.


If the Agile administrator has enabled them, the item BOM tab may also include *read-through* fields that allow you to conveniently view additional information derived from the items that are listed on the BOM table, for example, a child item's Page Two fields. A read-through field contains a read-only copy of attribute data from a child item. BOM tab read-through fields cannot be edited on the BOM tab, nor can they be edited on the Redline BOM tab.

To modify the attributes of an item listed on the BOM table, if it is a Preliminary item with no pending revisions, you can open it and use the Edit feature to modify it. See [Editing an Unreleased Item](#) (on page 26). If an item listed on the BOM table has been released, you must use a change order to modify it. See [Editing a Released Item](#) (on page 27).

For more information about read-through fields and about which fields are editable on the item BOM tab, see *Agile PLM Administrator Guide*.

Your assigned roles and privileges also determine which attributes you are allowed to edit.

To edit a field on the Redline BOM table in Java Client:

1. Select the rows to edit, and click the Edit button .
The Redline BOM dialog box appears.
2. Make the modifications.
3. When you are finished, click OK.

To edit a field on the Redline BOM table in Web Client:

1. Select the rows to edit, and click Edit.
2. Click inside each field and make the required changes.
3. Click Save.

For information about other BOM redlining actions, see [Redlining the BOM of a Released Item](#) (on page 104).

Undoing Changes to a Redline BOM Table

The Undo Redlines button lets you undo modifications to the Redline BOM tab. It removes the red elements from the selected row.

Note In Java Client, the Undo Redlines button is indicated with this icon: .

To undo a deletion (where Agile PLM has drawn a red line through the entire row):

1. Select the deleted row. You can select more than one row.
2. Click Undo Redlines.

To undo a modification (where Agile PLM has drawn a short red line through the modified value):

1. Select the modified row (or rows).
2. Click Undo Redlines.


To undo a newly added item (remove it from the Redline BOM table):

1. Select the added row (or rows).
2. Click Undo Redlines.

For information about other BOM redlining actions, see [Redlining the BOM of a Released Item](#) (on page 104).

Printing BOM Data

You can print object tabs and other data from your Agile PLM system. You can print the current tab or all tabs. Attachments are printed from their native applications or the Viewer.

In Java Client, with the object open, use the Print button .

In Web Client, with the object open, choose Actions | Print.

For additional information about printing objects, see *Getting Started with Agile PLM*.

In Java Client, to print only the BOM tab data, use the Print button drop-down menu and choose BOM. Complete the BOM Printing Options dialog, including the number of BOM levels you want to print and whether to include the AML.

In Web Client, you can print BOM information from your Web browser. Go to the BOM tab of an item and choose Actions | Print. You can print just the BOM tab or all tabs. When printing the BOM, select the BOM Printing Option you want, including the number of BOM levels to print and whether to include the AML.

See also: [Working with Product Reports and Process Reports](#) (on page 157).

Changes

This chapter includes the following:

▪ Change Classes	111
▪ Change Objects	112
▪ Workflow Routings Inbox	122
▪ Changes and Manufacturing Sites.....	122
▪ The Relationship of Changes to Item Revisions.....	125
▪ Creating Changes.....	126
▪ Modifying Changes.....	126
▪ Agile Change Control Workflows.....	127
▪ Redlining through ECOs, MCOs, and SCOs	127
▪ Deleting Changes	128
▪ Printing Change Tabs.....	129
▪ Routing Managers: Change Analyst and Component Engineer	129

Change Classes







The following classes, or types, of changes are available in Agile PLM:

- Change Orders class, including engineering change orders (ECOs)
- Change Requests class, including engineering change requests (ECRs)
- Manufacturer Orders class, including manufacturing change orders (MCOs)
- Site Change Orders class, including site change orders (SCOs)
- Deviations class
- Stop Ships class

Change Subclasses

Each Agile class has at least one out-of-the-box subclass. The Agile administrator may decide to use some or all of these change classes and subclasses, and may have created additional subclasses. For example, under the Change Orders class, you might have ECOs, Mechanical ECOs, Software ECOs, and so on.

The purpose of each change subclass is listed in the following table. Corresponding change icons are also listed. These icons are displayed next to the change number on the Cover Page, and next to each change in search results.

Change type	Purpose
ECO 	An <i>engineering change order</i> tells users that changes need to be made to specific items, and to go ahead and do the work. ECOs can affect common and site-specific portions of the BOM and AML. ECOs also let you release new items and redline BOMs, manufacturer data, and attachments. See Redlining through ECOs (on page 128).
ECR 	An <i>engineering change request</i> is used to request a change to be made to items. You can create an ECR against a non-latest released revision of an item. ECRs do not have any redlining functions.
MCO 	A <i>manufacturer change order</i> tells users that changes need to be made to the manufacturing data of specific items. MCOs can affect common and site-specific portions of the AML. MCOs allow you to redline the manufacturer data of an item, release new items, and change the lifecycle phase of items. See Redlining through MCOs (on page 128).
SCO 	A site change order tells users that changes need to be made to site-specific items, and to go ahead and do the work. SCOs affect only the site-specific portion of the BOM and AML; they do not affect the common portion. You can create an SCO against a non-latest released revision of an item. SCOs let you redline BOMs and AMLs.
Deviation 	A <i>deviation</i> is used to switch from one part to another for a specific amount of time. You can create a deviation against a non-latest released revision of an item. Deviations do not have any redlining functions.
Stop Ship 	A <i>stop ship</i> alerts users to stop shipping or using an item. You can create a stop ship against a non-latest released revision of an item. Stop ships do not have any redlining functions.

For information about changing the subclass of a change, see the chapter on workflows in *Getting Started with Agile PLM*.

Change Objects

This section includes the following topics:

- [Cover Page Tab](#) (on page 113)
- [Affected Items Tab](#) (on page 116)
- [Workflow Tab](#) (on page 117)
- [Relationships Tab](#) (on page 119)
- [Attachments Tab](#) (on page 120)
- [History Tab](#) (on page 120)

When you view a change in Java Client, information about it is displayed on tabs in its object window.

When you view a change in Web Client, information about it is displayed on tabs in the right pane.

The following table shows the tabs and the default fields for changes.

The Agile administrator may have added additional tabs or sections, called Page Two and Page Three by default. These tabs or sections contain custom fields defined by the administrator.

Tab name	Tab information includes
Cover Page	General information about the change plus any unique fields defined by the Agile administrator.
Affected Items	Which items are affected by the change. ECOs include redlined BOMs, AMLs, and file folders. SCOs include redlined BOMs and AMLs for a site. MCOs include redlined AMLs.
Workflow	Approvers and observers of the change and the results of their reviewing the change.
Relationships	The Relationships tab allows you to create relationships and dependencies between the current change object and other Agile objects, <i>both routable objects and lifecycle objects</i> . For more information about relationships, see <i>Getting Started with Agile PLM</i> .
Attachments	Attached files and URLs.
History	All actions taken on the change.

Cover Page Tab

The Cover Page tab of a change shows the information traditionally shown on a paper ECO form. Agile PLM completes some of the fields; you complete the rest.

This section contains the following topics:

- [Fields on the Cover Page Tab](#) (on page 114)
- [Status on the Cover Page Tab](#) (on page 115)

To edit fields on the Cover Page tab in Java Client:

Modify the fields and click Save.

To edit fields on the cover page tab in Web Client:

Click the Edit button, modify the fields, and click the Save button.

Sometimes you cannot edit a field. A field may be uneditable for three reasons:

- The change has been released.
- You do not have sufficient privileges to modify that field.
- The field is automatically filled in as the change progresses through its workflow statuses, for example, Status, Date Released, or Final Complete Date.

For information about all change object tabs, see [Change Objects](#) (on page 112).

Fields on the Cover Page Tab

The following table summarizes the Cover Page fields and what they contain. The fields on the Cover Page tab vary from one change type to another.

In Web Client, the Cover Page can contain two additional sections, called Page Two and Page Three by default. In Java Client, these are separate tabs. The Agile administrator determines whether these sections are enabled, and what they are called.

Field	How completed	Contents
Number	Automatically, when created.	The number assigned to the change when you create it.
Status	Automatically, when created; updated as the change moves through the assigned workflow.	Change status, described in Status on the Cover Page Tab (on page 115); if no workflow has been selected, this field is Unassigned.
Change Type	Automatically, when created.	The type of change selected when you create the change.
Change Category	Usually manually; can contain a default.	Category defined by the Agile administrator (can be selected from a drop-down list).
Description Of Change	Usually manually; can contain a default.	Maximum number of bytes is set by the Agile administrator; can be up to 1023 bytes, including spaces and carriage returns (which count as 2 bytes).
Reason For Change	Usually manually; can contain a default.	Maximum number of bytes is set by the Agile administrator; can be up to 1023 bytes, including spaces and carriage returns (which count as 2 bytes).
Reason Code	Usually manually; can contain a default.	Code defined by the Agile administrator (can be selected from a drop-down list).
Workflow	Automatically (if only one workflow applies to the change), when the change is moved to the next status from the Unassigned status. If more than one workflow applies to the change, the workflow is selected manually; the workflow selection can be changed as long as the change is in the Pending status type. Selecting the blank field in the Workflow drop-down list switches the change to the Unassigned status.	The name of the workflow being used to move this change through the change control process.

Field	How completed	Contents
Change Analyst or Component Engineer	May be provided automatically by the workflow; otherwise selected manually from an address book list of change analysts or component engineers.	Default routing manager. If the workflow is defined to notify the default change analyst or component engineer, the user in this field receives notifications about the change. If this field is left blank, then the notifications are sent to every change analyst or component engineer on the list. If the notification definition in the workflow is blank, no notifications are sent.
Originator	Usually automatically, when created (with the default set by the Agile administrator).	The user who created the change (can be selected from a drop-down list).
Date Originated	Usually automatically, when created.	The date the change was created.
Date Released	Automatically, when released.	The date the change was released.
Final Complete Date	Automatically, when the change enters the Complete status type.	The date the change moved into the Complete status type.
Product Line(s)	Usually manually; can contain a default.	Product line defined by the Agile administrator (can be selected from a drop-down list).
Effective From	Manually.	Deviations only. The date the deviation goes into effect.
Effective To	Manually.	Deviations only. The date the deviation is no longer in effect.
Resume Date	Manually.	Stop Ships only. The date the stop ship is no longer effective and the company can resume shipping of the item.

The Cover Page tab for deviations has two unique fields, Effective From and Effective To. The Cover Page tab for stop ships has one unique field, Resume Date.

The Cover Page tab for MCOs has a Component Engineer field (in the place of a Change Analyst field).

For information about all change object tabs, see [Change Objects](#) (on page 112).

Status on the Cover Page Tab

A label in the top right corner of a change indicates the status of the change. The Agile administrator defines the name of each status in each workflow.

Note The Agile administrator may have created customized workflows and statuses for your company. The table below lists only the 12 Agile default workflow statuses.

Status name	Status definition
Unassigned (no status type)	No workflow has been assigned to this change. The originator may still be developing the change. No statuses are displayed on the Workflow tab.
Pending (Pending status type)	The originator may still be developing the change. It has not yet been approved or perhaps even completed.
Submitted (Submit status type)	The change has been routed to the change analyst or component engineer for review and analysis.
CCB (Review status type)	The change has been routed to the members of the change control board (CCB) for approval.
Released (Released status type)	The change has been signed off by the CCB members and released.
Closed (Complete status type)	The change is an ECR that has been accepted and implemented.
Expired (Complete status type)	The change is a deviation where the "Effective To" date has been reached.
Implemented (Complete status type)	The change is an ECO or SCO that has been implemented or incorporated into new drawings.
Hold (Hold status type)	The change has been placed on hold while information is being gathered by the component engineer.
Resumed (Complete status type)	The change is a stop ship that has been lifted. Production of affected items can resume.
Canceled (Cancel status type)	The change has been canceled due to a fundamental flaw or rejection by several people.
First Article Complete (Complete status type)	The manufacturer part has been received and passed incoming inspection or quality assurance. The physical part has been validated against design documents or specifications (MCO only).

The **Workflow** tab shows all the statuses the change has been through, and the statuses remaining to complete the change control process. See **Workflow Tab**.

With appropriate privileges, you can switch a change to another status with the **Workflow** tab or the **Next Status** button. For more information, see the chapter on workflows in *Getting Started with Agile PLM*.

For information about all change object tabs, see [Change Objects](#) (on page 112).

Affected Items Tab

The **Affected Items** tab lists the items that are affected by a change. Users with sufficient privileges can complete the **Affected Items** tab and use it to redline BOMs, manufacturing data, and attachments.

Note If you do not have Discovery and Read privileges for an item, it does not appear on the Affected Items tab. You may see a message telling you how many items are not displayed.

To open an item listed on the Affected Items tab:

- In Java Client, double-click the affected item row. The item opens with the Title Block tab on top.
Or, right-click the item row, choose Open, then choose a tab. The item opens with the selected tab on top.
- In Web Client, click the item number. The item opens with the Title Block tab on top.

The revision associated with the change is selected in the Rev drop-down list.

For information about all change object tabs, see [Change Objects](#) (on page 112).

For information about working with Affected Items tabs, see the chapter, [Affected Items of Changes](#) (on page 131).

Workflow Tab

The Workflow tab shows all the statuses the change has passed through, and which statuses remain to be completed. It also shows all the approvals and rejections made during each approval cycle.

For example, suppose a change is returned to the originator, reworked, and then resubmitted for a second approval cycle. The Workflow tab shows the approvals and rejections of the change made during the first approval cycle, and during the second approval cycle.

Depending on where the change is in the workflow, the Workflow tab can have up to three sections:

- [Workflow Overview Section](#) (on page 117)
- [Summary Table](#) (on page 118)
- [Signoff History Table](#) (on page 118)

For information about all change object tabs, see [Change Objects](#) (on page 112).

See also: [User Action Timestamp](#) (on page 119).

Workflow Overview Section

The top section of the Workflow tab (visible for all changes that have been assigned a workflow) displays the name of the assigned workflow and a flowchart of the workflow, highlighting the current status of the change.

Some of the statuses in the flowchart are links. Links are underlined. You can switch the change to one of these statuses by clicking the link and filling in the Notify field. You need sufficient privileges to do this.

In Java Client, the status with a yellow background is the current status.

In Web Client, the status with an orange background is the current status.

See also: [Workflow Tab](#) (on page 117), [User Action Timestamp](#) (on page 119).

Summary Table

The Summary table (visible for changes in a Review or Released status) lists the signoff information for the current status. It has the following columns by default; the Agile administrator may have modified the table:

- Action – the action taken by the reviewer.
- Req'd – whether the reviewer is a required reviewer (approver) or not (observer).
- Reviewer – the user who reviewed the change. This can be an approver or an observer, and it can be a single user or a user group.
- Signoff User – the name of the user who actually approved or rejected the change.
- Local Client Time – the date and time of the action.
- Signoff Comments – any comments made by the reviewers (approvers and observers) during signoff.





See also: [Workflow Tab](#) (on page 117), [User Action Timestamp](#) (on page 119).

Signoff History Table



The History table of the Workflow tab lists past workflow and signoff information for the change. It has the following columns by default; the Agile administrator may have modified the table:

- Workflow – the name of the workflow that the change is following.
- Workflow Status – the name of the status.
- Action – the action taken by the reviewer.
- Req'd – whether the reviewer is a required reviewer (approver) or not (observer).
- Reviewer – the user who reviewed the change. This can be an approver or an observer, and it can be a single user or a user group.
- Signoff User – the name of the user who actually approved or rejected the change.
- Status Changed By – the name of the user who switched the status.
- Local Client Time – the date and time of the action.
- Signoff Comments – any comments made by the reviewers (approvers and observers) during signoff.

The Add Approvers/Observers and Remove Approvers/Observers actions are controlled by the Ad Hoc Approvers/Observers property settings for each workflow. In addition, you must have the appropriate privileges to add or remove approvers and observers. If the Agile administrator has not granted the appropriate privileges to you, the buttons on the Workflow tab are not available, and you cannot perform the actions.

In Java Client, the Add Approvers/Observers  and Remove Approvers/Observers  buttons appear at the top left of the Workflow tab. To add approvers or observers, and click  and select the workflow status you want in the dialog. To remove an approver or observer, click  and choose

the status you want in the dialog.

In Web Client, the  Add Approvers/Observers and  Remove Approvers/Observers buttons appear at the top left of the Workflow tab. Click the button for the action you want to perform, then follow the wizard steps.

See also: [Workflow Tab](#) (on page 117), [User Action Timestamp](#) (on page 119).

User Action Timestamp

Agile PLM provides two ways to record the date and time of any action taken against the change:

- Local Client Time – This is the date and time as shown on the local client computer of the user who is viewing the timestamp. Local client time is the default method of viewing timestamps.

For example, if Mary approves a change at 12 noon in New York (Eastern time), when John looks at the Workflow tab of the change in California, he sees the time Mary approved the change as 9 o'clock in the morning (Pacific time).
- User Action Time – This is the date and time on the computer where the action was performed. User action time is optional.

If Mary approves a change at 12 noon in New York, when John in California looks at the Workflow tab of the change, he sees the following:

- In the Local Client Time column, the time Mary approved the change is 9 o'clock in the morning (Pacific time).
- In the User Action Time column, the time Mary approved the change is 12 noon (Eastern time).

When Mary looks at the Workflow tab of the change, she sees the following:

- In the Local Client Time column, the time she approved the change is 12 noon (Eastern time).
- In the User Action Time column, the time she approved the change is 12 noon (Eastern time).

Local Client Time always appears on the Workflow tab and History tab. User Action Time is optional, and is displayed on the Workflow tab of changes and the History tab of any Agile object only if the Agile administrator specifies this.

See also: [Workflow Tab](#) (on page 117).

Relationships Tab

The change object Relationships tab allows you to create relationships and dependencies between the change object and other routable objects and lifecycle objects. The Rule column displays the rule that defines how the workflow status or lifecycle phase of other objects affect the workflow progression of the current change object, or how the workflow progression of the current change object affects the workflow progression of the objects.

A relationship without a specified rule does not limit or affect the workflow progression or lifecycle status of either the current change object or the related object. You can use non-rule relationships to record objects that are somehow related to the current change object, but do not have any dependencies with the current change object.

For more information about relationships and how to use this tab, see the chapter about working with business objects in *Getting Started with Agile PLM*.

For information about all change object tabs, see [Change Objects](#) (on page 112).

Attachments Tab

All objects have an Attachments tab. On the Attachments tab, you can attach files and URLs to the object by referencing those files and URLs in a file folder object. On the Attachments tab, you can view, copy (get), or print attached files if you have the appropriate privileges.

Individual attached files are stored in file folder objects and can be attached to multiple objects. The files in a file folder object can be drawings or scanned images, documents, non-viewable files, compressed files, and so on.

For detailed information about working with file folder objects and the Attachments tab, see *Getting Started with Agile PLM*.

Note	Files that pertain to an item should be referenced on the Attachments tab of the <i>item</i> , rather than the Attachments tab of a change that affects the item.
------	---

For information about all change object tabs, see [Change Objects](#) (on page 112).

History Tab

The History tab shows a summary of actions taken against an object, including a description of the action, which user took the action, the date of the action, and other details.

Note	If you do not have the appropriate Read privilege for an object, you cannot see the contents of the fields on the History tab. See Details about Discovery and Read Privileges (on page 183).
------	---

The History tab shows a summary of actions taken against the change, including:

- The current status of the change
- The next status of the change
- A description of the action
- Which user took the action
- The date and time of the action (local client time)
- The user action time (optional; see [User Action Timestamp](#) (on page 119))
- Which affected object was the subject of the action
- The find number of the component of the affected item
- Details of the action
- Comments made by users
- Users notified

While the change status is Unassigned or Pending, the following actions are recorded on the History

tab:

- The creation of the change.
- Any subclass modifications.
- Any actions on the Relationships tab and the Attachments tab.

Note	Actions for changes that have not moved out of the Pending status types are recorded for modifications to the Relationships tab and Attachments tab only. A change must have a status type other than Pending, such as Submit or Review, before other actions are recorded on the History tab.
------	--

The types of actions recorded after a change moves out of the Pending status are:

- Modify or remove an item on the Affected Items tab
- Redline an item on the redlines tab of the Affected Items tab
- Add, get, or check in or out a file attachment through the Attachments tab of the change
- Add or remove approvers
- Approvals and rejections
- Reminder notifications
- Escalation notifications
- Field change, any tab
- Status change
- Autopromotion failure
- Attempt to change status without satisfying status-specific criteria
- Subclass change
- Comments
- Send
- Print
- Subscribe
- Save As
- Share

When you make modifications to a date field on a change after the change has exited the Pending status type, Agile PLM records the dates and times in the Details column of the History tab using the local date and time on the computer where the Agile Application Server is installed. Agile PLM uses a static format, for example, 2003/08/02 15:00:23 (GMT - 07:00) (yyyy/MM/dd) (Greenwich Mean Time).


Comments on the History tab are different from the comments on the Workflow tab. Comments on the Workflow tab come from approvers and observers when they perform the online approval process. Comments on the History tab can be made by anyone with sufficient privileges at any time.

For information about all change object tabs, see [Change Objects](#) (on page 112).

Workflow Routings Inbox

You can view Agile changes that have been submitted to you in the Agile Workflow Routings Inbox.

To view the Workflow Routings Inbox in Java Client:

In the menu bar, click the small down arrow next to the Inbox button , and choose Workflow Routings.

To view the Workflow Routings Inbox in Web Client:

In the menu bar, click the Home button (or click the Inbox button, if it is displayed). Depending on the Preferred Inbox View setting in your user profile, either the Workflow Routings page appears, or you can click Workflow Routings under Inbox to display it.

You can also open your inbox from the shortcuts section of the navigation pane.

See also: [Routing Managers: Change Analyst and Component Engineer](#) (on page 129).

For detailed information about working with routable objects, see *Getting Started with Agile PLM*.


Changes and Manufacturing Sites

Changes can affect site-specific information. Before you add affected items to a change, specify the manufacturing site that you want to affect. For general information about sites, see the chapter [Sites and Distributed Manufacturing](#) (on page 35).

This section includes the following topics.

- [Site Information Affected by Changes](#) (on page 123)
- [Sites and ECOs](#) (on page 123)
- [Sites and MCOs](#) (on page 124)
- [Site Change Orders](#) (on page 124)

For information about working with the Affected Items tab, see the chapter [Affected Items of Changes](#) (on page 131).



Site Information Affected by Changes

The following data is subject to change control:

- Site-specific portion of the BOM
- Site-specific portion of the AML
- Dispositions
- Effectivity dates
- Release of a site association after the item is released

All of the above data can be directly edited before it is released. After the data is released, BOM and AML data may be redlined via an ECO, MCO, or SCO. A new item revision is not required, but will be made if the modification is made using an ECO.

See also: [Changes and Manufacturing Sites](#) (on page 122).

Sites and ECOs

You can use an ECO to perform the following site-related actions:

- Modify the common or site-specific BOM of an item.
- Modify the common or site-specific AML of an item.

- Modify dispositions site-specifically.
- Modify the effectivity and obsolete dates of site-specific items.

See also: [Changes and Manufacturing Sites](#) (on page 122).

Sites and MCOs

You can use an MCO modify the common and site-specific AML of an item or change the lifecycle phase of an item.

You can use MCOs for all sites. For example, let's say there are two competing MCOs with site-specific information. When the first MCO is released, the pending MCO is rebased to the newly released MCO. In a similar manner, if a pending MCO has competing site-specific redlines with a pending ECO or SCO, when the ECO or SCO is released, the pending MCO is rebased to the newly released ECO or SCO.

See also: [Changes and Manufacturing Sites](#) (on page 122).

Site Change Orders

You can use site change orders (SCOs) to make site-specific changes to an item without changing the revision of the parent item.

With SCOs, you can modify the effectivity and obsolete dates, and the dispositions of previous revisions of an item, on a site-by-site basis. This allows you to use an explicit process to propose, review, and approve the modification of effectivity dates and to record the reasons why the effectivity dates were changed.

Note	You cannot use an SCO to make redline modifications to a previous revision of an item. All redline modifications must be made to the latest released revision of an item.
------	---

You can use an SCO to do the following:

- Modify the site-specific BOM of an item for latest revisions.
- Modify the site-specific AML of an item for the latest revisions.
- Modify the site-specific dispositions. Includes latest and non-latest revisions.
- Modify the effectivity and obsolete dates of site-specific items. Includes latest and non-latest revisions.

More than one site can be affected by an SCO, however, each row on the Affected Items tab applies to only one site. Duplicate items are not allowed; for example, if you add item P001 for site A, you cannot also add P001 for site B. You cannot use an SCO to modify the common site portion of the BOM or AML. Also, you cannot use an SCO to modify the BOM of an item that has not been released by an ECO; that is, an SCO cannot modify preliminary BOMs.

See also: [Changes and Manufacturing Sites](#) (on page 122).

Site-Specific Effectivity and Obsolete Dates

You can use an SCO to add site-specific effectivity and obsolete dates of an item *without creating a new revision of the item*. (Use an ECO if you want to create a new revision.)

When items are added to the Affected Items tab of the SCO, the system checks to see if each of the BOM items lists the site on the Sites tab. Depending on Agile SmartRule settings, if a site is not listed, the SCO may not be released, and the site must be added to the item in order to release the SCO.

Note	Releasing the SCO sends the item and BOM information to the ERP system of the site. Depending on your ERP system, if the SCO is against a revision of the item other than the latest revision, this could result in a different current revision in the ERP system.
------	---

At the time you add an item to the Affected Items tab of an SCO, you select an ECO-released item revision. The dispositions and the effectivity and obsolete dates on the SCO Affected Items tab are initially set to be the same as the latest effectivity and obsolete date of that revision. (The latest effectivity and obsolete dates are derived from the ECO-released revision or from a previously released SCO based on the ECO-released revision.) You can then specify site-specific dispositions and site-specific effectivity and obsolete dates. If the dispositions and effectivity and obsolete dates of the ECO-released item revision are modified after you have added the item to the SCO Affected Items tab, these fields are not automatically updated on the SCO Affected Items tab. Instead, your site-specific dispositions and effectivity and obsolete dates are maintained on the SCO.

Note	If you rebase the SCO Affected Items tab row by selecting a different ECO-released item revision, the dispositions and the effectivity and obsolete dates on the SCO Affected Items tab row are also rebased and set to be the same as the newly selected ECO-released revision.
------	--

See also: [Changes and Manufacturing Sites](#) (on page 122), [Site Change Orders](#) (on page 124).

The Relationship of Changes to Item Revisions

This section describes the rules Agile PLM uses to determine which revision of an item is affected by the change and offers additional guidelines. For more information about item revisions, see [Working with Item Revisions](#) (on page 13).

Items with an ECO Revision Only

- A pending or released SCO can be based only on a revision created by a released ECO.
- An ECO cannot be unreleased if there is a pending or released SCO based on it.

MCOs on Items with ECO Revisions



- When a new ECO is created and released, and a pending MCO exists against a *previous* revision of the item, the MCO changes to be based on the new ECO revision, and it inherits content from the new revision.
- An MCO cannot be unreleased if there is a released SCO based on it.

Items with an Initial MCO Revision Only

When an MCO is released against the item before the item is released by an ECO (called an *initial* MCO revision, or *blank* revision), a pending SCO *cannot* be based on the blank revision.

Creating Changes

To create a change, you must have the appropriate privilege.

In Java Client, you can create a change with the File | New | Change command, the New Object button , or the Save As command, on the More Actions menu (click the More button  at the top of the object window) and on the right-click shortcut menu.

In Web Client, you can create an item with the Create  | Change command or the Actions | Save As command.

Note For a site change order (SCO), when you add an item to the Affected Items table, if the selected site is not listed on the Sites tab of the item, you are prompted to add it to the Sites tab of the item. If you later cancel the SCO, or remove the item from the Affected Items table, the new site assignment remains on the Sites tab of the item.

In Web Client, when you create a change, the create wizard allows you to add items to the Affected Items table of the change. If you cancel the change creation wizard, and do not complete the creation of the SCO, any new site assignments remain on the Sites tabs of the items.

For more information about creating changes and other objects, see *Getting Started with Agile PLM*.

Note Once a change is created, it exists until you delete it. If you create a new change, then decide you do not wish to keep it, be sure to delete the change (soft-delete, then hard-delete); otherwise, the new change remains in the database, and the number cannot be reused. For information, see [Deleting Changes](#) (on page 128).

See also: [Modifying Changes](#) (on page 126).

Site Change Order Save As Limitations

You cannot initiate Save As from a non-Site Change Order (SCO) change object in order to create an SCO object, nor can you initiate Save As from an SCO object in order to create a non-SCO change object. Because Site Change Orders (SCOs) affect only site-specific information, and other types of changes are not limited to site-specific information (for example, ECOs and MCOs), SCOs can be Save-As-created only from another SCO. The Site Change Order's site-specific only usage makes it incompatible with other change types when using the Save As feature.

Modifying Changes

With sufficient privileges, you can modify editable fields. You can modify only fields that have been made editable by the Agile administrator.

To edit a change:

1. On the Cover Page tab:
 - In Java Client, modify the appropriate fields. Click Save when you finish editing the Cover Page tab.

- In Web Client, click Edit to put the Cover Page tab in edit mode. Modify the appropriate fields. Click Save when you are finished.
- 2. On the Affected Items tab, you can remove, add, and edit rows of affected items. (For more information, see [Adding an Item to the Affected Items Tab](#) (on page 139).)
- 3. On the Relationships tab, you can add, edit, or remove relationships, and you can add, edit, or remove relationship rules. (For more information, see *Getting Started with Agile PLM*.)
- 4. On the Attachments tab, you can add and remove references to files and URLs in file folder objects. (For more information, see *Getting Started with Agile PLM*.)

You cannot edit information on the Workflow or History tabs; those tabs are completed automatically.

See also: [Creating Changes](#) (on page 126).

Agile Change Control Workflows

An Agile workflow is a sequence of statuses that a change follows as it goes through the change control process. The Agile administrator specifies the name of the workflow, the number and names of the statuses, and the properties that define each status.

See also: [Routing Managers: Change Analyst and Component Engineer](#) (on page 129).

For more information about routing changes and other Agile objects through workflows, see *Getting Started with Agile PLM*.

Redlining through ECOs, MCOs, and SCOs

Redlining highlights, in red, changes made to an object. ECOs, MCOs, and SCOs are the only changes that have redlining functions. Use these changes when you need to modify a released item. For information about the functions of these types of changes, see [Change Classes](#) (on page 111).

This section contains the following topics:

- [Redlining through ECOs](#) (on page 128)
- [Redlining through MCOs](#) (on page 128)
- [Redlining through SCOs](#) (on page 128)

Depending on your company policy, when you redline manufacturing data, use an ECO when you want to advance the revision of an item, or use an MCO when you *don't* want to advance the revision of an item.

For information about redlining a BOM, see [Redlining the BOM of a Released Item](#) (on page 104).

For information about redlining an AML, see [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).

For information about redlining attachments, see *Getting Started with Agile PLM*.

Redlining through ECOs

You can redline BOM and AML data and attachments using an ECO.

ECOs let you release new items and modify previously released items. When you create an ECO, a preliminary revision is created for any items modified by the change (the ones listed on the Affected Items tab). When the ECO is released, the preliminary revision is converted to a released revision for each modified item.

Redlining through MCOs

You can redline AML data using an MCO.

MCOs are similar in appearance and function to an ECO. However, MCOs do not change the revision of an item, unlike an ECO. Instead, the MCO number is displayed alongside the corresponding revision number in the Rev drop-down list. For example, if there is a pending MCO #M12345 against Rev B of an item, then, on the Rev drop-down list, that revision is listed as (B) M12345.

MCOs can be used to:

- Release a new item without a revision (but you can select its lifecycle phase)
- Modify the lifecycle phase of an item without changing its revision
- Redline manufacturing data (add, modify, or delete) on items (Manufacturers tab)

Redlining through SCOs

You can redline site-specific BOM and AML data using an SCO, but only against the latest released revision.

SCOs are similar in appearance and function to an ECO. However, SCOs do not change the revision of an item, unlike an ECO. Instead, the SCO number is displayed alongside the corresponding revision number in the Rev drop-down list. For example, if there is a pending SCO S12345 against revision B of an item, then, on the Rev drop-down list, that revision is listed as (B) S12345.

Deleting Changes

For important details about deleting change objects, see [Deleting Agile Objects](#) (on page 23).


Undeleting Changes

Since soft-deleted changes still exist in the database, you can undelete them if you have the necessary privileges, and if the change has no items on the Affected Items tab.

For more information on undeleting changes and other objects, see *Getting Started with Agile PLM*.

Printing Change Tabs

You can print object tabs and other data from your Agile PLM system. You can print the current tab or all tabs. Attachments are printed from their native applications or the Viewer.

In Java Client, with the object open, use the Print button .

In Web Client, with the object open, choose Actions | Print.

For additional information about printing objects, see *Getting Started with Agile PLM*.

When you print the Affected Items tab, redline information is also included.

Routing Managers: Change Analyst and Component Engineer

Note For detailed information about how to perform routing manager tasks, see *Getting Started with Agile PLM*, Chapter 8, Routing Objects with Workflows.

The user who oversees the routing and approval process of a change is the routing manager. The routing manager for changes is called the change analyst, and the routing manager for manufacturing change orders (MCOs) is called the component engineer. The Change Analyst or Component Engineer field on the Cover Page tab of the change lists the routing manager for that change. These fields are filled in automatically (as designated by the Agile administrator in the workflow settings) or selected manually by the user from a drop-down list.

Routing managers evaluate and assign changes, and they receive email notifications pertaining to the change objects to which they are assigned. Specific roles and privileges are required to perform the tasks of a routing manager. If you have questions about your assigned roles, contact the Agile administrator.

The following is an example of a typical change control process for a change using default Agile workflows:

1. A change (for example, an ECO or MCO) is created, and a workflow is selected.
2. The change is submitted to the change analyst (ECO) or component engineer (MCO).
3. The change analyst or component engineer switches the change to the next status, which routes the change to the specified approvers (members of the change control board) and observers.
4. The members of the change control board (CCB) either approve or reject the change, and their approval or rejection is recorded on the Workflow tab of the change.
5. If all the approvers approve the change, it is automatically promoted to the Released status (the next status).

Note Agile Administrator settings, including workflow settings and SmartRule settings, control when a change can be autopromoted. These settings determine the required fields that must be completed, the required actions of the approvers, and other conditions that must be met for autopromotion.

If any approvers reject the change, the change analyst or component engineer is notified and

either:

- Cancels the change by switching the status to Canceled.
- Returns the change to the originator by switching the status to Pending.
- Releases the change in spite of the rejection.

Depending on the workflow settings, the change may automatically be switched to a specified status when an approver rejects it.

For detailed information about working with and managing changes, see the chapter about routing objects with workflows in *Getting Started with Agile PLM*.

See also: [Agile Change Control Workflows](#) (on page 127).

Affected Items of Changes

This chapter includes the following:

▪ Affected Items Tab.....	131
▪ Affected Items by Manufacturing Site	138
▪ Viewing the Disposition of Parts in an ECO or SCO.....	139
▪ Adding an Item to the Affected Items Tab	139
▪ Working with the Affected Items Table	147
▪ Removing an Item from the Affected Items Tab	151
▪ Editing Rows in the Affected Items Tab.....	152
▪ Viewing the Redlines of an Affected Item.....	155

Affected Items Tab

This section includes the following topics:

- [Buttons on the Affected Items Tab](#) (on page 132)
- [Fields on the Affected Items Tab](#) (on page 133)

The Affected Items tab of a change lists the items that are affected by the change. If an item belongs to multiple manufacturing sites, then the default Affected Items row values are the default value for each site row. Users with sufficient privileges can use the Affected Items tab to:

- List the items affected by a change and give those items a pending revision (ECOs)
- Specify the revision of the item that is affected by the change (SCOs, ECRs, Deviations, Stop Ships)

Note	ECOs and MCOs affect only the most recently released revision of the item.
-------------	--

- View items listed on the Affected Items tab
- Create, view, or modify the Redline BOM tab data of affected items (ECOs and SCOs)
- Create, view, or modify the Redline Manufacturers tab data of affected items (SCOs, and MCOs; ECOs if SmartRule is set to allow it)
- Add redlines to attachments of items through the Redline Attachments tab (ECOs only)
- Specify the disposition of existing parts (ECOs, MCOs, SCOs, ECR, Deviation, and Stop Ship)

Users with Read privileges can:

- Open affected items
- Redline affected items (ECOs, MCOs, and SCOs)
- View the disposition of existing parts (ECOs, MCOs, and SCOs); you must scroll to the right to bring the disposition fields into view.

Note If you do not have the Discovery privilege for an item, it does not appear on the Affected Items tab. You may see a message telling you how many items are not displayed. Depending on your Read privileges, you may not be able to view all the fields on the Affected Items tab.










To open an item listed on the Affected Items tab:

- In Java Client, double-click the affected item row. The item opens with the Title Block tab on top. Or, right-click the item row, choose **Open**, then choose a tab. The item opens with the selected tab on top.
- In Web Client, click the item number. The item opens with the Title Block tab on top.













The revision associated with the change is selected in the Rev drop-down list.

Buttons on the Affected Items Tab

The following buttons on the Affected Items tab in Java Client are available or unavailable, depending on your privileges and whether it is appropriate to use them.

Button	Description
Edit Affected Items 	Displays the selected (checked) item in edit mode.
Remove 	Deletes the selected item from the Affected Items table.
	<p>Add — Adds an item below the selected item. Depending on which option you choose, you can:</p> <ul style="list-style-type: none">  Create an item while adding it.  Search for an existing item.  Type in Known Number(s) of one or more existing items.
Fill Down Rows, Fill Up Rows 	Copies the values in each column of the first selected row (for Fill Down) or the last selected row (Fill Up), and pastes them into the corresponding cells of all other selected rows. See Fill Up Rows and Fill Down Rows Buttons in Java Client (on page 153).
BOM Bulk Change 	Applies a change of an item to multiple BOMs that use the item.
Manufacturer Part Bulk Change 	Applies a change of an item to multiple AMLs that use the item.
View drop-down list	<p>Select Show Sites to list the site-specific information for each affected item. Each item is listed in multiple rows in the table, once for the default or common display of the item (the Sites field is blank) and once for each site associated with the item (the Sites field contains the appropriate site name.)</p> <p>Select Hide Sites to list only the default or common information of the item. Each item is listed only once in the table, and the Sites field is blank.</p>

The following buttons on the Affected Items tab in Web Client are available or unavailable, depending on your privileges and whether it is appropriate to use them.

Button	Description
 Edit	Displays the selected (checked) item in edit mode.
 Remove	Deletes the selected item from the Affected Items table.
 Add  Add  Add	Add — Adds an item below the selected item. Depending on which option you choose, you can:  Create an item while adding it.  Search for an existing item.  Type in Known Number(s) of one or more existing items.
Bulk Change	Applies a change of an item to multiple BOMs or AMLs that use the item.
 	Fill Up Fill Down (Appear in Edit mode only. Appear next to each attribute that can be filled up or down.) Copies the value of the field where the button is clicked to the fields above (Fill Up) or below (Fill Down) in the column of the selected rows. See Editing Affected Items Tab Rows in Web Client (on page 154).
 	Copy Paste Appear in Edit mode only. Allows you to copy and paste data from one row to another. Use the column header checkboxes or Copy button menu selection to select the columns you want to copy. Select the row, then click Copy . Select another and click Paste .
View drop-down list	Select Show Sites to list the site-specific information for each affected item. Each item is listed in multiple rows in the table, once for the default or common display of the item (the Sites field is blank) and once for each site associated with the item (the Sites field contains the appropriate site name.) Select Hide Sites to list only the default or common information of the item. Each item is listed only once in the table, and the Sites field is blank.

Fields on the Affected Items Tab

The following table shows the Affected Items fields for each change class.

Affected Items tab field	ECO	MCO	SCO	ECR	Stop ship	Deviation
Sites	✓	✓	✓			
Item Number	✓	✓	✓	✓	✓	✓
Old Rev	✓					
Old Lifecycle Phase	✓	✓				
Obsolete Date	✓		✓			
New Rev	✓					
Revision			✓	✓	✓	✓
Effective Date	✓		✓			
Lifecycle Phase	✓	✓		✓	✓	✓
Change Function	✓					
Old Item Description (appears only if enabled)	✓					
Item Description	✓	✓	✓	✓	✓	✓
On Order	✓		✓			
Stock	✓		✓			
Work in Progress	✓		✓			
Finished Goods	✓		✓			
Field	✓					

Note	All required fields must be completed before a change can be released. (A user with Override privilege can release a change without filling in the required fields.) The Agile administrator determines which fields are required, but the New Rev field on an ECO is always required and cannot be overridden. Perform a status audit or release audit to verify that all required fields have been completed. For more information about auditing, see the chapter on workflows in <i>Getting Started with Agile PLM</i> . See the Agile administrator if you have questions about required fields.
------	---

Sites Field in Affected Items Table

The Sites field indicates the manufacturing site for which the affected item was added. When the Sites field is blank, it indicates that the row shows information about the item that is common among all sites assigned to the item.

Old Item Description and Item Description

If the Agile administrator has configured the Agile system so that a released item's Description field can be changed only by using the Affected Items tab of a change order, the affected items table will include both the Old Item Description field and the Item Description field (which might be renamed to New Item Description).

If your Agile system is configured for change order modification of the item's Description field, the Old Item Description field is filled in automatically when you add the item to the Affected Items tab. You cannot modify the Old Item Description field on the Affected Items tab. However, if you have the appropriate privileges, you can enter a new description in the affected items table (New) Item Description field. This description appears in the Description field of the pending revision of the item.

The Item Description field (or New Item Description field) of a released change order cannot be used to modify an item's Description field; the released item's Description field can only be modified through the item's Title Block tab, with the appropriate modify item privileges. Once the change order with the item on its Affected Items tab is released, even though you may have a modify privilege for released change orders, the change order Item Description field of released change orders cannot be modified, and therefore cannot be used to modify the item's Description field.

For more information about modifying the item Description field, see [Editing a Released Item's Description Field](#) (on page 27).

Important The item Description field cannot be modified through an MCO because an MCO does not create a new item revision. The MCO uses the Description field information from the ECO revision or Introductory revision on which it is based.

Revision

The Revision field indicates which revision of the item is affected by the change. The following table explains which item revisions can be affected by each kind of Agile change.

Change class	Can be edited?	Default revision when item is added to Affected Items table
Change Order (ECO)	No	<p>When an item is added to the Affected Items table of a change order, the most recently released revision of the item appears in the Old Rev field.</p> <p>You cannot edit the ECO Affected Items table Old Rev field.</p> <p>Change orders always affect the most recently released revision of the item. If the item has never been released, then the change order affects the Introductory revision of the item. An ECO creates a new revision of the item and you must specify a new revision number or letter in the Affected Items table New Rev field.</p> <p>Note: A change order is the only Agile change object that can create a new item revision.</p> <p>For more information about ECOs, see Special Considerations for ECOs (on page 147)</p>
Manufacturer Change Order (MCO)	—	<p>Manufacturer change orders always affect the most recently released revision of the item. If the item has never been released, then the MCO affects the Introductory revision of the item.</p> <p>The item revision number upon which the MCO is based is not displayed on the Affected Items tab if an MCO.</p> <p>For more information about MCOs, see Special Considerations for MCOs (on page 148).</p>
Site Change Order (SCO)	Yes	<p>When an item is added to the Affected Items table of a site change order, the most recently released revision of the item appears in the Revision field.</p> <p>You can edit the SCO Affected Items table Revision field to select a different item revision.</p> <p>An SCO can affect any released revision of the item. An SCO cannot affect an Introductory revision of an item.</p> <p>Only one revision of an item can be included on the Affected Items table of an SCO</p>
Engineering Change Request (ECR)	Yes	<p>When an item is added to the Affected Items table of an engineering change request, the Revision field is blank. When the Revision field is blank, the ECR will affect the most recently released revision. Only released revisions are available for selection in this field. Pending revisions do not appear in this field. If the item has never been released, then the engineering change request affects the Introductory revision of the item.</p> <p>You can edit the ECR Affected Items table Revision field to select a different item revision.</p>

Change class	Can be edited?	Default revision when item is added to Affected Items table
Deviation	Yes	<p>When an item is added to the Affected Items table of a deviation, the Revision field is blank. When the Revision field is blank, the deviation will affect the most recently released revision of the item. If the item has never been released, then the deviation affects the Introductory revision of the item.</p> <p>You can edit the deviation Affected Items table Revision field to select a different item revision.</p>
Stop Ship	Yes	<p>When an item is added to the Affected Items table of a stop ship, the Revision field is blank. When the Revision field is blank, the stop ship will affect the most recently released revision of the item. If the item has never been released, then the stop ship affects the Introductory revision of the item.</p> <p>You can edit the stop ship Affected Items table Revision field to select a different item revision.</p>

Obsolete Date and Effective Date

The Obsolete Date field applies to the prior revision of the affected item, not the new revision. The obsolete date is the date the old revision becomes obsolete.

The Effective Date field applies to the new revision, and reflects the date that the new revision becomes effective.

Lifecycle Phase and Old Lifecycle Phase

By default, the Lifecycle Phase list has the following entries (the Agile administrator can add more):

- Inactive – Temporarily not in use and may be reactivated.
- Obsolete – Permanently discontinue the item.
- Pilot – Build with limited initial quantities as a pilot project.
- Production – Release for regular production.
- Prototype – Produce in very limited quantities for testing.

The Old Lifecycle Phase field is filled in automatically when you add the item to the Affected Items tab. You cannot modify the Old Lifecycle Phase field on the Affected Items tab.

If the item has been released, when you add it to the Affected Items tab, the Lifecycle Phase field is automatically filled in with the item's current lifecycle phase; you can then modify the Lifecycle Phase field. If the item has never been released, when you add it to the Affected Items tab, initially both the Old Lifecycle Phase field and the Lifecycle Phase field are blank. You can then modify the Lifecycle Phase field.

Note	If you leave the Affected Items table Lifecycle Phase field blank and release the change order, Agile uses the Old Lifecycle Phase to determine the lifecycle phase of the released object.
------	---

Affected Items by Manufacturing Site

With a change order (for example, an ECO), you can view and work with affected items for a specific manufacturing site by selecting Show Sites in the View drop-down list on the Affected Items tab. Each item on the table is expanded to display a row for each site associated with the item. Sites displayed are the ones to which you have access.

For example, to work with part number P345 for the Hong Kong site, select the row for part P345 with the site name Hong Kong in the Sites field of the row.

With a site change order (SCO), you view and work with items for a specific manufacturing site by selecting the appropriate site when you add the item to the Affected Items table. The modifications you specify on an SCO apply only to the site selected for the item.

Fields That Allow Site-Specific Values

The following fields in the Affected Items table can contain values that differ by site:

- Disposition fields: On Order, Work in Progress, Finished Goods, Stock, Field
- Effective Date
- Obsolete Date

The following fields in the Affected Items table *cannot* contain values that differ by site:

- Item Description
- Old Item Description
- Lifecycle Phase
- Old Lifecycle Phase
- Old Rev
- New Rev

The Agile administrator uses the Site-Specific Field property to determine whether the other fields in the Affected Items table can contain values that differ by site.

Site-Specific Effectivity and Obsolete Dates


To modify or set the effective and obsolete date for a specific site, and nothing else is being done with the ECO, add the item to the Affected Items tab and create a new revision. If you do not want to create a new revision just for this modification, create an SCO and modify the effective and obsolete dates for the site on the SCO Affected Items tab.

Viewing the Disposition of Parts in an ECO or SCO

ECOs and SCOs have fields on the Affected Items table that specify what to do with existing parts affected by the change: On Order, Stock, Work In Progress, or Finished Goods. ECOs also include Field (for “in the field”). Each of these fields can have a list of disposition types defined by the Agile administrator. Examples of dispositions are Use, Scrap, and Rework.

Adding an Item to the Affected Items Tab

You can use the Add button to add an item to the Affected Items tab.

In Java Client, if you create a change from an open item by using the Create Change command on the More Actions menu (click the More button  at the top of the object window) and on the right-click shortcut menu. That item is added to the Affected Items tab automatically.

In Web Client, if you create a change from an open item by using Actions | Create Change, that item is added to the Affected Items tab automatically.

This section contains the following topics:

- [Using the Add Affected Items Wizard](#) (on page 139)
- [Performing Bulk Changes](#) (on page 140)
- [Special Considerations for ECOs](#) (on page 147)
- [Special Considerations for MCOs](#) (on page 148)
- [Removing an Item from the Affected Items Tab](#) (on page 151)

Note You cannot add an item that is locked by another user. An item is locked if a user has made modifications to the item, but has not yet saved those modifications. Once the item is saved, it is unlocked.

Using the Add Affected Items Wizard

Note Tip: An easy way to use the Add button on the Affected Items tab in both clients is to click it once. The dialog appears that allows you to enter the number of an item, if you know it. In this dialog, click the Create or Search link to use those add item methods. If you are adding affected items to an SCO, the Create link is not available.

To add an item to the Affected Items tab in Java Client:

Open a change, and display the Affected Items tab.

1. Click the Add drop-down menu button and choose one of the add options: Search, Type in Known Numbers, or Create.

Note If you are adding affected items to an SCO, the Create option is not available.

2. Depending on your menu selection, do one of the following:
 - Search – Search for one or more existing items. In the Add Affected Item dialog box, select

a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.) In the search results, select the items you want, and click OK. All the items in the Selected Affected Item(s) list are added to the Affected Items table.

- Type in Known Numbers – enter one or more numbers and click Add.
- Create – Select a type from the Type drop-down list. If appropriate, enter an object number. Click OK.

Note If you are adding affected items to an SCO, in the Add for Site drop-down list, select the site you want.

Adding items to the Affected Items table is similar to adding items to the BOM table. For more information about how to complete the dialogs, see [Search for Items to Add to the BOM Table](#) (on page 88), [Type in the Number of an Item to Add to the BOM Table](#) (on page 88), and [Adding Nonexistent Items to the BOM Table](#) (on page 94).

To add an item to the Affected Items tab in Web Client:

1. Open a change, and display the Affected Items tab.
2. On the BOM tab, click the Add button and choose one of the add options: Search, Type in Known Numbers, or Create New.

Note If you are adding affected items to an SCO, the Create New option is not available.

3. Depending on your menu selection, do one of the following:
 - Search – Search for one or more existing items. In the Add Affected Items dialog box, select a search method. If you choose to perform a simple search, enter the value to search for and click Search. You can also define an advanced search, run a saved search, or select a bookmarked or recently visited item (Shortcuts). (For more information about searches, see *Getting Started with Agile PLM*.) In the search results, select the items you want, and click OK. All the items in the Selected list are added to the Affected Items table.
 - Type in Known Numbers – enter one or more numbers and click Add.
 - Create New – Select a type from the Type drop-down list. If appropriate, enter an object number. Click OK.

Note If you are adding affected items to an SCO, in the Add for Site drop-down list, select the site you want.

Adding items to the Affected Items table is similar to adding items to the BOM table. For more information about how to complete the dialogs, see [Search for Items to Add to the BOM Table](#) (on page 88), [Type in the Number of an Item to Add to the BOM Table](#) (on page 88), and [Creating an Item Using Add](#) (on page 21).

Performing Bulk Changes

You can create an ECO that automatically adds, replaces, or removes an item from the assemblies on several BOMs at one time. Likewise, you can create an ECO or MCO that automatically replaces or removes a manufacturer part on the AML (Manufacturers tab) of several assemblies at one time. Such changes are called *bulk changes* and are created with a Bulk Change wizard.

The following sections explain how to use the bulk change features:

- [BOM Bulk Changes Overview](#) (on page 141)
- [Java Client BOM Bulk Change Wizard](#) (on page 141)
- [Web Client BOM Bulk Change Wizard](#) (on page 143)
- [Manufacturer Part \(AML\) Bulk Changes Overview](#) (on page 144)
- [Java Client Manufacturer Part Bulk Change Wizard](#) (on page 145)
- [Web Client Manufacturer Part Bulk Change Wizard](#) (on page 146)

BOM Bulk Changes Overview

BOM bulk changes are available only from ECOs. The BOM Bulk Change wizard from an ECO gives you two options in the first wizard step:

- Add an item to multiple assemblies.
- Replace or remove an item from multiple assemblies.

If you select the option to replace or remove an item from multiple assemblies, the BOM Bulk Change wizard gives you the option to:

- Remove an item from all or some of the assemblies that use the item, and automatically redline the BOM of the assemblies affected by the Bulk Change.
- Replace an item in all or some of the assemblies that use the item, and automatically redline the BOM of the assemblies affected by the Bulk Change.
- Just add the selected assemblies to the Affected Items tab and manually redline their BOMs.


Java Client BOM Bulk Change Wizard


The Java Client BOM Bulk Change wizard allows you to specify modifications to multiple assemblies at one time. You have two BOM bulk change options:


- Add one item to multiple assemblies.
- Replace or remove one item from multiple assemblies.

The two procedures vary slightly; however, each wizard dialog guides you through the process. Both procedures are described below.

To add an item to multiple assemblies, Java Client:

1. From a pending or unassigned change, click the Affected Items tab to bring it forward. (You can use an existing change or create a new one.)
2. Click the BOM Bulk Change button .

The BOM Bulk Change wizard appears.
3. Select the option Add an Item to multiple Assemblies, and click Next.
4. In the next wizard dialog, you specify the item that you want to add to multiple assemblies. Type an item number, or click  to search for the item. In the Select Objects dialog, you can click the Create link to create a new item. After you specify an item number, click Next.
5. In the next wizard dialog, you specify which assemblies this bulk change will affect. Click the

Add button  to search for the assemblies to which you want to add the item selected in step 4. After you specify the assemblies, click Finish.


The redlined assemblies are added to the Affected Items table. You can view the change on the Redline BOM tab.

To replace or remove an item from multiple assemblies, Java Client:


1. From a pending or unassigned change, click the Affected Items tab to bring it forward. (You can use an existing change or create a new one.)

2. Click the BOM Bulk Change button .

The BOM Bulk Change wizard appears.

3. Select Replace or remove and item from multiple Assemblies, and click Next.
4. In the next wizard dialog, you specify the item that you want to redline (replace, delete, or otherwise modify) in the assemblies that use it. Type an item number, or click  to search for the item. After you specify an item number, click Next.
5. In the next wizard dialog, you specify which assemblies this bulk change will affect. From the displayed list of assemblies that use the item specified in step 4, select the assemblies you want to affect, then click Next.
6. In the next wizard dialog, you specify which action to perform. Your options are:

- Replace <item> on all selected assemblies with <item>.

That is, on the assemblies you selected in step 5, replace the item you selected in step 4 with the item you specify here. Type an item number, or click  to search for the item.

When you are done, click Next.

The redlined assemblies (selected in step 5) will be added to the Affected Items table. You can view the changes on the Redline BOM tab.

- Remove <item> from all selected assemblies

That is, remove the item you selected in step 4 from the assemblies you selected in step 5. Click Next.

The redlined assemblies (selected in step 5) will be added to the Affected Items table if they are not already in the Affected Items table. You can view the changes on the Redline BOM tab.

- Just add the selected assemblies to the Affected Items table and I will redline the BOMs myself.

That is, add the assemblies you selected in step 5 to the Affected Items table (if they are not already in the Affected Items table), but do not make any redline changes to the assemblies.

Click Finish.

The assemblies (selected in step 5) will be added to the Affected Items table if they are not already in the Affected Items table, and no redline changes will be made to them. Select an assembly in the Affected Items table, then make the redline changes you want on the Redline BOM tab.

The assemblies are added to the Affected Items table according to the option you selected in step 6 above.



Web Client BOM Bulk Change Wizard

The Web Client BOM Bulk Change wizard allows you to specify modifications to multiple assemblies at one time. You have two BOM bulk change options:

- Add one item to multiple assemblies.
- Replace or remove one item from multiple assemblies.


The two procedures vary slightly; however, each wizard page guides you through the process. Both procedures are described below.

To add an item to multiple assemblies, Web Client:

1. From a pending or unassigned change, click the Affected Items tab to bring it forward. (You can use an existing change or create a new one.)
2. Click the Bulk Change button and choose BOM from the menu.
3. In the Select Action wizard page, select Add an Item to Multiple assemblies, then click Next.
4. In the Identify Item To Add wizard page, you specify the item that you want to add to multiple assemblies. Type an item number, or click  to search for the item. In the Search Objects dialog, you can click the Create link to create a new item. After you specify an item number, click Next.
5. In the Identify Items to Add the item (*item number*) wizard page, you specify which assemblies this bulk change will affect. Click the  Add button to search for assemblies to which you want to add the item selected in step 4. After you specify the assemblies, click Finish.

The redlined assemblies are added to the Affected Items table. You can view the change on the Redline BOM tab.

To replace or remove an item from multiple assemblies, Web Client:

1. From a pending or unassigned change, click the Affected Items tab to bring it forward. (You can use an existing change or create a new one.)
2. Click the Bulk Change button and choose BOM from the menu.
3. In the Select Action wizard page, select Replace or remove an item from multiple assemblies, then click Next.
4. In the Identify Item To Replace or Remove wizard page, you specify the item that you want to redline (replace, delete, or otherwise modify) in the assemblies that use it. Type an item number, or click  to search for the item. After you specify an item number, click Next.
5. In the next wizard dialog, you specify which assemblies this bulk change will affect. From the displayed list of assemblies that use the item specified in step 4, select the assemblies you want to affect, then click Next.
6. In the Select Modify Action wizard dialog, you specify which action to perform. Your options are:
 - Replace Item Number on all selected assemblies with Item Number.

That is, on the assemblies you selected in step 4, replace the item you selected in step 5 with the item you specify here. Type an item number, or click Search to search for the item.

When you are done, click Finish.

The redlined assemblies (selected in step 4) will be added to the Affected Items table if they are not already in the Affected Items table. You can view the changes on the Redline BOM tab.

- Remove Item Number from all selected assemblies

That is, remove the item you selected in step 4 from the assemblies you selected in step 5. Click Finish.

The redlined assemblies (selected in step 4) will be added to the Affected Items table if they are not already in the Affected Items table. You can view the changes on the Redline BOM tab.

- Just add the selected assemblies to the affected items table and I will redline the BOMs myself.

That is, add the assemblies you selected in step 5 to the Affected Items table (if they are not already in the Affected Items table), but do not make any redline changes to the assemblies.

Click Finish.


The assemblies (selected in step 4) will be added to the Affected Items table and no redline changes will be made to them. Select an assembly in the Affected Items table, then make the redline changes you want on the Redline BOM tab.

The assemblies are added to the Affected Items table according to the option you selected in step 6 above.

Manufacturer Part (AML) Bulk Changes Overview

You can perform a manufacturer part bulk change from an ECO (with AML capabilities) or an MCO, which automatically replaces or removes a manufacturer part from the Manufacturers tab of several items at one time. Manufacturer part bulk changes are created with the Manufacturer Part Bulk Change wizard.

You can use MCOs to bulk-change manufacturers data without rolling the revision, and use ECOs to bulk-change manufacturers data when you want to roll the revision. Depending on your company policy, use an ECO or an MCO to determine if the revision of an item advances when you redline manufacturers data.



The Manufacturer Part Bulk Change wizard, from an MCO or an ECO, gives you the option to:

- Remove a manufacturer part from all or some of the parts that use it, and automatically redline the Manufacturers tab of the assemblies affected by the manufacturer part bulk change.
- Replace a manufacturer part in all or some of the parts that use it, and automatically redline the Manufacturers tab of the assemblies affected by the manufacturer part bulk change.
- Just add the selected manufacturer part to the Manufacturers tabs, and then go back later to manually redline it.


Java Client Manufacturer Part Bulk Change Wizard

To replace or remove a manufacturer part from multiple items, Java Client:


1. From a change that has not been released, click the Affected Items tab to bring it forward. (You can use an existing change or create a new one.)

2. Click the Manufacturer Part Bulk Change button .

The Manufacturer Part Bulk Change wizard appears.

3. In the first wizard dialog, you specify the manufacturer part that you want to redline (replace, delete, or otherwise modify) in the items that use it. Enter a manufacturer name and manufacturer part number, or click  to search for the manufacturer part you want. After you specify a manufacturer part, click Next.
4. In the next wizard dialog, you specify which items this bulk change will affect. From the displayed list of items that use the manufacturer part specified in step 3, select the items you want to affect, then click Next.
5. In the next wizard dialog, you specify which action to perform. Your options are:

- Replace *<manufacturer part>* on all selected assemblies with *<manufacturer part>*.

That is, on the items you selected in step 4, replace the manufacturer part you selected in step 3 with the manufacturer part you specify here. Enter a manufacturer name and manufacturer part number, or click  to search for the manufacturer part you want.

For additional information about selecting a manufacturer name, see [How to Use Manufacturer Name Automatic Validation](#) (on page 63).

When you are done, click Next.

The redlined items (selected in step 4) will be added to the Affected Items table if they are not already in the Affected Items table. You can view the changes on the Redline Manufacturers tab.

- Remove *<manufacturer part>* from all selected assemblies

That is, remove the manufacturer part you selected in step 3 from the items you selected in step 4.

Click Next.

The redlined items (selected in step 4) will be added to the Affected Items table if they are not already in the Affected Items table. You can view the changes on the Redline Manufacturers tab.

- Just add the selected assemblies to the affected items table.

That is, add the items you selected in step 4 to the Affected Items table (if they are not

already in the Affected Items table), but do not make any redline changes to the items.

Click Finish.

The items (selected in step 4) will be added to the Affected Items table and no redline changes will be made to them. Select an item in the Affected Items table, then make the redline changes you want on the Redline Manufacturers tab.

The items are added to the Affected Items table according to the option you selected in step 5 above.

Web Client Manufacturer Part Bulk Change Wizard

To replace or remove a manufacturer part from multiple items, Web Client:

1. From a change that has not been released, click the Affected Items tab to bring it forward. (You can use an existing change or create a new one.)
2. Click the Bulk Change button and choose Manufacturer Part from the menu.
The Bulk Change wizard appears.
3. In the Identify Manufacturer Part wizard page, you specify the manufacturer part that you want to redline (replace, delete, or otherwise modify) in the items that use it. Enter a manufacturer name and manufacturer part number, or click Search to search for the manufacturer part you want. After you specify a manufacturer part, click Next.
4. In the Identify items to do bulk change operation wizard page, you specify which items this bulk change will affect. From the displayed list of items that use the manufacturer part specified in step 3, select the items you want to affect, then click Next.
5. In the Select Action wizard page, you specify which action to perform. Your options are:

- Just add the selected assemblies to the affected items table.

That is, add the items you selected in step 4 to the Affected Items table (if they are not already in the Affected Items table), but do not make any redline changes to the items.

Click Next.

The items (selected in step 4) will be added to the Affected Items table and no redline changes will be made to them. Select an item in the Affected Items table, then make the redline changes you want on the Redline Manufacturers tab.

- Replace Manufacturer Part Number <manufacturer part> on all selected assemblies with Manufacturer Part Number <manufacturer part>.

That is, on the items you selected in step 4, replace the manufacturer part you selected in step 3 with the manufacturer part you specify here. Enter a manufacturer name and manufacturer part number, or click Search to search for the manufacturer part you want or to create a new manufacturer part.

For more information about selecting a manufacturer name, see [How to Use Manufacturer Name Automatic Validation](#) (on page 63).

When you are done, click Next.

The redlined items (selected in step 4) will be added to the Affected Items table if they are not already in the Affected Items table. You can view the changes on the Redline Manufacturers tab.

- Remove Manufacturer Part Number <manufacturer part> from all selected assemblies

That is, remove the manufacturer part you selected in step 3 from the items you selected in step 4.

Click Finish.

The redlined items (selected in step 4) will be added to the Affected Items table if they are not already in the Affected Items table. You can view the changes on the Redline Manufacturers tab.

The assemblies are added to the Affected Items table according to the option you selected in step 5 above.

Working with the Affected Items Table

Once items have been added to the Affected Items table, there are additional steps required to complete each type of Agile change. The following sections summarize those steps.

- [Special Considerations for ECOs](#) (on page 147)
- [Special Considerations for MCOs](#) (on page 148)
- [Special Considerations for SCOs](#) (on page 149)
- [Special Considerations for ECRs](#) (on page 150)
- [Special Considerations for Deviations](#) (on page 150)
- [Special Considerations for Stop Ships](#) (on page 151)

Special Considerations for ECOs


The basic steps to complete an ECO are:

1. Add the items you want to modify to the Affected Items tab.
See [Adding an Item to the Affected Items Tab](#) (on page 139).

Note	If you add a released item that has pending changes against it, Agile PLM tells you that the item has pending changes.
------	--

2. Edit the Affected Item tab fields, including the required fields, as described in [Fields Required to Release an ECO](#) (on page 148).
See [Editing Rows in the Affected Items Tab](#) (on page 152).
3. If you added a released item that has BOM data or manufacturing data, you can redline the BOM data or manufacturing data and attachments (referenced in file folder objects) on the Redlines pane (Java Client) or page (Web Client).
 - See [Redlining the BOM of a Released Item](#) (on page 104).
 - See [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).
 - For information about redlining attachments, see the *Viewer Supplement*. For more information about attachments, see *Getting Started with Agile PLM*.

Note	If you use the Create Change command to create an ECO from an open item, Agile PLM adds the item to the Affected Items table and, for released items, automatically prompts you to redline any BOM or manufacturer data.
------	--

In Java Client, the Create Change command is available on the item More Actions menu (click the More button  at the top of the object window) and on the right-click shortcut menu. In Web Client, use Actions | Create Change in the item Actions menu.

Fields Required to Release an ECO

Required fields are defined for each status in the workflow. Use the audit feature to determine if all the required fields have been filled in.

In addition to the required fields defined in the workflow, the following Affected Items tab fields must always be completed before Agile PLM releases the ECO:

- New Rev
- Item Number

Note	The Item Number field is completed automatically when you add the item to the Affected Items tab.
------	---



To complete the fields required to release an ECO:

In the New Rev field, type the new revision number.

If you leave the New Rev field blank, Agile PLM places a question mark (?) in the Rev field of the item.

You cannot release an ECO with a blank value in the affected item's Rev field.

Note	Other tabs may also have required fields that must be completed. The specific fields on your system may vary, depending on the workflow settings.
------	---

In Java Client, use the Audit Release button  on the object window toolbar to verify that all required fields have been completed. Use the Audit Status button  to verify that status required fields have been completed.

In Web Client, use the Audit Release command on the Actions menu to verify that all required fields have been completed. Use the Audit Status command on the Actions menu to verify that status required fields have been completed.

You cannot change the New Rev field on the Affected Items tab on a released change, even if you have the appropriate privileges to modify released changes. If you do not have the appropriate privilege to modify the Lifecycle Phase on the Affected Items tab of a released change, you can use an MCO to modify the lifecycle phase of an item without changing its revision level. See [Redlining through MCOs](#) (on page 128) or more information.

Special Considerations for MCOs

The basic steps to complete an MCO are:


1. Add the items you want to modify to the Affected Items tab.
See [Adding an Item to the Affected Items Tab](#) (on page 139).
2. Edit the Affected Item tab fields, including the required fields. MCOs allow you to select a new Lifecycle Phase.

See [Editing Rows in the Affected Items Tab](#) (on page 152).

3. If you added a released item that has manufacturing data, redline the manufacturers data.


See [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).

Note If you use the Create Change command to create an MCO from an open item, Agile PLM adds the item to the Affected Items table and, for released items, automatically prompts you to redline any manufacturer data.

In Java Client, the Create Change command is available on the item More Actions menu (click the More button  at the top of the object window) and on the right-click shortcut menu. In Web Client, use Fields Required to Release an MCO

In addition to the required fields defined in the workflow, the Item Number field on the Affected Items tab must be completed before Agile PLM releases the MCO. This field is completed automatically when you add items to the Affected Items tab.

Note Other tabs also have required fields that must be completed. The specific fields on your system may vary, depending on the workflow settings.

In Java Client, use the Audit Release button  on the object window toolbar to verify that all required fields have been completed.

In Web Client, use the Audit Release command on the Actions menu to verify that all required fields have been completed.

Special Considerations for SCOs

The basic steps to complete an SCO are:

1. Add the items you want to modify to the Affected Items tab.

See [Adding an Item to the Affected Items Tab](#) (on page 139).

Note If you add a released item that has pending changes against it, Agile PLM tells you that the item has pending changes.

2. Edit the Affected Item tab fields, including the required fields. You can modify the site-specific dispositions and the effective and obsolete dates of site-specific items for both the latest and non-latest revisions.



See [Site Change Orders](#) (on page 124).

3. If you added the most recently released revision of an item to the SCO, you can redline site-specific BOM and AML data, but only against the latest released revision.

- See [Redlining through ECOs, MCOs, and SCOs](#) (on page 127).
- See [Redlining the BOM of a Released Item](#) (on page 104).
- See [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).

Note Only the most recently released revision of an item can be redlined with an SCO.

Other tabs also have required fields that must be completed. The specific fields on your system may vary, depending on the workflow settings.

In Java Client, use the Audit Release button  on the object window toolbar to verify that all required fields have been completed. Use the Audit Status button  to verify that status required fields have been completed.

In Web Client, use the Audit Release command on the Actions menu to verify that all required fields have been completed. Use the Audit Status command on the Actions menu to verify that status required fields have been completed.

Special Considerations for ECRs

The basic steps to complete an ECR are:

1. Add the items to the Affected Items tab.

See [Adding an Item to the Affected Items Tab](#) (on page 139).

When adding by Type in Known Numbers, you can enter the revision, preceded by a space character, when you type the number. For example:


1000-02 A
P003872 D

Note	If you add a released item that has pending changes against it, Agile PLM tells you that the item has pending changes.
------	--

2. Edit the Affected Item tab Revision field and any custom fields that may be defined for your Agile system.

See [Editing Rows in the Affected Items Tab](#) (on page 152).

Note	Other tabs also have required fields that must be completed. The specific fields on your system may vary, depending on the workflow settings.
------	---

In Java Client, use the Audit Release button  on the object window toolbar to verify that all required fields have been completed.

In Web Client, use the Audit Release command on the Actions menu to verify that all required fields have been completed.

Special Considerations for Deviations

The basic steps to complete a Deviation are:

1. Add the items to the Affected Items tab.

See [Adding an Item to the Affected Items Tab](#) (on page 139).

When adding by Type in Known Numbers, you can enter the revision, preceded by a space character, when you type the number. For example:

1000-02 A
P003872 D


Note	If you add a released item that has pending changes against it, Agile PLM tells you that the item has pending changes.
------	--

2. Edit the Affected Item tab Revision field and any custom fields that may be defined for your Agile

system.

See [Editing Rows in the Affected Items Tab](#) (on page 152).

Note Other tabs also have required fields that must be completed. The specific fields on your system may vary, depending on the workflow settings.

In Java Client, use the Audit Release button  on the object window toolbar to verify that all required fields have been completed.

In Web Client, use the Audit Release command on the Actions menu to verify that all required fields have been completed.

Special Considerations for Stop Ships

The basic steps to complete a Stop Ship are:

1. Add the items to the Affected Items tab.

See [Adding an Item to the Affected Items Tab](#) (on page 139).

When adding by Type in Knows Numbers, you can enter the revision, preceded by a space character, when you type the number. For example:


1000-02 A
P003872 D

Note If you add a released item that has pending changes against it, Agile PLM tells you that the item has pending changes.

2. Edit the Affected Item tab Revision field and any custom fields that may be defined for your Agile system.

See [Editing Rows in the Affected Items Tab](#) (on page 152).

Note Other tabs also have required fields that must be completed. The specific fields on your system may vary, depending on the workflow settings.

In Java Client, use the Audit Release button  on the object window toolbar to verify that all required fields have been completed.

In Web Client, use the Audit Release command on the Actions menu to verify that all required fields have been completed.


Removing an Item from the Affected Items Tab


When you delete an item from the Affected Items tab, any attachments added to the item under the pending revision defined in that change are lost. This is true for all pending revisions, including items that have never been released and have only one change against them. If there is only one change pending against the item, and you delete the item from that change, the item reverts to a preliminary item with no changes against it, and any attachments added under that last change are lost.

When you remove an item from the Affected Items tab, any item redlines made through that change are dropped and discarded. Any attachments added to the pending revision created by that change are removed from the item. Agile PLM displays warnings before dropping redlines or removing


attachments; accept the warnings to complete the item removal.


To remove an item from the Affected Items tab in Java Client:

1. If necessary, select Show Sites in the View drop-down list to expand the table to show an item row for each site assigned to the item.
2. Click to select the row for the item that you want to delete. (You can select multiple items.)
3. Click the Remove button .

Note Be sure to use the Remove button on the Affected Items tab to remove items from that tab. If you use the Delete  button on the object window toolbar (Java Client) or the Delete command on the object Actions menu (Web Client), Agile PLM deletes the entire change.

To remove an item from the Affected Items tab in Web Client:

1. If necessary, select Show Sites in the View drop-down list to expand the table to show a row for each site assigned to the item.
2. Check the box for the item that you want to delete. (You can check multiple items.)
3. Click the  Remove button.

Note Be sure to use the Remove button on the Affected Items tab to remove items from that tab. If you use the Delete  button on the object window toolbar (Java Client) or the Delete command on the object Actions menu (Web Client), Agile PLM deletes the entire change.

Editing Rows in the Affected Items Tab

You can edit rows on the Affected Items table, including rows associated with a specific site. You can also copy and paste information between these rows.


Note You cannot edit the item description from MCOs, ECRs, deviations, or stop ships. The item description is inherited from the latest released ECO.

This section includes the topics:

- [Editing Affected Items Tab Rows in Java Client](#) (on page 152)
- [Editing Affected Items Tab Rows in Web Client](#) (on page 154)

Editing Affected Items Tab Rows in Java Client



To edit affected item information in Java Client:



1. If necessary, select Show Sites in the View drop-down list to expand the table to show a row for each site assigned to the item.
2. Click to select the rows you want to edit. You can use Ctrl-click and Shift-click to select multiple rows.
3. Click the Edit button .

The Edit Affected Items dialog box appears.

4. Make the modifications you want.
5. When you are finished, click OK.


Fill Up Rows and Fill Down Rows Buttons in Java Client

By selecting a group of fields in one column, you can use the Fill Up Rows button  to copy the contents of the bottom-most selected field into all the selected fields above it. You can use the Fill Down Rows button  to copy the contents of the top-most selected field into all the selected fields below it. You can use Ctrl-click to select non-contiguous fields, and you can use Shift-click to select contiguous fields.

You can fill up and fill down in multiple columns at one time. Once you have selected fields in one column, you can select multiple additional columns using Ctrl-click (non-contiguous columns) and Shift-click (contiguous columns). The Fill Up Rows button  copies the contents of the bottom-most selected field in each column into all the selected fields in each column. The Fill Down Rows button  copies the contents of the topmost selected fields in each column into all the selected fields in each column.

Note Fill Up and Fill Down are available in edit mode for any editable table. Attributes that require unique identifier data or other unique data do not have Fill Up and Fill Down capability, for example: Item Number on the Affected Items tab, Manufacturer Name and Manufacturer Part Number on the item Manufacturers tab, or Item Number and Find Number on the item BOM tab.

To copy information between rows in Java Client:



1. If necessary, select Show Sites in the View drop-down list to expand the table to show a row for each site assigned to the item.
2. Click to select the rows you want to edit. You can use Ctrl-click and Shift-click to select multiple rows.
3. Click the Edit button .

The Edit Affected Items dialog box appears.

4. Click to select the fields you want to fill in. Use Shift-click and Ctrl-click to select the fields in each column and to select additional columns you want to fill in. The fill up and fill down action is defined by the selected (highlighted) fields in each column in the Affected Items table.

Both the source row and the target rows must be highlighted. The top-most row or the bottom-most row is the source row.

You may want to edit the top-most or bottom-most row in the Affected Items table, then use the Fill Up Rows and Fill Down Rows buttons to complete the remaining rows in the table.

5. Click the Fill Up Rows  or Fill Down Rows  button to fill in the selected Affected Items table fields.
6. When you are finished, click OK.

Editing Affected Items Tab Rows in Web Client



To edit affected item information in Web Client:



1. If necessary, select Show Sites in the View drop-down list to expand the table to show a row for each site assigned to the item.
2. Select the row of item that you want to edit. (You can select multiple items and multiple site rows for each item.)
3. Click Edit. Text boxes, drop-down lists, and calendar buttons appear in the editable columns.
4. Make any changes, then click Save to save the changes, or click Cancel to cancel the changes.



Fill Up Rows and Fill Down Rows Buttons in Web Client

To copy information between rows in Web Client:

1. If necessary, select Show Sites in the View drop-down list to expand the table to show a row for each site assigned to the item.
2. Select the rows of items that you want to edit. (You can select multiple items and multiple site rows for each item.)
3. Click Edit. Text boxes, drop-down lists, and calendar buttons appear in the editable columns.

A set of Fill Down and Fill Up buttons   appear next to each field that can be copied between rows.

4. Select (highlight) the target rows, the rows to which you want to copy cell values.
5. Click the Fill Down  button to copy the contents of that cell to all the cells in the highlighted rows in the column below the current cell.
6. Click the Fill Up  button to copy the contents of that cell to all the cells in the highlighted rows in the column above the current cell.

Note If you click Fill Down  or Fill Up  next to an empty cell, the cells in the column below (fill down) or above (fill up) the current cell are cleared; the empty cell is copied down or up the column.

7. When you are finished editing the affected items, click the Save button.


Copy and Paste Buttons in Web Client



To copy information between rows in Web Client:




1. If necessary, select Show Sites in the View drop-down list to expand the table to show a row for each site assigned to the item.
2. Select the rows of items that you want to edit. (You can select multiple items and multiple site rows for each item.)
3. Click Edit. Text boxes, drop-down lists, and calendar buttons appear in the editable columns.

The column headers now have checkboxes so that you can specify which information to copy

and paste.

4. Click the row from which you want to copy information. The row changes color to indicate that it is selected. (To deselect a row, just click it again.)
5. Click the  Copy button. The row you selected is now outlined with a dashed line. This indicates that this is the row from which you are going to copy information.

You can now use the  Copy button menu selections. The  Copy button menu has the following menu commands:



- Select All Columns
 - Deselect All Columns
 - Cancel Copy
6. Click the row into which you want to paste the information. You can select multiple rows using the Shift or Ctrl key and the arrow keys.
 7. Select the checkboxes of the columns into which you want to paste data. To select or deselect all columns, click the  Copy button and choose Select All Columns or Deselect All Columns.
 8. To paste the information, click the  Paste button.
 9. To paste information from a different row, click the  Copy button and choose Cancel Copy. This clears the copy/paste Clipboard.

To cancel a copy operation, before pasting, click the  Copy button and choose Cancel Copy.

10. When you are finished editing the affected items, click the Save button.

Viewing the Redlines of an Affected Item

In Java Client, if an affected item has a BOM, an AML, or attachments, you can view its Redlines tabs by clicking in its row in the Affected Items table. The Redline tabs for the selected item appear in the bottom portion of the Affected Items tab.

In Web Client, if an affected item has a BOM, an AML, or attachments, you can view its Redlines page by clicking the  or  button in its row in the Affected Items table.

- For information about the Redline BOM tab, see [Redlining the BOM of a Released Item](#) (on page 104).
- For information about the Redline Manufacturers tab, see [Modifying Manufacturing Data from the Redlines Tab](#) (on page 72).
- For information about the Redline Folders tab, see *Getting Started with Agile PLM*.

Working with Product Reports and Process Reports

This chapter includes the following:

▪ About Agile Reports.....	157
▪ About Product Reports and Process Reports.....	158
▪ Agile Products Reports.....	159
▪ Agile Process Reports.....	173

About Agile Reports

Reports allow you to display the values of your product records. By accessing this information and summarizing it in a meaningful way, reports provide insight into your business processes and can help guide better-informed decisions. Agile PLM provides a robust reporting platform that allows you to:

- Measure and monitor business performance using standard out-of-the-box reports. These standard reports capture the best practices in product lifecycle management business processes.
- Configure reports with Agile's custom reporting to obtain the specific information you need.
- Use a single point of access to all relevant reports—even those developed outside of the Agile PLM application—through Agile's external reporting capability.

For detailed information about using all types of Agile reports, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*, which includes information about:

- How your roles and privileges affect reports
- Report object tabs
- Creating and modifying report layouts
- Creating custom and external reports
- Running, scheduling, saving, and deleting reports
- Report output window

This chapter covers the Agile standard reports that are included as part of Agile Product Collaboration: product reports and process reports.

Oracle BI Publisher Report Options

If the Agile administrator has enabled the use of the Oracle BI Publisher report capabilities in Agile PLM, when you execute many standard reports, you will have the option to choose to use BI

Publisher to generate your report. This allows you to choose from several different report output formats. The BOM Explosion Report and the Manufacturer BOM Report also offer the option to use BI Publisher templates that the Agile administrator has configured.

Detailed instructions are included in each report topic.

For more information about Agile PLM and BI Publisher, see *Agile PLM Administrator Guide*.

For more information about Oracle BI Publisher see, <http://xdo.us.oracle.com/?tab=Home>.

About Product Reports and Process Reports

Standard reports provide you with the information you commonly need to analyze your business processes. Product reports and process reports are the standard out-of-the-box reports for Product Collaboration. You select predefined criteria and specify the results you want. You can run them as they are, modify the default layouts, or create your own layouts. You can run Agile product reports and process reports from Agile Web Client or Java Client.

Accessing Product Reports and Process Reports

To access product reports in Java Client:

1. Click the Analytics and Reports tab in the left pane to display the reports folders.
2. Open the Standard Reports folder to locate the Product Reports folder or the Process Reports folder.
3. Open the Product Reports folder or the Process Reports folder and double-click the report you want. Web Client opens and displays the report page you selected.

To access product reports in Web Client:

1. Click the Analytics and Reports icon in the left pane to display the reports folders.
2. Open the Standard Reports folder to locate the Product Reports folder or the Process Reports folder.
3. Open the Product Reports folder or the Process Reports folder and click the report you want. The report page is displayed in the right pane.

Products Reports

The Products Reports folder lists the following reports:

- [Assembly Cost \(Item Master\) Report](#) (on page 160)
- [BOM Comparison Report](#) (on page 161)
- [BOM Explosion Report](#) (on page 163)
- [Consolidated BOM Report](#) (on page 165)
- [Effective BOM Explosion Report](#) (on page 166)
- [Item Activity Report](#) (on page 168)
- [Item Manufacturers Report](#) (on page 169)
- [Manufacturer BOM Report](#) (on page 170)

- [Where Used Report](#) (on page 172)

For more information about specific product reports, see [Agile Products Reports](#) (on page 159).

Process Reports

The Process Reports folder lists the following reports:

- [Change Activity Report](#) (on page 174)
- [Change Backlog Report](#) (on page 175)
- [Change Cycle Time Report](#) (on page 177)
- [Change Metrics Report](#) (on page 178)
- [Change Package Report](#) (on page 179)
- [IP Transfer Report](#) (on page 181)

For more information about specific product reports, see [Agile Process Reports](#) (on page 173).

Agile Products Reports

The Products Reports folder under Standard Reports in the navigation pane lists the Product Collaboration reports.

Report	Displays...
Bill of Materials (BOM) reports	
Assembly Cost (Item Master) Report (on page 160)	The Assembly Cost report takes the bill of material for a specified assembly and computes the cost of the BOM and each subassembly.
BOM Comparison Report (on page 161)	The BOM Comparison report shows the differences between two or more bills of material.
BOM Explosion Report (on page 163)	The BOM Explosion report displays the bill of material for a specified assembly up to the desired number of levels.
Consolidated BOM Report (on page 165)	The Consolidated BOM report takes the bill of material for a specified assembly and consolidates it into a single-level bill, computing the total quantity of each item.
Effective BOM Explosion Report (on page 166)	The Effective BOM report displays the bill of material for a specified assembly that is effective during a specific time period.
Item Activity Report (on page 168)	The Item Activity report shows the items that were processed during a specified period of time.
Where Used Report (on page 172)	The Where Used report shows where the component or subassembly is used, up to any practical number of levels.
Manufacturer reports	
Item Manufacturers Report (on page 169)	The Manufacturer Item report displays a list of all the items matching a query and shows the manufacturers that are used for each item. (Requires AML server license.)


Report	Displays...
Manufacturer BOM Report (on page 170)	The Manufacturer BOM report runs the BOM Explosion report and includes the manufacturers that are used for each item in the bill of material. (Requires AML server license.)

Assembly Cost (Item Master) Report

This report generates a cost rollup by determining the cost and quantity of each component and assembly and calculating the total cost. The report shows the same data as the BOM Explosion report with the addition of three columns:

- Individual Cost
- Total Cost
- Assembly Cost

To run the Assembly Cost report:


1. Select the Assembly Cost report in the Products Reports folder. The Assembly Cost Report page appears.
2. Click the  Execute button. The Select Layout and Configuration page appears.

Note	If the Agile administrator has enabled the use of Oracle Business Intelligence Publisher (report publisher), you see a checkbox labeled Use BI Publisher.
------	---

3. To select a layout when *not* using BI Publisher (the Use BI Publisher checkbox is not visible or the Use BI Publisher checkbox is unchecked):
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Click Next.
4. To use BI Publisher, check the Use BI Publisher checkbox and continue as follows:
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Select a report output format: PDF, WORD, EXCEL, or HTML.
 - c. Click the Save the Report checkbox to automatically save a copy of the report in the selected format on the Historical Reports tab.
 - d. Click Next.
5. Select the items you want to include in the report. Click Add to open the Add Items wizard. You can then select Search or Advanced Search to find items, or locate them using saved searches or shortcuts (My Bookmarks list or Recently Visited list). Select the items you want in the Search Results window; the selected items appear in the Selected Items list. Click OK to close the wizard.
6. By default, the most recently released revision of the item is selected in the Select Items for Report page of the report wizard. To select a different revision, use the drop-down list in the Revision column of the table.

7. To select multiple revisions of an item or to select site-specific revisions of an item, use the following procedure:
 - a. Select one item in the table, then click the Select Multiple Revisions button. You can expand only one item at a time.

Note	An unexpanded item has a drop-down list in the revision column.
-------------	---

 - b. In the displayed dialog, select the sites for which you want to expand the item revisions. To expand the revisions of the common BOM, select All Sites. Click OK.
If your company does not have the Sites server license, this step is omitted.
 - c. When Select Multiple Revisions is complete, all revisions of the item for each selected site are displayed on separate rows of the table. For example, you might see both Revision B for the India site and Revision B for the Hong Kong site.
If your company does not have the Sites server license, all revisions of the item are displayed, each revision on a separate row of the table.
 - d. If you do not want to include every revision displayed in the Select Items for Report table, select the rows you do not want to use, then click Remove.
 - e. Repeat step a through step d for each item for which you want to expand the revisions.
8. Specify the item types by clicking the  button and selecting from the list.
9. Select values from the Cost Field and Option drop-down lists. The options are Part Cost Only, Assembly Level Cost only, or Assembly Level Cost Plus Rolled-Up Cost.
10. Click Finish to run and display the report.

If you checked the Use BI Publisher checkbox, you are prompted to download the report in the format you selected.

Report layout fields	Description
Level	The BOM level, for example, 0, 1, 2, or 3.
Individual Cost	The part cost selected in the Cost Field in the report wizard.
Total Cost	Individual Cost * total quantity (Qty) for that row
Assembly Cost	Cost of the assembly.
Item fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the selected item's Title Block , Page Two or BOM tabs. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting Started with Agile PLM</i> .

BOM Comparison Report


The BOM (Bills of Material) Comparison report shows the differences between two or more bills of material. It compares the first-level BOM of the selected items to the BOMs of the other items on the report and shows you which components are not common to both.

Only those items that have differences are listed in the report. Components that match exactly are

not listed. An item may be listed multiple times to indicate the differences in find number and reference designator information.

You can compare the BOMs by item number or by find number. The comparison will be sorted by item number and by find number.

To run the BOM Comparison report:

1. Select the BOM Comparison report in the Products Reports folder. The BOM Comparison Report page appears.
2. Click the  Execute button. The Select Layout and Configuration page appears.

Note	If the Agile administrator has enabled the use of Oracle Business Intelligence Publisher (report publisher), you see a checkbox labeled Use BI Publisher.
------	---


3. To select a layout when *not* using BI Publisher (the Use BI Publisher checkbox is not visible or the Use BI Publisher checkbox is unchecked):
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Click Next.
4. To use BI Publisher, check the Use BI Publisher checkbox and continue as follows:
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Select a report output format: PDF, WORD, EXCEL, or HTML.
 - c. Click the Save the Report checkbox to automatically save a copy of the report in the selected format on the Historical Reports tab.
 - d. Click Next.
5. Select the items you want to include in the report. Click Add to open the Add Items wizard. You can then select Search or Advanced Search to find items, or locate them using saved searches or shortcuts (My Bookmarks list or Recently Visited list). Select the items you want in the Search Results window; the selected items appear in the Selected Items list. Click OK to close the wizard.
6. By default, the most recently released revision of the item is selected in the Select Items for Report page of the report wizard. To select a different revision, use the drop-down list in the Revision column of the table.
7. To select multiple revisions of an item or to select site-specific revisions of an item, use the following procedure:
 - a. Select one item in the table, then click the Select Multiple Revisions button. You can expand only one item at a time.

Note	An unexpanded item has a drop-down list in the revision column.
------	---

- b. In the displayed dialog, select the sites for which you want to expand the item revisions. To expand the revisions of the common BOM, select All Sites. Click OK.

If your company does not have the Sites server license, this step is omitted.
- c. When Select Multiple Revisions is complete, all revisions of the item for each selected site are displayed on separate rows of the table. For example, you might see both Revision B for the India site and Revision B for the Hong Kong site.

If your company does not have the Sites server license, all revisions of the item are displayed, each revision on a separate row of the table.

- d. If you do not want to include every revision displayed in the Select Items for Report table, select the rows you do not want to use, then click Remove.
 - e. Repeat step a through step d for each item for which you want to expand the revisions.
8. Specify the item types you want to include in the report.
- By default, all the item types are selected; if you want to include all item types in your report, you do not need to modify this list. If you want to specify which item types to include, click the  button. Move the item types you do not want to include from the Selected Values list to the Available Values list. When you are finished, click OK.
9. Select the attribute used to match items being compared: Item Number or Find Number.
10. Click Finish to run and display the report.


If you checked the Use BI Publisher checkbox, you are prompted to download the report in the format you selected.

Report layout fields	Description
Comparison Data	The report includes one column for each item revision selected in the Select Items for Report wizard page.
Item fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the selected item's Title Block , Page Two or BOM tabs. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .

BOM Explosion Report

The BOM Explosion report displays the items that are in the bill of material for a specified assembly, up to the desired number of levels.

To run the BOM Explosion report:

1. Select the BOM Explosion report in the Products Reports folder. The BOM Comparison Report page appears.
2. Click the  Execute button. The Select Layout and Configuration page appears.


Note If the Agile administrator has enabled the use of Oracle Business Intelligence Publisher (report publisher), you see a checkbox labeled Use BI Publisher.

3. To select a layout when *not* using BI Publisher (the Use BI Publisher checkbox is not visible or the Use BI Publisher checkbox is unchecked):
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Click Next.
4. To use BI Publisher, check the Use BI Publisher checkbox:

5. To use a standard report layout with BI Publisher:
 - a. Select the layout you want from the Layout drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Select a report output format: PDF, WORD, EXCEL, or HTML.
6. To use a BI Publisher template with BI Publisher:
 - a. Check the Use Template for Layout checkbox.
 - b. Select the template you want from the Template drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - c. Select a report output format: PDF, WORD, EXCEL, HTML, or XML.
7. Select the items you want to include in the report. Click Add to open the Add Items wizard. You can then select Search or Advanced Search to find items, or locate them using saved searches or shortcuts (My Bookmarks list or Recently Visited list). Select the items you want in the Search Results window; the selected items appear in the Selected Items list. Click OK to close the wizard.
8. By default, the most recently released revision of the item is selected in the Select Items for Report page of the report wizard. To select a different revision, use the drop-down list in the Revision column of the table.
9. To select multiple revisions of an item or to select site-specific revisions of an item, use the following procedure:
 - a. Select one item in the table, then click the Select Multiple Revisions button. You can expand only one item at a time.

Note An unexpanded item has a drop-down list in the revision column.
 - b. In the displayed dialog, select the sites for which you want to expand the item revisions. To expand the revisions of the common BOM, select All Sites. Click OK.

If your company does not have the Sites server license, this step is omitted.
 - c. When Select Multiple Revisions is complete, all revisions of the item for each selected site are displayed on separate rows of the table. For example, you might see both Revision B for the India site and Revision B for the Hong Kong site.

If your company does not have the Sites server license, all revisions of the item are displayed, each revision on a separate row of the table.
 - d. If you do not want to include every revision displayed in the Select Items for Report table, select the rows you do not want to use, then click Remove.
 - e. Repeat step a through step d for each item for which you want to expand the revisions.
10. Specify the depth, or number of levels in the BOM, you want to include. Specify the item types by clicking the  button and selecting from the list.
11. Click Finish to run and display the report.

If you checked the Use BI Publisher checkbox, you are prompted to download the report in the format you selected.


Report layout fields	Description
Level	The BOM level, for example, 0, 1, 2, or 3.

Report layout fields	Description
Item fields as specified in the selected layout	<p>Depending on the layout, the report can include any attributes from the selected item's Title Block, Page Two or BOM tabs.</p> <p>For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i>.</p>

Consolidated BOM Report

The Consolidated BOM report takes the bill of material for a specified assembly and consolidates it into a single-level bill, computing the total quantity of each item. It shows a summary of all parts for a given assembly, regardless of level, including total quantities in the whole assembly.

To run the Consolidated BOM report:

1. Select the Consolidated BOM report in the Products Reports folder. The Consolidated BOM Report page appears.
2. Click the  Execute button. The Select Layout and Configuration page appears.

Note If the Agile administrator has enabled the use of Oracle Business Intelligence Publisher (report publisher), you see a checkbox labeled Use BI Publisher.
3. To select a layout when *not* using BI Publisher (the Use BI Publisher checkbox is not visible or the Use BI Publisher checkbox is unchecked):
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Click Next.
4. To use BI Publisher, check the Use BI Publisher checkbox and continue as follows:
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Select a report output format: PDF, WORD, EXCEL, or HTML.
 - c. Click the Save the Report checkbox to automatically save a copy of the report in the selected format on the Historical Reports tab.
 - d. Click Next.
5. Select the items you want to include in the report. Click Add to open the Add Items wizard. You can then select Search or Advanced Search to find items, or locate them using saved searches or shortcuts (My Bookmarks list or Recently Visited list). Select the items you want in the Search Results window; the selected items appear in the Selected Items list. Click OK to close the wizard.
6. By default, the most recently released revision of the item is selected in the Select Items for Report page of the report wizard. To select a different revision, use the drop-down list in the Revision column of the table.
7. To select multiple revisions of an item or to select site-specific revisions of an item, use the

following procedure:

- a. Select one item in the table, then click the Select Multiple Revisions button. You can expand only one item at a time.

Note	An unexpanded item has a drop-down list in the revision column.
------	---

- b. In the displayed dialog, select the sites for which you want to expand the item revisions. To expand the revisions of the common BOM, click OK.

If your company does not have the Sites server license, this step is omitted.


- c. When Select Multiple Revisions is complete, all revisions of the item for each selected site are displayed on separate rows of the table. For example, you might see both Revision B for the India site and Revision B for the Hong Kong site.

If your company does not have the Sites server license, all revisions of the item are displayed, each revision on a separate row of the table.

- d. If you do not want to include every revision displayed in the Select Items for Report table, select the rows you do not want to use, then click Remove.
- e. Repeat step a through step d for each item for which you want to expand the revisions.

8. Specify the depth, or number of levels in the BOM, you want to include.

Specify the item types you want to include in the report. By default, all the item types are selected; if you want to include all item types in your report, you do not need to modify this list.

If you want to specify which item types to include, click the  button. Move the item types you do not want to include from the Selected Values list to the Available Values list. When you are finished, click OK.

9. Click Finish to run and display the report.


If you checked the Use BI Publisher checkbox, you are prompted to download the report in the format you selected.

Report layout fields	Description
Total Quantity	Total quantity of each specific item in the whole assembly (BOM)
Item fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the seitem's Title Block , Page Two or BOM tabs. For detailed information about layouts, see the <i>Working with Agile Reports</i> chapter in <i>Getting started With Agile PLM</i> .


Effective BOM Explosion Report

The Effective BOM Explosion report displays the report based on the Rev Release Date of parts in the BOM.

To run the Effective BOM Explosion report:

1. Select the Effective BOM Comparison Report in the Products Reports folder. The Effective BOM Comparison Report page appears.
2. Click the  Execute button. The Select Layout and Configuration page appears.

Note If the Agile administrator has enabled the use of Oracle Business Intelligence Publisher (report publisher), you see a checkbox labeled Use BI Publisher.


3. To select a layout when *not* using BI Publisher (the Use BI Publisher checkbox is not visible or the Use BI Publisher checkbox is unchecked):
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Click Next.
4. To use BI Publisher, check the Use BI Publisher checkbox and continue as follows:
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Select a report output format: PDF, WORD, EXCEL, or HTML.
 - c. Click the Save the Report checkbox to automatically save a copy of the report in the selected format on the Historical Reports tab.
 - d. Click Next.
5. Select the items you want to include in the report. Click Add to open the Add Items wizard. You can then select Search or Advanced Search to find items, or locate them using saved searches or shortcuts (My Bookmarks list or Recently Visited list). Select the items you want in the Search Results window; the selected items appear in the Selected Items list. Click OK to close the wizard.
6. For each row, you can select a site, or all sites, from the drop-down list. Click Next. The Select Depth and Type page is displayed.
7. Specify the depth, or number of levels in the BOM, you want to include.
 Specify the item types you want to include in the report. By default, all the item types are selected; if you want to include all item types in your report, you do not need to modify this list.
 If you want to specify which item types to include, click the  button. Move the item types you do not want to include from the Selected Values list to the Available Values list. When you are finished, click OK.
 Select the sort type: Maintain BOM Structure or Sort By Item Type. Click Next.
8. On the Select Date Range page, select a start date and an end date.
 The report will display all the BOM components that were released on or after the start date and on or before the end date.
9. Click Finish to run and display the report.
 If you checked the Use BI Publisher checkbox, you are prompted to download the report in the format you selected.



Default fields	Description
Level	The BOM level, for example, 0, 1, 2, or 3
Item fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the selected item's Title Block , Page Two , Changes , or BOM tabs. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .

Item Activity Report

The Item Activity report shows the items that were processed during a specified period of time.

To run the Item Activity report:

1. Select the Item Activity report in the Products Reports folder. The Item Activity Report page appears.
2. Click the  Execute button. The Select Layout and Configuration page appears.

Note	If the Agile administrator has enabled the use of Oracle Business Intelligence Publisher (report publisher), you see a checkbox labeled Use BI Publisher.
------	---
3. To select a layout when *not* using BI Publisher (the Use BI Publisher checkbox is not visible or the Use BI Publisher checkbox is unchecked):
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Click Next.
4. To use BI Publisher, check the Use BI Publisher checkbox and continue as follows:
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Select a report output format: PDF, WORD, EXCEL, or HTML.
 - c. Click the Save the Report checkbox to automatically save a copy of the report in the selected format on the Historical Reports tab.
 - d. Click Next.
5. Specify the start and end dates of the period to be covered by the report. Click Next.
6. Click  button next to the Item Lifecycle Phase field and select the lifecycles to be included. Click the  next to the Sites field and select the sites you want.
7. Click Finish to run and display the report.



If you checked the Use BI Publisher checkbox, you are prompted to download the report in the format you selected.

Report layout fields	Description
Site	The name of the site associated with the listed item. The sites listed are determined by the sites you selected in the report wizard.
Item fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed item's Title Block or Page Two tabs. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .

Item Manufacturers Report

The Item Manufacturers report displays a list of all the items matching a query and shows the manufacturers that are used for each item.

To run the Item Manufacturers report:

1. Select the Item Manufacturer report in the Products Reports folder. The Item Manufacturer Report page appears.
 2. Click the  Execute button. The Select Layout and Configuration page appears.
- Note** If the Agile administrator has enabled the use of Oracle Business Intelligence Publisher (report publisher), you see a checkbox labeled Use BI Publisher.
3. To select a layout when *not* using BI Publisher (the Use BI Publisher checkbox is not visible or the Use BI Publisher checkbox is unchecked):
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Click Next.
 4. To use BI Publisher, check the Use BI Publisher checkbox and continue as follows:
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Select a report output format: PDF, WORD, EXCEL, or HTML.
 - c. Click the Save the Report checkbox to automatically save a copy of the report in the selected format on the Historical Reports tab.
 - d. Click Next.
 5. Click the Save the Report checkbox to automatically save a copy of the report in the selected format on the Historical Reports tab.
 6. Click Next.
 7. Click Saved Search if you want to use a search from the list of global or personal searches. Click Advanced Search to create a new query.
 8. Click the  buttons next to the Preferred Status, Manufacturer Part Lifecycle Status, and Sites (optional) fields to select values from the lists.
 9. Click Finish to run and display the report.

If you checked the Use BI Publisher checkbox, you are prompted to download the report in the format you selected.


Report layout fields	Description
Item attributes	
For each item listed in the report, item fields as specified in the selected layout	<p>Depending on the layout, the report can include any attributes from the listed item's Title Block or Page Two tabs.</p> <p>For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i>.</p>

Report layout fields	Description
Manufacturer part attributes	
Under each listed item, manufacturer part information as specified in the selected lay	<p>Depending on the layout, the manufacturer part information under each item can include any attributes from the listed item's Manufacturers tab, attributes from the manufacturer part's General Info tab, and attributes from the manufacturer's General Info tab.</p> <p>For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i>.</p>

Manufacturer BOM Report

The Manufacturer BOM report runs the BOM Explosion report and shows the manufacturers that are used for each item in the bill of material. Manufacturer data can be filtered by the lifecycle status of the manufacturer or of the manufacturer part.



To run the Manufacturer BOM report:

1. Select the Manufacturer BOM report in the Products Reports folder. The Manufacturer BOM Report page is displayed.
2. Click the  Execute button. The Select Layout and Configuration page appears.

Note If the Agile administrator has enabled the use of Oracle Business Intelligence Publisher (report publisher), you see a checkbox labeled Use BI Publisher.
3. To select a layout when *not* using BI Publisher (the Use BI Publisher checkbox is not visible or the Use BI Publisher checkbox is unchecked):
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Click Next.
4. To use BI Publisher, check the Use BI Publisher checkbox:
5. To use a standard report layout with BI Publisher:
 - a. Select the layout you want from the Layout drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Select a report output format: PDF, WORD, EXCEL, or HTML.
6. To use a BI Publisher template with BI Publisher:
 - a. Check the Use Template for Layout checkbox.
 - b. Select the template you want from the Template drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - c. Select a report output format: PDF, WORD, EXCEL, HTML, or XML.
7. Click the Save the Report checkbox to automatically save a copy of the report in the selected format on the Historical Reports tab.

8. Click Next.
9. Select the items you want to include in the report. Click Add to open the Add Items wizard. You can then select Search or Advanced Search to find items, or locate them using saved searches or shortcuts (My Bookmarks list or Recently Visited list). Select the items you want in the Search Results window; the selected items appear in the Selected Items list. Click OK to close the wizard.
10. By default, the most recently released revision of the item is selected in the Select Items for Report page of the report wizard. To select a different revision, use the drop-down list in the Revision column of the table.
11. To select multiple revisions of an item or to select site-specific revisions of an item, use the following procedure:
 - a. Select one item in the table, then click the Select Multiple Revisions button. You can expand only one item at a time.

Note An unexpanded item has a drop-down list in the revision column.

 - b. In the displayed dialog, select the sites for which you want to expand the item revisions. To expand the revisions of the common BOM, select All Sites. Click OK.
If your company does not have the Sites server license, this step is omitted.
 - c. When Select Multiple Revisions is complete, all revisions of the item for each selected site are displayed on separate rows of the table. For example, you might see both Revision B for the India site and Revision B for the Hong Kong site.
If your company does not have the Sites server license, all revisions of the item are displayed, each revision on a separate row of the table.
 - d. If you do not want to include every revision displayed in the Select Items for Report table, select the rows you do not want to use, then click Remove.
 - e. Repeat step a through step d for each item for which you want to expand the revisions.
12. Specify the depth, or number of levels in the BOM, you want to include. Specify the item types by clicking the  button and selecting from the list.
13. Click the  buttons next to the Preferred Status, Manufacturer Part Lifecycle Status, and Sites (if it appears) fields to select the values you want to use.
14. Click Finish to run and display the report.

If you checked the Use BI Publisher checkbox, you are prompted to download the report in the format you selected.

Report layout fields	Description
Item attributes	
Level	The BOM level, for example, 0, 1, 2, or 3.
For each item listed in the report, item fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed item's Title Block , Page Two , or BOM tabs. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .
Manufacturer part attributes	


Report layout fields	Description
Under each listed item, manufacturer part information specified in the selected layout	<p>Depending on the layout, the manufacturer part information under each item can include any attributes from the listed item's Manufacturers tab, attributes from the manufacturer part's General Info tab, and attributes from the manufacturer's General Info tab.</p> <p>For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i>.</p>

Where Used Report


The Where Used report shows where the specified component or subassembly is used, up to the specified number of levels. It can show just the highest level of the assembly, all levels, or any number of levels in between.

Note An item will be selected for the report only if the specified component or subassembly is included in the BOM of the item's latest released revision.


To run the Where Used report:

1. Select the Where Used report in the Products Reports folder. The Where Used Report page appears.
2. Click the  Execute button. The Select Layout and Configuration page appears.

Note If the Agile administrator has enabled the use of Oracle Business Intelligence Publisher (report publisher), you see a checkbox labeled Use BI Publisher.
3. To select a layout when *not* using BI Publisher (the Use BI Publisher checkbox is not visible or the Use BI Publisher checkbox is unchecked):
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Click Next.
4. To use BI Publisher, check the Use BI Publisher checkbox and continue as follows:
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Select a report output format: PDF, WORD, EXCEL, or HTML.
 - c. Click the Save the Report checkbox to automatically save a copy of the report in the selected format on the Historical Reports tab.
 - d. Click Next.
5. Select the items you want to include in the report. Click Add to open the Add Items wizard. You can then select Search or Advanced Search to find items, or locate them using saved searches or shortcuts (My Bookmarks list or Recently Visited list). Select the items you want in the Search Results window; the selected items appear in the Selected Items list. Click OK to close the wizard.
6. Specify the depth, or number of levels in the BOM, you want to include. Specify the item types

by clicking the  button and selecting from the list.

The Only End Items checkbox determines which items that contain the specified item are included in the report. In a Where Used report on Item P0003 below, selecting the checkbox causes only P0001 to be included, while clearing the checkbox causes P0001 and P0002 to be included.



7. Click Finish to run and display the report.

If you checked the Use BI Publisher checkbox, you are prompted to download the report in the format you selected.

Default fields	Description
Level	The BOM level, for example, 0, 1, 2, or 3.
Item fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed item's Title Block , Page Two , or BOM tabs. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .

Agile Process Reports

The Agile Process reports provide information about changes and transfer orders. The Process Reports node folder under Standard Reports in the navigation pane lists the following reports:


Report	Displays...
Change process reports	
Change Activity Report (on page 174)	The Change Activity report shows the changes that were processed during a specified period of time.
Change Backlog Report (on page 175)	The Change Backlog report counts the changes that were at a specified status but have not moved to another specified status during a time period.
Change Cycle Time Report (on page 177)	The Change Cycle Time report calculates the time it took the specified changes to move from one status to another during the specified period. For example, the report indicates the average time it took for a change to go from Submitted to Released each month during the last year, grouped by product line.

Report	Displays...
Change Metrics Report (on page 178)	The Change Metrics report counts the changes that were moved to a specified status during a specified period.
Change Package Report (on page 179)	You can print the Change Package report to view the information about a change in an easy-to-read format.
IP Transfer reports	
IP Transfer Report (on page 181)	The IP Transfer report show the objects sent (by Agile transfer orders) to a given destination and when they were sent. (Requires the Agile Content Service server license.)

Change Activity Report

The Change Activity report shows the changes that were processed during a specified period of time. You choose which workflow to include in the report (for example, Default Change Orders or All Change Workflows). You also choose which status transitions to include in the report. For example, if you select Default Change Orders workflow and Released status type, the reports lists all the changes orders that used the Default Change Orders workflow and that moved into the Released type status during the specified time period.


To run the Change Activity report:

1. Select the Change Activity report in the Process Reports folder. The Change Activity Report page appears.
2. Click the  Execute button. The Select Layout and Configuration page appears.

Note	If the Agile administrator has enabled the use of Oracle Business Intelligence Publisher (report publisher), you see a checkbox labeled Use BI Publisher.
------	---

3. To select a layout when *not* using BI Publisher (the Use BI Publisher checkbox is not visible or the Use BI Publisher checkbox is unchecked):
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Click Next.
4. To use BI Publisher, check the Use BI Publisher checkbox and continue as follows:
 - a. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting Started with Agile PLM*.
 - b. Select a report output format: PDF, WORD, EXCEL, or HTML.
 - c. Click the Save the Report checkbox to automatically save a copy of the report in the selected format on the Historical Reports tab.
 - d. Click Next.

Note To run this report for price change orders, select a layout that applies to price change orders. (The Agile-provided default layouts are Default Layout for Change and Default Layout for PCO.) If you create new layouts for this report, you can choose a Layout Type: either Changes or Price Change Orders. Make sure the name you choose for the new layout indicates whether the layout applies to changes or price change orders.

5. Specify the start and end dates of the period to be covered by the report. Click Next.
 6. Select the workflow from the drop-down list. Click  button next to the Status Changes field, and select the statuses to be included from the Available Values list.
-

Note If you select All Change Workflows, the status types are listed in the Status Changes selection dialog; this allows you to select status types that apply to all workflows (for example, Released status type). However, if you select a specific workflow (for example, All Change Orders) the specific status names that apply to that workflow are listed in the Status Changes selection dialog.

7. Click Finish to display the report.

If you checked the Use BI Publisher checkbox, you are prompted to download the report in the format you selected.

Report layout fields	Description
Main Header attributes	
Status	Status based on the Status Changes selections in wizard.
Status Date	Date the change entered the selected status.
For each change listed in the report, change object fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed change's Cover Page or Page Two tabs. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .
Affected Item attributes	
Under each change object status transition row, item information from the change's Affected Items tab, as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed change's Affected Items tab. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .


Change Backlog Report

The Change Backlog report counts the changes that were at a specified status but have not moved to another specified status during a time period.

Note The option to use Oracle Business Intelligence Publisher (BI Publisher) is not available with this report.

To run the Change Backlog report:

1. Select the Change Backlog report in the Process Reports folder. The Change Backlog Report page appears.

- Click the  Execute button. The Select Layout and Configuration page appears. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting started With Agile PLM*. Click Next.

Note	To run this report for price change orders, select a layout that applies to price change orders. (The Agile-provided default layouts are Default Layout for Change and Default Layout for PCO.) If you create new layouts for this report, you can choose a Layout Type: either Changes or Price Change Orders. Make sure the name you choose for the new layout indicates whether the layout applies to changes or price change orders.
------	--

- Click Saved Search if you want to use a search from the list of available searches. Click Advanced Search to create a new query. Or you can select All Changes to include all changes. Click Next.
- Specify the other settings for the report:

- The time period covered
- The workflow
- The starting status (to include changes that were in this status or moved into this status during the specified time period) and ending status (to include changes that have *not yet* moved into this status during the specified time period)

For example, if you select starting status = Pending and ending status = Released, the report will count changes that were either in the Pending status or moved into the Pending status during the specified time period, but these changes have *not* moved into the Released status. The changes might be in a Submit type or Review type status, but they have not moved through the workflow to the Released status.

- The time unit used in the report
- The way to group data to evaluate trends

Select the checkboxes if you want to display the changes or price change orders and exclude empty columns.

- Click Finish to display the report.

Report layout fields	Description
Main Header attributes	
Days since Submitted	Number of days since the change entered the Submit type status.
Days at current status	Number of days the change has been at the current status.
Hold Date	Date the change entered the Hold type status.
Submit Date	Date the change entered the Submit type status
For each change listed in the report, change object fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed change's Cover Page or Page Two tabs. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .
Affected Item attributes	


Report layout fields	Description
Under each change object status transition row, item information from the change's Affected Items tab, as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed change's Affected Items tab. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .

Change Cycle Time Report

The Change Cycle Time report calculates the time it took the specified changes to move from one status to another during the specified period. For example, the report indicates the average time (in days) it took for a change to go from Submitted to Released each week during the last year, grouped by product line.

Note The option to use Oracle Business Intelligence Publisher (BI Publisher) is not available with this report.

To run the Change Cycle Time report:

1. Select the Change Cycle Time report in the Process Reports folder. The Change Cycle Time Report page appears.
2. Click the  Execute button. The Select Layout and Configuration page appears. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting started With Agile PLM*. Click Next.

Note To run this report for price change orders, select a layout that applies to price change orders. (The Agile-provided default layouts are Default Layout for Change and Default Layout for PCO.) If you create new layouts for this report, you can choose a Layout Type: either Changes or Price Change Orders. Make sure the name you choose for the new layout indicates whether the layout applies to changes or price change orders.

3. Click Saved Search if you want to use a search from the list of available searches. Click Advanced Search to create a new query. Or you can select All Changes to include all changes. Click Next.
4. Specify the other settings for the report:
 - The time period covered
 - The workflow
 - The starting status (to include changes that were in this status or moved into this status during the specified time period) and ending status (to include changes that moved into this status during the specified time period)
 - The time units used in the report
 - The way to group data to evaluate trends

Select the checkboxes if you want to display the changes or price change orders and exclude empty columns.
5. Click Finish to display the report.


Default fields	Description
Main Header attributes	
Days since Submitted	Number of days since the change entered the Submit type status.
Days at current status	Number of days the change has been at the current status.
Enter Status Date	Date the change entered the starting status selected in the report wiz
End Status Date	Date the change entered the ending status selected in the report wizard.
Number Days	The number of days between the Enter Status Date and the End Status Date.
For each change listed in the report, change object fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed change's Cover Page or Page Two tabs. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .
Affected Item attributes	
Under each change object row, item information from the change's Affected Items tab, as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed change's Affected Items tab. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .

Change Metrics Report

The Change Metrics report counts the changes that were moved to a specified status during a specified period.

Note	The option to use Oracle Business Intelligence Publisher (BI Publisher) is not available with this report.
------	--

To run the Change Metrics report:

1. Select the Change Metrics report in the Process Reports folder. The Change Metrics Report page appears.
2. Click the  Execute button. The Select Layout and Configuration page appears. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting started With Agile PLM*. Click Next.

Note	To run this report for price change orders, select a layout that applies to price change orders. (The Agile-provided default layouts are Default Layout for Change and Default Layout for PCO.) If you create new layouts for this report, you can choose a Layout Type: either Changes or Price Change Orders. Make sure the name you choose for the new layout indicates whether the layout applies to changes or price change orders.
------	--

3. Click **Saved Search** if you want to use a search from the list of available searches. Click **Advanced Search** to create a new query. Or you can select **All Changes** to include all changes. Click **Next**.
4. Specify the other settings for the report:
 - The time period covered
 - The workflow
 - The status type (to include changes that moved into this status type during the specified time period)
 - The time unit used in the report
 - The way to group data to evaluate trends

Select the checkboxes if you want to display the changes or price change orders and exclude empty columns.

5. Click **Finish** to display the report.


Report layout fields	Description
Main Header attributes	
Date	Date the change entered the status you selected in the report wizard.
For each change listed in the report, change object fields as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed change's Cover Page or Page Two tabs. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .
Affected Item attributes	
Under each change object row, item information from the change's Affected Items tab, as specified in the selected layout	Depending on the layout, the report can include any attributes from the listed change's Affected Items tab. For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i> .

Change Package Report



You can print the Change Package report to view the information about a change in an easy-to-read format.

Note The option to use Oracle Business Intelligence Publisher (BI Publisher) is not available with this report.

To run the Change Package report:

1. Select the Change Package report in the Process Reports folder. The Change Package Report page appears.
2. Click the  **Execute** button. The Select Layout and Configuration page appears. Select the layout you want from the drop-down list, or use the Layout Manager to create a new layout. For more detailed information about layouts, see the Working with Agile Reports chapter in *Getting started With Agile PLM*. Click **Next**.

Note Agile PLM supplies a default layout for each change type. If you create new layouts for this report, you can choose a Layout Type. The layout type can be for all changes in a particular class (for example, change orders) or the layout type can be for a specific type of subclass of change (for example, ECOs). For ease of use, make sure the name you choose for the new layout indicates the selected layout type.

3. Select the items you want to include in the report. Click Add to open the Add Items wizard. You can then select Search or Advanced Search to find items, or locate them using saved searches or shortcuts (My Bookmarks list or Recently Visited list). Select the items you want in the Search Results window; the selected items appear in the Selected Items list. Click OK to close the wizard. Click Next.
4. Click  next to the Tables field to specify the tables to include in the report. Click  next to the Sites field to specify sites to include.
5. Click Finish to display the report.

Report layout pages and fields	Description
Cover Page Affected Items Workflow Attachments History	<p>Tabs of the change object that can be included in the report layout. Depending on the layout, the report can include any attributes from the change's tabs.</p> <p>For detailed information about layouts, see the Working with Agile Reports chapter in <i>Getting started With Agile PLM</i>.</p> <p>All Change Package layouts can include these tabs. Some change types can include additional information, as explained below.</p>
Affected Items.BOM	<p>Lists the BOM redlines that appear on the change's affected item Redline BOM tab. Depending on the layout, the report can include any attributes from this tab.</p> <p>Available for change orders and site change orders only.</p>
Affected Items.Manufacturers	<p>Lists the manufacturer redlines that appear on the change's affected item Redline Manufacturers tab. Depending on the layout, the report can include any attributes from this tab.</p> <p>Available for change orders, site change orders, and manufacturer orders only.</p>
Affected Items.Attachments	<p>Lists the attachments that appear on the change's affected item Redline Folder tab: the list of attachments for the pending revision of the item. Depending on the layout, the report can include any attributes from this tab.</p> <p>Available for change orders only.</p>

IP Transfer Report

Note For information about Agile Content Service (ACS) and transfer orders, see the chapter about ACS settings in *Administrator Guide* and see *Agile Content Service User Guide*.

This report shows the objects sent by transfer orders to a given destination and when they were sent.

For details about running this report, see the Working with Transfer Orders chapter of *Agile Content Service User Guide*.

Help For Power Users

This chapter includes the following:

▪ Details about Discovery and Read Privileges	183
▪ Part or Document?	184
▪ Changing an Item's Subclass	185
▪ About Matching Criteria in Workflows	186
▪ Details About Revision Display on BOMs	187
▪ Quick Access to Agile Objects using Smart Object URLs	189

Details about Discovery and Read Privileges

Note For more information about the discovery warning messages, see the chapter about SmartRules in the *Administrator Guide*.

The Agile administrator can use the Discovery privilege to limit discovery of objects in the following ways:

- Prevent a set of users from seeing certain objects when they run a search. These objects are not displayed on the results table, even though they meet the search criteria. The Agile administrator can specify whether or not to display a warning message on the search results page.
- Prevent a set of users from seeing certain objects that are listed on these tables:
- Affected items
 - Where used
 - Manufacturers
 - Changes
 - Sites
 - User address book

The Agile administrator can specify whether to display a warning message.

- Prevent a set of users from seeing certain objects on the BOM tab. The Agile administrator specifies whether or not to display a warning message. The Agile administrator also has the option of displaying either the item number only or the item description only on the BOM tab, so the user can see a complete BOM, but does not have access to the undiscovered items.
- Prevent a set of users from running reports.

Note that while one set of users is prevented from seeing certain objects or fields, other users with different Discovery privilege and Read privilege settings can see those same objects and fields.

The creator of an object is always able to read and discover the object he created, even when he

has not been granted Discovery privilege for that object.

Discovery and Read privileges are assigned by the Agile administrator. If you have questions about your Discovery privileges or Read privileges, see the Agile administrator.

Displaying Non-viewable Fields

Note	The Agile administrator can create Read privilege masks that limit your ability to read specific fields. The Enforce Field Level Read privilege determines whether or not the Read privilege mask is enforced at the field level. If you have a role that includes the Enforce Field Level Read privilege, you may not be able to view the contents of specific fields. This section describes how those non-viewable fields are displayed. For more information, see the <i>Administrator Guide</i> .
------	--

If you do not have the appropriate Read privilege for a field, the words No Privilege appear in the field.

If a copy of a non-readable field appears in another object or in a table, the words No Privilege appear there also. For example, if you do not have Read privilege for the Description field of changes, when those changes are listed in a table, the words No Privilege also appear in the Description field of that table. Following are examples of tables where objects may be listed:

- Search results
- Change history
- Manufacturers
- Where used
- Affected items
- Audit results

On the BOM table only, the SmartRule that determines how non-discovered items are displayed on the BOM table is also applied to the non-readable fields. See [How the Agile Administrator Controls What You See](#) (on page 78).

Part or Document?

In general, if the document is shipped as part of a product, or it has costs associated with it, create it as a part object. If the document is an internal document, procedure, or reference, create it as a document object.

In certain cases, though, you may want to create a document as a part. Here are three examples illustrating when you might choose to create a document as a part object or as a document object.

Example 1: If a document is the controlling document for a part (that is, it has the same number as the part), create that document as a part object.

For example, if you have an engineering drawing number 123 that specifies and describes part number 123 (thus the document controls the part), create part 123 and include the engineering drawing as an attachment.

Use this method if the part number *must* be the same as the document number. Note that the

document does not exist as a separate document object in the Agile PLM database.

In contrast to the above example, if it is *not* necessary for the drawing number and part number to be the same, create a document object (for example, document number 222) and add the engineering drawing to its Attachments tab (reference the engineering drawing in the appropriate file folder object). Then create a part object (for example, part 444). Add document 222 to the BOM tab of part 444 and enter zero or REF as the quantity. Enter zero as the find number; this forces a document object to appear at the top of the BOM tab for easy reference.

Example 2: If the document has costs associated with it, or it is shipped as part of a product, create it as a part object.

An example of a document that is shipped with a product is a manual. A manual might have a BOM that includes the binder, labels for the binder, binder tabs, and the printed document itself.

If a document goes to your customer with a product, create it as a part object, even if it does not have a BOM. Examples of such a document might be a warranty card, an instruction booklet, assembly instructions, or a printed software licensing agreement.

If the document has costs associated with it, such as printing costs, create it as a part object. When you add the document part to a BOM tab, and you enter a quantity of 1, the costs of the document part object are included in any reports that compute costs. (See *Getting Started with Agile PLM* for information about running reports.)

Example 3: If the following applies to a document, create it as a document object:

- It does not need to have the same number as a part.
- It is not shipped as part of a product.
- It does not have costs associated with it.

Examples of such documents might be a manufacturing process (a Quality Assurance procedure, a test procedure, or manufacturing instructions) or a reference document (a specification or an engineering drawing).

Create any internal company documents as document objects.

Note Because Agile PLM is so flexible, you are not required or forced to use the approach outlined in these examples when creating documents. You should, however, always follow your company's policies or guidelines when creating a document as a part object or as a document object. If you have questions, see the Agile administrator.

If you create a document object, and later want to change it to a part object, you can hard-delete the document object (if you have the appropriate privileges), which removes it from the database and frees up the item number. Then you can create the document as a part object, using the same item number. For more information, see [Deleting Agile Objects](#) (on page 23).

Changing an Item's Subclass

If the Agile administrator has created additional subclasses, and you have the appropriate privileges, you can change the subclass of an item. For example, you can change the subclass of a particular document from Specification to Data Sheet.

Note When you change the subclass of an item, its data fields change, and all previous information about the Page Three tab is cleared.

To change the subclass of an item:

1. On the Title Block tab of the part, select a new subclass from the Part Type drop-down list.
2. If Page Three is visible and has data, a warning message appears, alerting you that all Page Three data is cleared.
 - Click Yes (Java Client) or OK (Web Client) to continue changing the subclass and to allow Page Three to be cleared.
 - Click No (Java Client) or Cancel (Web Client) to cancel the change subclass process; no changes are made to the item. In the object screen or window, click Cancel to discard your modifications and exit the edit mode.
3. If the new subclass has an autonumber scheme assigned by the Agile administrator, Agile PLM asks you if you want to select a new autonumber for the new subclass.
 - Click Yes (Java Client) or OK (Web Client) to change the subclass but retain the existing number.

If the new subclass either does not have an autonumber scheme assigned to it or does not require an autonumber, the process is completed; the subclass is changed but the number is not changed.
 - Click No (Java Client) or Cancel (Web Client) to reject the existing number. Manually select or enter a number, then click Save in the object page or window.
4. If you reject the existing number in the step above, you must manually select a new number. Depending on your system configuration, do one of the following:
 - If there is one autonumber source designated for the new subclass, click the Autonumber button to assign a new autonumber. Click Save in the object window or page to complete the process.
 - If an autonumber is not required, you can type in a number. Click Save in the object window or page to complete the process.
 - If autonumbering is required in your system, and more than one autonumber source is designated for the new subclass, use the Autonumber button to select one of the autonumber sources. Click Save in the object window or page to complete the process.

Note If the item is in use, you may see a dialog box alerting you that the item is locked. Click OK; the change subclass process is canceled.

5. Agile PLM displays the new number in the Number field, and enters the event on the History tab of the item.

About Matching Criteria in Workflows

Matching criteria are used to find which workflows may be used for each change. Agile PLM matches each change to a list of valid workflows for that change.

The Agile administrator selects matching criteria from a list of reusable criteria. A reusable criteria is a database query, just like an advanced search. Reusable criteria are named and defined by the Agile administrator.

Some examples of possible reusable criteria are:

- All MECOs – finds all the changes that are MECOs (mechanical ECOs).
- Scorpio ECOs – finds all the ECOs that include “Scorpio” in the Product Line(s) field of the change.
- Libra Project – finds all the change orders that have any items on the Affected Items tab that contain “Libra” in the Product Line(s) field of the item.

By specifying a list of reusable criteria for each workflow, the Agile administrator limits which changes can use a specific workflow. For example, the Agile administrator might create a workflow named General Use, and select the three reusable criteria named above (All MECOs, Scorpio ECOs, and Libra Project) as the matching criteria for that workflow.

Example 1: If you create a change that is a Mechanical ECO (MECO), it matches one of the matching criteria of the General Use workflow (All MECOs). The General Use workflow appears in the Workflow drop-down list on the Cover Page tab of the change.

Example 2: If you create a change that is an ECO that includes “Scorpio” in the Product Line(s) field of the ECO, it matches one of the matching criteria of the General Use workflow (Scorpio ECOs). The General Use workflow appears in the Workflow drop-down list on the Cover Page tab of the change.

Example 3: If you create a change order and add items to its Affected Items tab that contain “Libra” in the Product Line(s) field, Agile PLM examines the Product Line(s) field on the Affected Items tab for every affected item. The General Use workflow appears in the Workflow drop-down list on the Cover Page tab of the change depending on the Criteria Matching Type setting for the workflow:

- Some – One or more (but not all) affected items must match the affected item–based reusable criteria, in this case, Libra Project.
- All – When multiple affected item–based reusable criteria are used as matching criteria, each affected item must match at least one affected item–based reusable criteria; however, each affected item does not have to match the same reusable criteria.
- Same – All affected items must match the same affected item–based reusable criteria, in this case, Libra Project.

Note As you add items to the Affected Items tab and complete the fields on the tabs of the change, the Workflow drop-down list on the Cover Page tab may vary, depending on which matching criteria apply at the moment. Contact the Agile administrator if you have questions about the matching criteria of a specific workflow.

In Java Client, when editing a change object, click the Refresh button to save and update the change object and display the correct list of workflows in the Workflow drop-down list.

In Web Client, when editing the Cover Page tab, click the Validate button to save and update the change object and display the correct list of workflows in the Workflow drop-down list.

The Criteria Matching Type setting also applies for each status in the workflow. For detailed information about workflows and Criteria Matching Type, see the *Administrator Guide*.

Details About Revision Display on BOMs

Agile PLM calculates the revision number (or letter) that appears in the Rev field of the BOM table is by checking the release date of the parent item, if already released, then locating the latest revision

of the child item prior to that date and analyzing it. If the parent item hasn't been released, the most recent revision of the child item is found.

The child item revision is analyzed according to three criteria:

- Its lifecycle phase (Preliminary or other)
- Whether there are any released revisions of the child item
- Whether there are no released revisions of the child item

Note	In Agile PLM, if there are no released revisions of an item (the item has never been released), the Introductory revision is considered the latest revision, regardless of whether or not there are pending revisions of the never-released item. See Introductory Revisions (on page 13).
------	--


Depending on which revision of the parent you select, the child revision displayed may or may not be the latest revision of that child item. The following is an explanation of which child revision appears:

- The latest revision of the parent item always displays the latest revision of the child item. This means that the parent BOM reflects any changes that may be made to the child item since the parent revision was released. This applies until the next revision of the parent is released.
- The rev shown for a child item of any past revision of the parent item is the latest revision as of the time just preceding the next parent revision.
- For each child item, the lifecycle phase appears that corresponds to the displayed revision.

The child item may display a blank Rev field if it has no revision number as of the release of the parent revision. This occurs:

- If the child item has never been released as of the present moment, if you are viewing the latest parent revision, or
- If it had not been released by the time of the next occurring parent revision, if you are viewing past parent item revisions.

Caution Be aware that the unrelease and release of child items may affect the child revisions displayed on the parent BOM.

Note	Pending revisions of the child item are not displayed on the parent item BOM table. However, any child item that has a pending change is indicated by the  icon in its row in the parent item BOM table.
------	--

The change order (ECO) or manufacturer change order (MCO) number associated with the displayed revision is included in the Item Rev column of the BOM table. The ECO number is the ECO that released the displayed revision. An MCO number is displayed with the revision upon which it is based.

Site change orders (SCO) are based on ECO-released revisions and the revision displayed on the BOM table may include SCO-defined content, however, SCO numbers are not displayed on the BOM table.

For more information about item revisions, see [Working with Item Revisions](#) (on page 13).

Quick Access to Agile Objects using Smart Object URLs

You can generate quick access URLs that provide direct pointers to either Agile objects or to Agile attachment files.

These quick access URLs can be pasted into other applications or files such as spreadsheet files, word processing files, a company Intranet web page or WIKI page, or into an email.

This section includes the topics:

- [Agile-Generated Quick Access Object URLs](#) (on page 189)
- [Formats for User-Generated Smart Object URLs](#) (on page 189)
- [Using Quick Access Object URLs](#) (on page 190)

For information about quick access to attachment files using attachment quick access URLs, see *Getting Started with Agile PLM*.

Agile-Generated Quick Access Object URLs

From Web Client, you can generate Agile PLM object quick access URLs from the Web Client Actions menu.

To generate an Agile PLM object quick access URL:

1. Login to Agile PLM Web Client and open the desired object.
2. In the Actions menu, choose Copy URL to Clipboard.
3. The URL is copied to your clip board. You can then paste it into another application or file, such as a word processing file, a spreadsheet file, or an email.

Formats for User-Generated Smart Object URLs

The Agile Smart Object URL feature is designed to enable effective collaboration through email, spreadsheets, documents, WIKIs, and so forth. Users or automated tools can generate smart readable URLs that point to a specific object in Agile. By using the following format, a user does not need to log into Agile to generate the object URL. Automated tools can also use this format to generate object URLs.

Smart Object URLs can be used for objects available from Web Client.

Smart Object URL Format

URLs for pointing to Agile objects use the following format:

<http://server:port/VirtualPath/object/ObjectType/ObjectName>

The following table defines the Smart Object URL parameters:

Parameter	Description
<a href="http://server:port/<VirtualPath>/object/<ObjectType>/<ObjectName>">http://server:port/<VirtualPath>/object/<ObjectType>/<ObjectName>	
server port VirtualPath	Server, port, and VirtualPath identify the Agile PLM instance.
object	The text "object" indicates to Agile that the URL is an object URL.
ObjectType	ObjectType refers to the subclass (type) of object, for example, ECO, Part, Manufacturer, File Folder, Program, Activity, or Discussion.
ObjectName	<p>ObjectName refers to the unique identifier for the object. Depending on the object class, the unique identifier is either an object number or a name.</p> <p>Note Manufacturer Parts are a special class of objects that are uniquely identified by two parameters: a Manufacturer Name and a Manufacturer Part Number. Therefore, a URL referring to a specific Manufacturer Part uses the following format:</p> <p>http://server:port/VirtualPath/object/ObjectType/MfrName/MfrPart Number</p>

Agile PLM identifies and handles special tags (such as %20) added to URLs to handle special characters (such as spaces and other special characters such as asterisk "**") in an object's unique identifier. For example, the URL

<http://server:port/VirtualPath/object/Manufacturer/Philips%20Semiconductor>

resolves to the manufacturer "Philips Semiconductor".

Using Quick Access Object URLs

When a user clicks a Quick Access Object URL, the user actions are the same whether the URL is an Agile-generated quick access URL or a user-generated Smart Object URL:

1. The user clicks the URL and the Agile PLM login screen is displayed in a browser window.
2. The user enters her login information.
3. Upon successful login, Agile PLM searches for the object specified in the link.

(If the object is not found, Agile PLM displays an error and returns to the user's Home page.)

When the object is found, Agile PLM verifies that the user has the appropriate privileges to read the object and displays the object's first tab, for example, the Title Page.